

## **SECTION 00 02 00 - NOTICE TO BIDDERS**

### **NOTICE TO BIDDERS**

Notice is hereby given that sealed bids will be received:

By: School City of Hammond and  
Hammond Multi-School Building Corporation  
41 Williams Street  
Hammond, IN 46320

For: School City of Hammond - Hammond Central High School - Bid Package 3 -  
Athletic Fields and Building Demolition  
5926 Calumet Avenue  
Hammond, IN 46320

At: School City of Hammond and  
Hammond Multi-School Building Corporation  
41 Williams Street  
Hammond, IN 46320

Until: 10:00 AM (local time), March 24, 2021

Bid Opening: Bids will be publicly opened and read aloud at 10:00 AM (local time), in the  
**School City of Hammond Administration Center and Hammond Multi  
School Building Corporation, 41 Williams Street Hammond, IN 46320**

**Via Microsoft Teams:**

**Join on your computer or mobile app**

[Click here to join the meeting](#)

**Or call in (audio only)**

[+1 317-762-3960,,215874118#](#) United States, Indianapolis

Phone Conference ID: 215 874 118#

All work for the complete construction of the Project will be under one or more Prime Contracts with the Owner based on bids received and on combinations awarded. The Construction Manager will manage the construction of the Project.

Construction shall be in full accordance with the Bidding Documents which are on file with the Owner and may be examined by prospective bidders at the following locations:

Office of the Construction Manager  
The Skillman Corporation  
8006 Aetna Street  
Merrillville, IN 46410

The Skillman Plan Room

[www.skillmanplanroom.com](http://www.skillmanplanroom.com)

Prime and Non-Prime Contract Bidders must place an order on [www.skillmanplanroom.com](http://www.skillmanplanroom.com) to be able to download documents electronically or request printed documents. There is no cost for downloading the bidding documents. Bidders desiring printed documents shall pay for the cost of printing, shipping, and handling. Reprographic Services are provided by:

**Reprographic Arts, 2824 E. Michigan Blvd., Michigan City, IN 46360, Phone (219) 872-9111**

A Pre-Bid Conference will be held on **March 4, 2021 at 1:30 PM, local time**, at 5926 Calumet Avenue Hammond, IN 46320. All attendees shall enter thru the south elevation at Door B of the existing High School. Attendance by bidders is optional, but recommended, in order to clarify or answer questions concerning the Drawings and Project Manual for the Project.

**Via Microsoft Teams:**

**Join on your computer or mobile app**

[Click here to join the meeting](#)

**Or call in (audio only)**

[+1 317-762-3960,,538338799#](#) United States, Indianapolis

Phone Conference ID: 538 338 799#

Bid security in the amount of ten percent (10%) of the Bid must accompany each Bid in accordance with the Instructions to Bidders.

The successful Bidders will be required to furnish Performance and Payment Bonds for one hundred percent (100%) of their Contract amount prior to execution of Contracts.

Contractors submitting bids for the performance of any Work as specified in this building Project should make such Bids to **School City of Hammond and Hammond Multi-School Building Corporation**. Contractors are advised that the Contract as finally entered into with any successful Bidder may be entered into with either the School Corporation or the Building Corporation or certain portions of the Contract may be entered into by both the School Corporation and the Building Corporation.

The Owner reserves the right to accept or reject any Bid (or combination of Bids) and to waive any irregularities in bidding. All Bids may be held for a period not to exceed **60** days before awarding contracts.

**School City of Hammond**  
By: Mr. Scott Miller, Superintendent

END OF SECTION 00 02 00

## **SECTION 01 12 00 - MULTIPLE CONTRACT SUMMARY**

### **PART 1 - GENERAL**

#### **1.01 RELATED DOCUMENTS**

- A. Drawings and General Provisions of the Prime Contract, including amended General Conditions and other Division 1 Specification Sections, apply to Work of this Section.

#### **1.02 SUMMARY**

- A. The intent of this Section is to indicate the Work required by the Contractors and to provide information regarding the duties, responsibilities, and cooperation required by the Contractors, with similar requirements for the subcontractors and suppliers.
- B. Owners right to maintain current operations
- C. Occupancy requirements
- D. Work by Owner
- E. Permits, fees, and notices
- F. Labor and materials
- G. Verifications of existing dimensions
- H. Project security
- I. Coordination of work
- J. Time of commencement and completion
- K. Schedule of contract responsibilities

#### **1.03 WORK UNDER SEPARATE CONTRACTS**

- A. Prime Contracts are defined to include the following contracts described in the Schedule of Contract Responsibilities included hereinafter; and each is recognized to be a major part of the project, with Work to be performed concurrently and in close coordination with Work of other Prime Contracts.
- B. The "Contract Documents," as defined in the General Conditions, include "the Drawings." Although Drawings are grouped and identified by classification of the Work, Contractors shall be responsible for their Work as specified herein and as

indicated on the Drawings. Although the majority of the Drawings are "to scale," Contractors are directed to use indicated dimensions for determining material quantities and for other reasons. No additional monies will be allowed due to Contractors using "scaling instruments" to determine material quantities or for other reasons.

- C. Separate prime contracts will be awarded as per the **"Schedule of Contract Responsibilities"** (see Part 3 – Execution). Contractors shall include Work required by the Specifications and Drawings for each contract area defined in the Schedule.
- D. Work for the complete construction of the Project will be under multiple prime contracts with the Owner. The Construction Manager will manage the construction of the Project.
- E. Each Contractor shall be responsible for demolition and disposal of existing items relative to his Contract.

#### **1.04 ADMINISTRATIVE RESPONSIBILITIES OF PRIME CONTRACTORS AND CM**

- A. The Construction Manager shall be responsible for the maintenance of the Construction Schedule and management of every phase of the Work.
  - 1. Each Contractor shall read the Specifications and Drawings for other separate Contracts for fixed equipment and the like to be incorporated or attached or built into the Work; and familiarize himself with the requirements and responsibilities of other Contracts to enable the required coordination and supervision.
  - 2. Each Contractor shall also familiarize himself with other items to be incorporated into the Work including equipment and Work by the Owner.
  - 3. Each Contractor shall cooperate with the Construction Manager in notifying him when the Work is at a stage to require the services of other Contractors and shall notify the Construction Manager in the event that such other Contractors do not carry out their responsibilities in connection with such notification.
- B. Contractors shall cooperate with and assist the Construction Manager in the preparation of construction progress and procedures, schedule of product deliveries, and their effect on the overall project progress and completion. Other Contractors shall cooperate in getting their Work and the Work of their subcontractors completed according to the schedule as prepared and maintained by the Construction Manager. Each Contractor shall immediately notify the Construction Manager of a delay in delivery of products or the scheduled date of completion that may affect the total progress of construction.
- C. The Owner will furnish the topographical survey, either as a part of these Drawings or separately, giving the general topographical lines existing at the site and the property lines.

- D. Contractors required to make connections to existing utilities, especially sewerage where gravity flow occurs, shall verify grades and locations at points of such connections and shall notify the Construction Manager of circumstances which would adversely affect the proper flow or connection to such facilities.

#### **1.05 PRIME CONTRACTORS USE OF PREMISES**

- A. Use of the Site: Limit use of the premises to work in areas indicated. Confine operations to areas within contract limits indicated. Do not disturb portions of the site beyond the areas in which the Work is indicated.
  - 1. Owner Occupancy: Allow for Owner occupancy and use by the public.
  - 2. Driveways and Entrances: Keep driveways and entrances serving the premises clear and available to the Owner, the Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on site.

#### **1.06 OWNERS RIGHT TO MAINTAIN OPERATIONS**

- A. During the course of this Project, normal and customary functions and operations must be maintained. The Contract Documents are intended to define a strict separation between the school activities of students and staff from the activities of the construction project.
- B. The Construction Manager, Architect, and Owner will not tolerate any visible or audible actions initiated or responded to by any employees of Contractors on this Project toward any students, teachers, or staff members at the school system. Violators shall be promptly removed from the site.
- C. The Owner intends to instruct students, teachers, and staff to refrain from communications with Contractor's personnel working on this Project. All communication with Owner and staff shall be through the Construction Manager.
- D. Contractors must expend their best effort toward protection of the health, safety, and welfare of occupants on the Owner's property during the course of Work on this Project.

#### **1.07 OCCUPANCY REQUIREMENTS**

- A. Full Owner Occupancy: The Owner will occupy the site and existing building during the entire construction period. Cooperate with the Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with the Owner's operations.

## **1.08 WORK BY OWNER**

- A. The Owner intends to complete the following items of Work outside the provisions of these Contract Documents. Contractors shall not restrict or interfere with the Owner's right to the Project to accomplish this Work.
  - 1. Equipment and furniture except as scheduled and specified under Divisions 11 and 12 and shown on the Drawings.
  - 2. Items which may be deleted from Contracts for Work as required by the Contract Documents.
  - 3. Existing school maintenance work.
  - 4. The purchase and supplying of certain materials as noted in the Project Manual.

## **1.09 PERMITS, FEES, AND NOTICES**

- A. The **Bid Category No. 3 Contractor** shall pay and secure the permits for the Athletic Buildings only. **The Bid Category No. 1, 2, 4, and 5 Contractors** shall secure and pay for other permits including site improvement, building demolition, governmental fees, and licenses necessary for the proper execution and completion of his Work, which are applicable at the time the bids are also received. Fees to relocate utilities on Owner's property shall be included in the bid of the Contractor doing the relocation.
  - 1. State filing fees for plan approval are the responsibility of the Owner and will be paid by the Owner.
- B. Utility Tie-Ins: Shall be arranged with local utility company and other involved parties for minimum interruption of service.
- C. Shutdowns of existing systems shall be limited to minimum time required and scheduled with other involved parties. Provide 2 days written notice of shutdown to Construction Manager and Owner.
- D. Inspections of installed work shall be performed by the governing authority as arranged for by the Contractor. Work shall not be covered until approved.
- E. Each Contractor shall give notices and comply with laws, ordinances, rules, regulations, and orders of public authorities bearing on the performance of his Work. If a Contractor observes that the Contract Documents are at variance therewith, he shall promptly notify the Construction Manager in writing, and necessary changes shall be adjusted by appropriate notification. If a Contractor performs Work knowing it to be contrary to such laws, ordinances, rules, and regulations, and without such notice to the Construction Manager, he shall assume full responsibility therefore and shall bear the costs attributable thereto.

## **1.10 LABOR AND MATERIALS**

- A. Unless otherwise specifically noted, the Contractor shall provide and pay for labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation, and other facilities and services necessary for the proper execution and completion of his Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.
- B. Each Contractor shall enforce strict discipline and good order among his employees or other persons carrying out Work of his Contract and shall not permit employment of unfit person or persons or anyone not skilled in the task assigned to them.
- C. Contractors and Subcontractors shall be subject to such rules and regulations for the conduct of the Work as the Owner may establish. Employees shall be properly and completely clothed while working. Bare torsos, legs and feet will not be allowed. Possession or consumption of alcoholic beverages or drugs, tobacco or other noxious behavior on the site is strictly prohibited. Violators shall be promptly removed from the site. Smoking is not permitted on school property or within school buildings.
- D. Contractors will conduct criminal background checks (extent of and/or service to be used will be established by the Owner) on every employee assigned to work on the Project and clear them through the National Sex Offender Registry prior to their assignment to Project. Contractors will require the same of sub-contractors. ID Badges will be issued by The Skillman Corporation upon receipt of verification from the Contractor that the employee/subcontractor employee or independent contractor has a satisfactory record to work on the Project.
- E. E-Verify Compliance: Pursuant to I.C. 22-5-1.7, Contractor shall enroll in and verify the work eligibility status of all newly hired employees of Contractor through the E-Verify Program (Program). Contractor is not required to verify the work eligibility status of all newly hired employees through the Program if the Program no longer exists. Also pursuant to I.C. 22-5-1.7, Contractor must execute an affidavit affirming that the Contractor does not knowingly employ an unauthorized alien and confirming Contractor's enrollment in the Program, unless the Program no longer exists, shall be filed with the Owner prior to the execution of this contract. This contract shall not be deemed fully executed until such affidavit is delivered to the Owner.

Contractor and its subcontractors shall not knowingly employ or contract with an unauthorized alien or retain an employee or contract with a person that contractor or its subcontractor subsequently learns is an unauthorized alien. If Contractor violates this provision the Owner shall require Contractor to remedy the violation not later than thirty (30) days after the Owner notifies Contractor. If Contractor fails to remedy the violation within the thirty (30) day period, the Owner shall terminate the contract for breach of contract. If Owner terminates the contract, Contractor shall be liable to the Owner for actual damages in addition to any other

contractual remedies. There is a rebuttable presumption that Contractor did not knowingly employ an unauthorized alien if Contractor verified the work eligibility status of the employee through the Program.

Prior to performing any work, Contractor shall require each subcontractor to certify to Contractor that the subcontractor does not knowingly employ or contract with an unauthorized alien and has enrolled in the Program. Contractor shall maintain on file a certification from each subcontractor throughout the duration of this contract or project which is the subject of this contract. If Contractor determines that a subcontractor is in violation of this provision, Contractor may terminate its contract with the subcontractor for such violation. In Accordance with I.C. 5-16-13 Contractor must provide the E-Verify Case Number of every employee that works on the project. This requirement includes the contractor's subs and suppliers to the fourth (4<sup>th</sup>) tier.

- F. The Owner is requiring that all contractors' personnel and their onsite employees (trade employees) and subcontractors submit an expanded criminal history check through SafeVendor, a product of Safe Hiring Solutions. Please visit [www.safevisitorsolutions.com/safevendor-app-agreement](http://www.safevisitorsolutions.com/safevendor-app-agreement) to create your account with SafeVendor. (Contractor is responsible for the cost of this background check). This should meet with the Owner's approval prior to the employee starting work on the project. All contractors' personnel and employees once cleared for work will be issued a project identification badge that must be worn at all times while on site. All contractors will be expected to provide the required name, address, picture state driver's license or picture state identification card information to The Skillman Corporation Site Manager no later than 24 hours in advance of the employee coming to work at the project site.
- H. Pursuant to Indiana Code 5-16-13 Requirements for Contractors on Public Works Projects enacted by the Indiana Legislator requires, in addition to requirements already in effect, contractors to comply with the following:
1. Tier 1 –General/Prime Contractors to self-perform 15% of their total Contract.
  2. Qualification thru the Department of Administration or INDOT requirement in accordance with IC 4-13.6-4.
    - a. **Bids shall not be considered unless (1) the Prime Bidder and (2) all lower tiered subcontractors whose subcontract value is estimated to be \$300,000 or more are qualified at the time of the bid in accordance with IC 4 – 13.6 – 4.**
  3. Include Written Drug Testing Plan that covers all employees of the bidder who will perform work on the public work project and meets or exceeds the requirements set in IC 4-13-18-5 or IC 4-13-18-6 with Bid.
  4. Minimum Insurance Requirements \$1M/occurrence \$2M/aggregate. However, check your bidding requirements as the Owners may have higher limit requirements.



5. Mandatory enrollment in E-Verify by all contractors down to the 4th Tier Sub Contracts and must provide the case verification number of all employees working on the project.
  6. Prohibits contractors down to the 4th Tier Sub Contract from paying employees in cash.
  7. Requirement to retain payroll records for 3 years
  8. All contractors down to the 4th Tier Sub Contract must comply with Fair Labor Act, Indiana's Workers Compensation and Unemployment Compensation Insurance.
  9. Mandatory Training Requirements based upon number of employees.
  10. Failure to comply may result in debarment from public works projects for up to 4 years.
- I. All contractors down to the 4<sup>th</sup> Tier Sub Contract must maintain general liability insurance in at least the following amounts: Each Occurrence Limit of \$1,000,000 and General Aggregate Limit of \$2,000,000. Other requirements and limits may apply see specification section 00 08 20 Schedule of Insurance Requirements.

#### **1.11 CUTTING AND PATCHING**

- A. Refer to Section 01 73 10 – Cutting and Patching, for provisions on this subject.

#### **1.12 VERIFICATIONS OF EXISTING DIMENSIONS**

- A. When verification of existing dimensions is required, the Contractor requiring said verification for the construction or fabrication of his material shall be the Contractor responsible for the procurement of the field information.

#### **1.13 PROJECT SECURITY**

- A. Each Prime Contractor shall take all reasonable precautions to prevent injury, damage or loss to people and property in, on and adjacent to the project. This shall include not only their own work or property but that of other contractors and the Owner.
- B. If deemed necessary by The Construction Manager a project wide security program may be developed for the purpose of preventing damage or loss at the project site or property adjacent thereto. Once accepted by the Owner, contractors shall comply.

#### **1.14 SCHEDULE OF CONTRACT RESPONSIBILITIES - SCOPE**

- A. Contractors shall submit their proposals based on the work included under each contract area as listed herein. Include Work necessary for a complete project, as shown on the Drawings and called for in the Specifications.

- B. Questions concerning the phasing, or "Schedule of Contract Responsibilities" should be directed to the Construction Manager, who will be the interpreter and be responsible for this Schedule of Contract Responsibilities and Contract Breakdown, prior to submitting proposals and during construction.
- C. The requirements of Division 1 are a part of the Work of each and every contract area. The Contractor for any one contract area shall be familiar with the Work and requirements of all other contract areas.
- D. Certain Specification Sections describe Work to be performed under several contract areas. (Example: 06 10 00 - Rough Carpentry.) Provide Work of this nature as required for each contract area whether or not enumerated in the Schedule of Contract Responsibilities.
- E. The following contract areas are broken down by Specifications Section conforming basically to the CSI format.
- F. The Drawings and Specifications as furnished for each of the Contracts is for the convenience of the Contractor in preparing a proposal for this Project. However, each Contractor is responsible to review the complete set of Drawings and Specifications to assure that Work required to be installed to complete his phase of the Work is included in his proposal. This "Schedule of Contract Responsibilities" is a definition of the work as it is to be bid in separate contracts. Where a specific item of Work is not defined, but is normally inherent to a trade, or is included in the scope of the applicable technical revision, it will be the responsibility of that Contractor to include the Work in his proposal.
- G. This "Schedule of Contract Responsibilities" is to aid each Contractor in defining the Scope of Work to be included in his proposal. However, omissions from this "Schedule of Responsibilities" do not relieve the Contractor from including in his proposal that Work which will be required to complete his Contract. Each Contractor should read the "Schedule of Contract Responsibilities" completely to familiarize himself with the Work of other Contractors that may have Work in adjacent areas and to coordinate the interfacing problems that may occur as the work is assembled and constructed.
- H. Where specific Work is to be completed under a particular phase of the Project and the Work is wholly or partially completed by other trades because of the type of work involved or jurisdictional trade agreements, the Contractor will be responsible to subcontract the Work as necessary to complete the Work included in his Contract. No delay in the Work will be allowed due to the failure of the Contractor to subcontract related work required by jurisdictional trade agreements.

## **1.15 COORDINATION OF WORK**

- A. Each Contractor is responsible to coordinate his Work with the Work of other trades and other Contractors and requirements of the school system. The Contractor must make space allowances for Work of other Contractors; provide necessary openings

where indicated or implied by the Drawings and Specifications. Each Contractor is responsible to protect his own Work.

## **1.16 TIME OF COMMENCEMENT AND COMPLETION**

- A. The Contractor shall commence work within ten (10) days after being notified in writing to proceed and shall complete the Work within the time limitations established in the Form of Agreement.
1. It is anticipated that construction will start within **15** calendar days after receipt of bids.
  2. Construction shall be complete within **402** consecutive calendar days, or earlier, after Notice to Proceed.

## **PART 2 - PRODUCTS** (Not Used)

## **PART 3 - EXECUTION**

### **3.01 SCHEDULE OF CONTRACT RESPONSIBILITIES**

### **3.02 GENERAL REQUIREMENTS**

A. PROVIDED BY OWNER THROUGH THE CONSTRUCTION MANAGER

Section	01 32 00	Schedules and Reports
Section	01 45 10	Testing Laboratory Services
Section	01 71 50	Final Cleaning

B. PROVIDED BY ALL CONTRACTORS AS APPLICABLE

Section	01 12 00	Multiple Contract Summary
Section	01 21 00	Allowances
Section	01 23 00	Alternates
Section	01 25 00	Contract Modification Procedures
Section	01 28 00	Schedule of Values
Section	01 29 00	Applications for Payment
Section	01 31 00	Project Meetings
Section	01 32 00	Schedules and Reports
Section	01 33 00	Submittal Procedures
Section	01 40 00	Quality Requirements
Section	01 45 10	Testing Laboratory Services (Paragraph 1.05)
Section	01 50 50	Temporary Facilities and Controls
Section	01 54 60	Environment Protection
Section	01 54 80	Utility Protection
Section	01 56 30	Water Control
Section	01 56 90	Housekeeping & Safety
Section	01 59 20	Offices and Sheds
Section	01 60 00	Product Requirements
Section	01 72 50	Work Layout

Section	01 73 10	Cutting and Patching
Section	01 77 00	Contract Closeout

All Contractors shall provide their Superintendents with radios capable of handling multiple channels and compatible with radios used by the Construction Manager.

All contractors shall subscribe to PlanGrid for use on this project. Number of users is up to the contractor, however, at a minimum your site personnel will be required to use this product to facilitate communication. PlanGrid will be used for the current construction documentation to include, current set, addenda, ASI, As Built Conditions, QA/QC, and Punch List. Visit the [www.PlanGrid.com](http://www.PlanGrid.com) to determine subscription pricing. It is recommended that you have an office administrator to assist your field personnel. PlanGrid is a tool for the construction phase and will not be used for bidding. Visit [www.skillmanplanroom.com](http://www.skillmanplanroom.com) for bid documents

C. **PROVIDED BY DESIGNATED CONTRACTORS**

Section	01 51 10	Temporary Electric, Lighting, and Warning
Section	01 51 50	Temporary Water
Section	01 51 60	Temporary Sanitary Facilities
Section	01 51 80	Temporary Fire Protection
Section	01 52 60	Rubbish Container
Section	01 53 10	Fences (Temporary Security)
Section	01 53 20	Tree and Plant Protection
Section	01 56 20	Dust Control
Section	01 56 80	Erosion Control
Section	01 57 60	Project Signs
Section	01 72 00	Field Engineering

### 3.03 **BID CATEGORIES**

A. **BID CATEGORY NO. 1 - BUILDING DEMOLITION AND ENVIRONMENTAL REMOVAL**

General Requirements in Paragraph 3.02.B above.

Section	01 52 60	Rubbish Container
Section	01 56 20	Dust Control
Section	01 53 20	Tree and Plant Protection
Section	02 41 16	Structure Demolition (As Applicable)
Section	07 92 00	Joint Sealants (As Applicable)
Section	31 10 00	Site Clearing (As Applicable)
Section	31 50 00	Excavation Support and Protection (As Applicable)

Clarification No. 1:

The **Bid Category No. 2 Contractor** is responsible to remove any dirt and mud that is tracked on public roadways on a daily basis. The **Bid Category No. 1 Contractor** is also responsible to remove any dirt and mud that is tracked on public roadways on a daily basis for their work only.

Clarification No. 2:

The **Bid Category No. 1 Contractor** shall establish a subbase elevation of 590.00' once the building is demolished and engineered fill is placed. This will be the elevation at which the **Bid Category No. 2 Contractor** shall start to perform their work for parking lot construction.

Clarification No. 3:

The **Bid Category No. 1 Contractor** is responsible for backfilling after the building demolition and shall utilize the existing 9,000 CY of engineered fill onsite. This material is located at the northwest corner of Eaton St. and Sohl Ave. The remaining engineered fill needed for the demolition backfill, shall be figured as base bid. Any excess of this material shall be removed by the **Bid Category No. 1 Contractor**.

Clarification No. 4:

Regarding Specification Section 02 41 16 - Building Demolition; The **Bid Category No. 1 Contractor** shall ensure that all building materials and/or site structures, existing utilities onsite, and existing asphalt shall be removed as indicated in the Contract Documents on sheet CD101.3. All utilities shall be removed to the nearest main disconnect or valve. Coordinate all utilities with the City of Hammond Public Works, Engineer Department, and all Public Utilities for gas, electrical, and water. The **Bid Category No. 1 Contractor** shall also be responsible to follow the City of Hammond building demolition requirements. The **Bid Category No. 2 Contractor** is responsible for coordinating all other utility disconnects outside the scope of the main building demolition. The **Bid Category No. 2 Contractor** is also responsible for all other demolition/removal for site improvements as indicated in the Contract Documents on sheets CD102.3 and 103.3.

Clarification No. 5:

The **Bid Category No. 1 Contractor** is responsible to remove and safely store/crate the Class of 1924 Limestone Bench and Urn along with removing and disposing of the existing foundations associated with these items. The **Bid Category No. 1 Contractor** is responsible to remove the existing High School cornerstone as indicated on the Contract Documents and return to Owner. The **Bid Category No. 3 Contractor** is responsible to provide the new foundations and final location of these two items as indicated on the Contract Documents.

Clarification No. 6:

The **Bid Category No. 1 Contractor** is responsible to secure the building demolition work with perimeter fencing. The fencing shall be 6' high chain link with two (2) gates and locks. Fabric to be 9 ga. galvanized wire mesh. The fencing shall be in place until the building demolition has been completely backfilled. All other fencing shall be the responsibility of the **Bid Category No. 3 Contractor**.

Clarification No. 7:

Private utilities locate will be required. The **Bid Category No. 1 Contractor** is to include in their bid, any costs associated to have a private utility locate company identify all utilities on the site outside the public utility boundaries within the main building demolition only. The **Bid Category No. 2 Contractor** is responsible for all other private utility locates.

B. BID CATEGORY NO. 2 - SITEWORK/UTILITIES/PAVING

General Requirements in Paragraph 3.02.B above.

Section	01 52 60	Rubbish Container
Section	01 53 10	Fences (Temporary Security)
Section	01 53 20	Tree and Plant Protection
Section	01 56 20	Dust Control
Section	01 56 80	Erosion Control
Section	01 72 00	Field Engineering
Section	02 41 16	Structure Demolition (As Applicable)
Section	03 30 00	Cast-In-Place Concrete (As Applicable)
Section	04 22 00	Concrete Unit Masonry
Section	07 92 00	Joint Sealants (As Applicable)
Section	10 14 53.99	Traffic Signage
Section	11 68 23.99	Site Athletic Equipment
Section	22 11 13	Facility Water Distribution Piping (Site)
Section	22 13 13	Facility Sanitary Sewers (Site)
Section	31 10 00	Site Clearing (As Applicable)
Section	31 20 00	Earth Moving (As Applicable)
Section	31 50 00	Excavation Support and Protection (As Applicable)
Section	32 12 16	Asphalt Paving
Section	32 13 13	Concrete Paving (As Applicable)
Section	32 13 73	Concrete Paving Joint Sealants (As Applicable)
Section	32 18 23.33	Running Track Surfacing
Section	32 18 23.99	Synthetic Turf Playing Surface
Section	32 31 13	Chain Link Fences and Gates
Section	32 31 21	Commercial Architectural Privacy Fence
Section	32 92 00	Turf and Grasses
Section	32 92 19.99	Athletic Field Seeding
Section	32 92 28.99	Porous Stone Base and Drainage System for Synthetic Turf Playing Surface
Section	33 41 00	Storm Utility Drainage Piping
Section	33 46 00	Subdrainage
Section	33 46 23.99	Aluminized Type II Corrugated Metal Pipe Underground Detention and Infiltration System

Clarification No. 1:

The **Bid Category No. 2 Contractor** is responsible to provide and implement the SWPPP, and all associated items within the erosion control plan. The **Bid Category No. 2 Contractor** shall be responsible to maintain their own concrete washout area. The **Bid Category No. 3 Contractor** is responsible to provide, maintain, and dispose of the concrete washout area for their own work.

Clarification No. 2:

The **Bid Category No. 1 Contractor** shall establish a subbase elevation of 590.00' once the building is demolished and engineered fill is placed. This will be the elevation at which the **Bid Category No. 2 Contractor** shall start to perform their work for parking lot construction.

Clarification No. 3:

Soil investigation indicates unsuitable bearing materials at various building footprint locations and onsite. Column and wall footings are to bear on allowable soil pressure as indicated in the Contract Documents. Where this capacity cannot be achieved, the **Bid Category No. 2 Contractor** is responsible to remove 3,000 CY of soils (hauled off site) and replaced with engineered fill. At the end of the project, unexcavated yardages will be converted into a dollar amount and included as a deduct Change Order. This quantitative amount shall be a line item on the Schedule of Values and tracked on a monthly basis.

Clarification No. 4:

The **Bid Category No. 2 Contractor** is to include in his bid, small tools, and a total of 80 man-hours at a union laborer's pay rate (including all fringe benefits and payroll expenses) for work to be performed at the direction of the Construction Manager. At the end of the project, unused hours will be converted into a dollar amount per Wage Scale (including fringe benefits) and included as a deduct Change Order.

Clarification No. 5:

The **Bid Category No. 2 Contractor** is responsible to remove any dirt and mud that is tracked on public roadways on a daily basis. The **Bid Category No. 1** is also responsible to remove any dirt and mud that is tracked on public roadways on a daily basis for their work only.

Clarification No. 6:

Regarding Specification Section 03 30 00 – Cast in Place Concrete; The **Bid Category No. 2 Contractor** shall provide the perimeter concrete around the track in its entirety along with the concrete associated for specification section 11 68 23.99 – Site Athletic Equipment. Concrete equipment pads and housekeeping pads shown or required for plumbing/HVAC, and electrical equipment is the responsibility of the contractor installing or providing the equipment. Concrete for light pole bases along with the Scoreboard/Time Clock are to be provided by the **Bid Category No. 5 Contractor**. The **Bid Category No. 3 Contractors** shall provide all other concrete within the 03 30 00 specification section.

Clarification No. 7:

The **Bid Category No. 2 and Bid Category No. 4 Contractors** are responsible for the excavation and backfilling of their associated underground utility work in accordance with the Contract Documents.

Clarification No. 8:

Regarding Specification Section 07 92 00 - Joint Sealants; contractors are to provide caulking in accordance with the Contract Documents. In general, the Contractor whose work creates a joint that requires caulking (in the normal sequence of work) is to provide the caulking.

Clarification No. 9:

Private utilities locate will be required. The **Bid Category No. 1 Contractor** is to include in their bid, any costs associated to have a private utility locate company identify all utilities on the site outside the public utility boundaries within the main building demolition only. The **Bid Category No. 2 Contractor** is responsible for all other private utility locates.

Clarification No. 10:

The **Bid Category No. 2 Contractor** is to provide all underground utilities (sanitary sewer, storm sewer, water lines, etc.) to within 5'- 0" of the building perimeter. The **Bid Category No. 4 Contractors** are to provide cleanouts and make final connections for the undergrounds. The **Bid Category No. 3 Contractors** shall provide all final downspout connections.

Clarification No. 11:

Regarding Specification 01 72 00 - Field Engineering, **Bid Category No. 2 Contractor** shall provide Field Engineering required for work on the Site Drawings. The **Bid Category No. 3 Contractor** shall provide Field Engineering for the Athletic Buildings and at the exterior perimeter required for all work shown on Foundation and Structural Drawings including the Certified Survey.

Clarification No. 12:

The **Bid Category No. 1 Contractor** is responsible to remove and safely store/crate the Class of 1924 Limestone Bench and Urn along with removing and disposing of the existing associated foundations with these items. The **Bid Category No. 3 Contractor** is responsible to provide the new foundations and final location of these two items as indicated on the Contract Documents.

Clarification No. 13:

Regarding Specification Section 02 41 16 - Building Demolition; The **Bid Category No. 1 Contractor** shall ensure that all building materials and/or site structures, existing utilities onsite, and existing asphalt shall be removed as indicated in the Contract Documents on sheet CD101.3. All utilities shall be removed to the nearest main disconnect or valve. Coordinate all utilities with the City of Hammond Public Works, Engineer Department, and all Public Utilities for gas, electrical and water. The **Bid Category No. 1 Contractor** shall also be responsible to follow the City of Hammond building demolition requirements. The **Bid Category No. 2 Contractor** is responsible for coordinating all other utility disconnects outside the scope of the main building demolition. The **Bid Category No. 2 Contractor** is also responsible for all other demolition/removal for site improvements as indicated in the Contract Documents on sheets CD102.3 and 103.3.

Clarification No. 14:

Regarding Specification 32 18 23.99 - Synthetic Turf Playing Surface; all shop drawings, product data and color sample submittals are to be completed and submitted for review by April 19, 2021 or sooner.



Clarification No. 15:

The **Bid Category No. 2 Contractor** shall utilize the existing 650 ton of IN No.53 slag stone material for their use on the project. This material is located within the contract documents on sheet CD 101.3. If the material cannot be utilized, the **Bid Category No. 2 Contractor** shall remove offsite. The **Bid Category No. 2 Contractor** shall remove the existing aluminum bleachers and press box located on the southeast corner of Sohl Ave. and Eaton St.

Clarification No. 16:

Regarding Specification Section 01 56 80 - Erosion Control; The **Bid Category No. 2 Contractor** is responsible to prepare and submit a complete Notice of Intent Letter (and pay NOI letter fees) to IDEM. The **Bid Category No. 2 Contractor** is also responsible for the SWPPP as indicated on the Contract Documents including site inspection and the maintenance log.

Clarification No. 17:

Regarding Specification Section 32 13 13 - Concrete Paving, and Specification Section 32 13 73 - Concrete Paving Joint Sealants; The **Bid Category No. 2 Contractor** is responsible to provide the concrete curbs and gutters at the new east elevation parking lot. The **Bid Category No. 3 Contractor** is responsible to provide all other Concrete Paving items along with the aggregate base.

Clarification No. 18:

The **Bid Category No. 2 and Bid Category No. 3 Contractor** are responsible to provide dewatering as required to perform their respective scopes of work without causing delays to the overall schedule.

C. BID CATEGORY NO. 3 - GENERAL TRADES

General Requirements in Paragraph 3.02.B above.

Section	01 51 60	Temporary Sanitary Facilities
Section	01 51 80	Temporary Fire Protection
Section	01 52 60	Rubbish Container
Section	01 53 10	Fences (Temporary Security)
Section	01 57 60	Project Signs
Section	01 72 00	Field Engineering
Section	03 30 00	Cast-In-Place Concrete (As Applicable)
Section	05 12 00	Structural Steel Framing
Section	05 51 00	Metal Stairs
Section	05 52 13	Pipe and Tube Railings
Section	06 10 00	Rough Carpentry
Section	06 10 53	Miscellaneous Rough Carpentry
Section	06 16 00	Sheathing
Section	06 17 53	Shop-Fabricated Wood Trusses
Section	07 21 00	Thermal Insulation
Section	07 24 13.99	Direct-Applied Exterior Finish System
Section	07 24 19	Water-Drainage Exterior Insulation (EIFS)
Section	07 31 13	Asphalt Shingles
Section	07 41 13.16	Standing-Seam Metal Roof Panels
Section	07 42 13.13	Formed Metal Wall Panels
Section	07 54 23	Thermoplastic Polyolefin (TPO) Roofing
Section	07 71 00	Roof Specialties
Section	07 92 00	Joint Sealants (As Applicable)
Section	08 11 13	Hollow Metal Doors and Frames
Section	08 31 13	Access Doors and Frames (As Applicable)
Section	08 33 13	Coiling Counter Doors
Section	08 51 13	Aluminum Windows
Section	08 71 00	Door Hardware
Section	08 80 00	Glazing
Section	09 65 13	Resilient Base and Accessories
Section	09 65 19	Resilient Tile Flooring
Section	09 67 23.13	Resinous Flooring - Level 1
Section	09 96 00.99	High Performance Coatings
Section	10 11 00	Visual Display Units
Section	10 14 00	Signage
Section	10 21 13.19	Plastic Toilet Compartments
Section	10 28 00	Toilet, Bath, and Laundry Accessories
Section	10 51 13	Metal Lockers
Section	10 75 00	Flagpoles
Section	31 20 00	Earth Moving (As Applicable)
Section	32 13 13	Concrete Paving (As Applicable)
Section	32 13 73	Concrete Paving Joint Sealants (As Applicable)
Section	32 14 00	Unit Paving
Section	32 80 00	Irrigation
Section	32 93 00	Plants

Clarification No. 1:

The **Bid Category No. 2 Contractor** is responsible to provide and implement the SWPPP, and all associated items within the erosion control plan. The **Bid Category No. 2 Contractor** shall be responsible to maintain their own concrete washout area. The **Bid Category No. 3 Contractor** is responsible to provide, maintain, and dispose of the concrete washout area for their own work.

Clarification No. 2

The **Bid Category No. 2 Contractor** is to provide all underground utilities (sanitary sewer, storm sewer, water lines, etc.) to within 5'- 0" of the building perimeter. The **Bid Category No. 4 Contractors** are to provide cleanouts and make final connections for the undergrounds. The **Bid Category No. 3 Contractor** shall provide all final downspout connections.

Clarification No. 3:

Regarding Specification Section 07 92 00 - Joint Sealants; contractors are to provide caulking in accordance with the Contract Documents. In general, the Contractor whose work creates a joint that requires caulking (in the normal sequence of work) is to provide the caulking.

Clarification No. 4:

The **Bid Category No. 3 Contractor** is to include \$12,000 in their bid for costs associated with The submittal website and document management subscription. Any unused amount will be credited back to the Owner as a deductive Change Order.

Clarification No. 5

Regarding Specification Section 03 30 00 - Cast in Place Concrete; The **Bid Category No. 2 Contractor** shall provide the perimeter concrete around the track in its entirety along with the concrete associated for specification section 11 68 23.99 - Site Athletic Equipment. Concrete equipment pads and housekeeping pads shown or required for plumbing/HVAC, and electrical equipment is the responsibility of the contractor installing or providing the equipment. Concrete for light pole bases along with the Scoreboard/Time Clock are to be provided by the **Bid Category No. 5 Contractor**. The **Bid Category No. 3 Contractor** shall provide all other concrete within the 03 30 00 specification section.

Clarification No. 6:

The **Bid Category No. 3 Contractor** is responsible to provide any special requirements and grading to provide equipment access for lifts and lulls to perform their work.

Clarification No. 7:

The **Bid Category No. 1 Contractor** is to include in his bid, sweeping compound and 80 man-hours for general building and site clean-up (or other work) to be performed by a skilled laborer at the direction of the Construction Manager throughout the duration of the project. At the end of the project, unused hours will be converted into a dollar amount and returned to the Owner as a deduct Change Order.

Clarification No. 8:

Regarding Specification 01 72 00 - Field Engineering, **Bid Category No. 2 Contractor** shall provide Field Engineering required for work on the Site Drawings. The **Bid Category No. 3 Contractor** shall provide Field Engineering for the Athletic Buildings and at the exterior perimeter required for all work shown on Foundation and Structural Drawings including the Certified Survey.

Clarification No. 9:

Regarding Specification Section 08 31 13 - Access Doors and Frames; the **Bid Category No. 4 and No. 5** are responsible to coordinate their access doors and frames for installation purposes with the **Bid Category No. 3 Contractor**. All other access doors and frames included within this section is the responsibility of the **Bid Category No. 3 Contractor**.

Clarification No. 10:

The **Bid Category No. 2 Contractor** is responsible to provide and implement the SWPPP, and silt fencing per the erosion control plan. The **Bid Category No. 2 Contractor** shall be responsible to maintain their own concrete washout area. The **Bid Category No. 3 Contractor** is responsible to provide, maintain, and dispose of the concrete washout area for their own work.

Clarification No. 11:

The **Bid Category No. 2 and Bid Category No. 3 Contractor** are responsible to provide dewatering as required to perform their respective scopes of work without causing delays to the overall schedule.

Clarification No. 12:

The **Bid Category No. 1 Contractor** is responsible to remove and safely store/crate the Class of 1924 Limestone Bench and Urn along with removing and disposing of the existing foundations associated with these items. The **Bid Category No. 1 Contractor** is responsible to remove the existing High School cornerstone as indicated on the Contract Documents and return to Owner. The **Bid Category No. 3 Contractor** is responsible to provide the new foundations and final location of these two items as indicated on the Contract Documents.

Clarification No. 13:

Regarding Specification Section 32 13 13 - Concrete Paving, and Specification Section 32 13 73 - Concrete Paving Joint Sealants; The **Bid Category No. 2 Contractor** is responsible to provide the concrete curbs and gutters at the new east elevation parking lot. The **Bid Category No. 3 Contractor** is responsible to provide all other Concrete Paving items along with the aggregate base.

Clarification No. 14:

The **Bid Category No. 1 Contractor** is responsible to secure the building demolition work with perimeter fencing. The fencing shall be 6' high chain link with two (2) gates and locks. Fabric to be 9 ga. galvanized wire mesh. The fencing shall be in place until the building demolition has been completely backfilled. All other fencing shall be the responsibility of the **Bid Category No. 3 Contractor**.

D. BID CATEGORY NO. 4 - PLUMBING/HVAC

General Requirements in Paragraph 3.02.B above.

Section	01 51 50	Temporary Water
Section	03 30 00	Cast-In-Place Concrete (As Applicable)
Section	07 92 00	Joint Sealants (As Applicable)
Section	08 31 13	Access Doors and Frames (As Applicable)
Section	08 91 19	Fixed Louvers (As Applicable)
Section	22 05 00	Common Work Results for Plumbing
Section	22 05 19	Meters and Gages for Plumbing Piping
Section	22 05 23	General-Duty Valves for Plumbing Piping
Section	22 05 29	Hangers and Supports for Plumbing Piping and Equipment
Section	22 05 53	Identification for Plumbing Piping and Equipment
Section	22 07 00	Plumbing Insulation
Section	22 11 16	Domestic Water Piping
Section	22 11 19	Domestic Water Piping Specialties
Section	22 11 23	Domestic Water Pumps
Section	22 13 16	Sanitary Waste and Vent Piping
Section	22 13 19	Sanitary Waste Piping Specialties
Section	22 13 23	Separators
Section	22 33 00	Electric Water Heaters
Section	22 40 00	Plumbing Fixtures
Section	23 05 00	Common Work Results for HVAC
Section	23 05 13	Common Motor Requirements for HVAC Equipment
Section	23 05 29	Hangers and Supports for HVAC Piping and Equipment
Section	23 05 48	Vibration and Seismic Controls for HVAC Piping and Equipment
Section	23 05 53	Identification for HVAC Piping and Equipment
Section	23 05 93	Testing, Adjusting, and Balancing for HVAC
Section	23 09 00.99	Direct Digital Control Systems
Section	23 31 13	Metal Ducts
Section	23 33 00	Air Duct Accessories
Section	23 34 23	HVAC Power Ventilators
Section	23 37 13.99	Diffusers, Registers, and Grilles
Section	23 82 39.19	Wall and Ceiling Unit Heaters

Clarification No. 1:

Regarding Specification Section 07 92 00 - Joint Sealants; contractors are to provide caulking in accordance with the Contract Documents. In general, the Contractor whose work creates a joint that requires caulking (in the normal sequence of work) is to provide the caulking.

Clarification No. 2

The **Bid Category No. 2** and **Bid Category No. 4 Contractor** are responsible for the excavation and backfilling of their associated underground utility work in accordance with the Contract Documents.

Clarification No. 3:

The **Bid Category No. 2 Contractor** is to provide all underground utilities (sanitary sewer, storm sewer, water lines, etc.) to within 5'- 0" of the building perimeter. The **Bid Category No. 4 Contractor** are to provide cleanouts and make final connections for the undergrounds. The **Bid Category No. 3 Contractor** shall provide all final downspout connections.

Clarification No. 4:

Regarding Specification Section 03 30 00 - Cast in Place Concrete; The **Bid Category No. 2 Contractor** shall provide the perimeter concrete around the track in its entirety along with the concrete associated for specification section 11 68 23.99 - Site Athletic Equipment. Concrete equipment pads and housekeeping pads shown or required for plumbing/HVAC, and electrical equipment is the responsibility of the contractor installing or providing the equipment. Concrete for light pole bases along with the Scoreboard/Time Clock are to be provided by the **Bid Category No. 5 Contractor**. The **Bid Category No. 3 Contractor** shall provide all other concrete within the 03 30 00 specification section.

Clarification No. 5:

Regarding Specification Section 08 31 13 - Access Doors and Frames; the **Bid Category No. 4** and **No. 5** are responsible to coordinate their access doors and frames for installation purposes with the **Bid Category No. 3 Contractor**. All other access doors and frames included within this section is the responsibility of the **Bid Category No. 3 Contractor**.

E. BID CATEGORY NO. 5 - ELECTRICAL

General requirements in Paragraph 3.02.B above.

Section	01 51 10	Temporary Electric, Lighting, and Warning
Section	03 30 00	Cast-In-Place Concrete
Section	08 31 13	Access Doors and Frames (As Applicable)
Section	11 68 33.53	Track Timing System
Section	11 68 43.43	Scoreboards/Message Boards
Section	26 05 00	Common Work Results for Electrical
Section	26 05 19	Low-Voltage Electrical Power Conductors and Cables
Section	26 05 26	Grounding and Bonding for Electrical Systems
Section	26 05 29	Hangers and Supports for Electrical Systems
Section	26 05 33	Raceways and Boxes for Electrical Systems
Section	26 05 44	Sleeves and Sleeve Seals for Electrical Raceways and Cabling
Section	26 05 53	Identification for Electrical Systems
Section	26 05 74.99	Short-Circuit/Coordination Study/Arc Flash Risk Assessment
Section	26 09 23	Lighting Control Devices
Section	26 22 13	Low-Voltage Distribution Transformers
Section	26 24 16	Panelboards
Section	26 27 26	Wiring Devices
Section	26 28 13	Fuses
Section	16 28 16	Enclosed Switches and Circuit Breakers
Section	26 29 13	Enclosed Controllers
Section	26 43 13	Surge Protection for Low-Voltage Electrical Power Circuits
Section	26 51 19	LED Interior Lighting
Section	26 52 13	Emergency and Exit Lighting
Section	26 56 13	Lighting Poles and Standards
Section	26 56 19	LED Exterior Lighting
Section	26 56 68	Exterior Athletic Lighting
Section	27 05 28	Pathways for Communications Systems
Section	27 05 44	Sleeves and Sleeve Seals for Communications Pathways and Cabling
Section	27 11 00	Communications Equipment Room Fittings
Section	27 13 00	Communications Backbone Cabling
Section	27 15 13	Communications Copper Horizontal Cabling
Section	27 17 00.99	Telecommunications Grounding and Bonding
Section	27 17 50.99	Sound Reinforcement System (Football/Baseball/Softball)
Section	27 77 10.99	Audio/Video Systems
Section	28 13 00.99	Electronic Access Control System (ACS)
Section	28 23 00.99	Video Surveillance System (VSS)
Section	28 46 21	Addressable Fire-Alarm Systems

Clarification No. 1:

Regarding Specification Section 07 92 00 - Joint Sealants; contractors are to provide caulking in accordance with the Contract Documents. In general, the Contractor whose work creates a joint that requires caulking (in the normal sequence of work) is to provide the caulking.

Clarification No. 2:

Regarding Specification Section 03 30 00 – Cast in Place Concrete; The **Bid Category No. 2 Contractor** shall provide the perimeter concrete around the track in its entirety along with the concrete associated for specification section 11 68 23.99 - Site Athletic Equipment. Concrete equipment pads and housekeeping pads shown or required for plumbing/HVAC, and electrical equipment is the responsibility of the contractor installing or providing the equipment. Concrete for light pole bases along with the Scoreboard/Time Clock are to be provided by the **Bid Category No. 5 Contractor**. The **Bid Category No. 3 Contractor** shall provide all other concrete within the 03 30 00 specification section.

Clarification No. 3:

Regarding Specification Section 08 31 13 - Access Doors and Frames; the **Bid Category No. 4, and 5** are responsible to coordinate their access doors and frames for installation purposes with the **Bid Category No. 3 Contractor**. All other access doors and frames included within this section is the responsibility of the **Bid Category No. 3 Contractor**.

END OF SECTION 01 12 00