GROUND FLOOR PLAN - UNIT D - PLUMBING

SCALE: 1/8" = 1'-0"

NORTH

PLAN NOTES:

1. REFER TO SHEET P203 FOR CONTINUATION OF PIPING.
2. 1 1/2" WASTE DOWN. 1 1/2" VENT UP.
3. 3/4" HOT AND COLD WATER DOWN. 2" VENT FROM BELOW
4. 1/2" HOT AND COLD WATER DOWN, 1 1/2" WASTE DOWN. 1 1/2" VENT UP.
5. 1/2" COLD WATER DOWN, 2" WASTE DOWN. 1 1/2" VENT UP.
6. 2" COLD WATER, 4" WASTE DOWN. 2" VENT UP. 4" VENT THROUGH ROOF.
7. REFER TO SHEET P202 FOR CONTINUATION OF PIPING.
8. 6" STORM DOWN.
9. 4" STORM FROM ROOF DRAIN FROM ABOVE.
10. 4" STORM FROM OVERFLOW ROOF DRAIN FROM ABOVE.
11. 3/4" COLD WATER DOWN.
12. 3/4" HOT WATER, 1 1/2" COLD WATER DOWN.
13. 4" WASTE DOWN. 2" VENT UP.
14. 3/4" HOT AND COLD WATER DOWN. 1 1/2" VENT UP.
15. BALANCE VALVE 0.5 GPM

GENERAL NOTES:

1. REFER TO SHEET PM001 FOR ADDITIONAL GENERAL NOTES.



CARMEL CLAY SCHOOLS
CARMEL, INDIANA

CSO
8831 Keystone Crossing, Indianapolis, IN 46240
317.848.7600 | csoinc.net

© 2019 CSO Architects, Inc. All Rights Reserved

DA#19022

R.E. Dimond and Associates, Inc.
Consulting Engineers
7250 Naval Station Road
Indianapolis, IN 46214
Phone: (317) 634-4672 Fax: (317) 638-4725
Email: info@redimond.com

PROJECT:
NEW ELEMENTARY SCHOOL
FOR
CARMEL CLAY SCHOOLS
CARMEL, IN

SCOPE DRAWINGS:

These drawings indicate the general scope of the project in terms of architectural design concept, the dimensions of the building, the major architectural elements and the type of structural, mechanical and electrical systems.

The drawings do not necessarily indicate or describe all work required for the performance and completion of the requirements of the Contract.

On the basis of the general scope indicated or described, the trade contractors shall furnish all items required for the proper execution and completion of the work.

REVISIONS:

1	ADDENDUM #1	12-06-19

ISSUE DATE	DRAWN BY	CHECKED BY
11/19/19	AMB	GAC

DRAWING TITLE:
GROUND FLOOR PLAN - UNIT D - PLUMBING

CERTIFIED BY:
DANIEL E. DIMOND
REGISTERED
No. PE60910351
STATE OF INDIANA
PROFESSIONAL ENGINEER
11/19/2019

DRAWING NUMBER
P204

PROJECT NUMBER
18094