ADDENDUM NO. 2

December 19, 2019

Carmel Elementary School
Carmel, IN 46032

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications and the Drawings dated November 19, 2019, by CSO Architects. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Page ADD 2-1, CSO Architects Addendum 2, dated December 13, 2019, consisting of 3 pages, and S002CE – General Structural Notes & Schedules by LHB, S201CE – Foundation Plan – Unit A – CE by LHB, S202CE – Foundation Plan - Unit B –CE by LHB, S203 – Foundation Plan – Unit C by LHB, and A800 – Finished Legend And Notes – by CSO.

ADDENDUM

CSO
ARCHITECTURE · INTERIOR DESIGN

ADDENDUM NO: 2

BID PACKAGE NO: N/A

PROJECT: Carmel Clay Center Elementary School

PROJECT NO: 18094 DATE: 12/13/2019 BY: Brent Hite

JOHN E. RIGSBEE REGISTERED No. 920019 STATE OF INDIANA ARCHITECT

This Addendum is issued in accordance with the provisions of "The General Conditions of the Contract for Construction," Article 1, "Contract Documents" and becomes a part of the Contract Documents as provided therein. This Addendum includes:

Addendum Pages:
Attachments:
S002CE – GENERAL STRUCTURAL NOTES & SCHEDULES By LHB
S201CE – FOUNDATION PLAN – UNIT A – CE By LHB
S202CE – FOUNDATION PLAN - UNIT B –CE By LHB
S203 – FOUNDATION PLAN – UNIT C By LHB
A800 – FINISHED LEGEND AND NOTES – By CSO

PART 1 - BIDDING AND CONTRACT REQUIRMENTS

1.01 NOT USED

PART 2 - SPECIFICATIONS

2.01 08 41 13 – ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

A. Add 2.01A9 as follows:

9. Manko Window Systems

PART 3 - DRAWINGS

STRUCTURAL

3.01 S002CE – GENERAL STRUCTURAL NOTES & SCHEDULES

A. Revise COLUMN FOOTING SCHEDULE as shown on attached sheet.

B. Add CONCRETE GRADE BEAM SCHEDULE as shown on attached sheet.

3.02 S201CE – FOUNDATION PLAN – UNIT A – CE

A. Revise foundations in the vicinity of the existing sanitary line as shown on attached sheet.

B. Add foundation plan notes 18, 19 & 20 as shown on attached sheet.

8831 Keystone Crossing, Indianapolis, IN 46240 | 317.848.7800 | csoinc.net

3.03 S202CE – FOUNDATION PLAN – UNIT B – CE

A. Revise foundations in the vicinity of the existing sanitary line as shown on attached sheet.

B. Add foundation plan notes 18, 19 & 20 as shown on attached sheet.

3.04 S203 – FOUNDATION PLAN – UNIT C

A. Revise foundations in the vicinity of the existing sanitary line as shown on attached sheet.

B. Add foundation plan notes 18, 19 & 20 as shown on attached sheet.

MEP

3.05 DRAWING 100 – SITE PLAN – ELECTRICAL

A. CARMEL ELEM. EXTERIOR FIXTURE SCHEDULE

1. Add "CREE" as an Manufactruer Equal for the following fixtures:

   A. A.10, B.12, B.15, C.12, D.20, D.27, D.30, E.20 E.30, and F.27.

2. Add "DLC QUALIFIED" to Description to the following fixtures:

   A. B.12, B.15, C.12

3. Add "90 DEG FULL CUT OFF" to Description to the following fixtures:

   A. A.10, B.12, B.15, C.12, D.20, D.27, D.30, E.20, E.30, and F.27

ARCHITECTURAL

3.06 A203 – GROUND FLOOR PLAN UNIT - C

A. Add Plan note "**12**" as follows to the PLAN NOTE list: **"THIS WALL INSTALL A LAYER OF 5/8" FIRE RATED PLYWOOD BEHIND THE GYPSUM WALL BOARD, FULL WIDTH OF INDICATED WALL. PLYWOOD TO EXTEND SAME HEIGHT AS GYPSUM WALL BOARD, SEE INTERIOR DETAIL 16/A800 FOR MORE INFORMATION"**

B. Plan note "**12**" added in Corridor C105 pointing towards the wall between windows 140.4 and 140.5

3.07 A211-A214 – REFLECTED CEILING PLANS

A. Revise finish of ceiling type CL4 to read **"Constants Redux Wood Wheat"** in place of ~~"T.B.D."~~ in reflected ceiling legend.

B. Add **"Corridor C105"** under ceiling type CL4 location in reflected ceiling legend.

3.08 A800 – FINISH LEGEND & NOTES

A. Finish legend revisions made to the following tags as follows:

1. VW7 – VINYL WALLCOVERING

MFR:	MDC
STYLE:	ARTISAN
COLOR:	JAR7201 BLONDE ON BLONDE
MATERIAL:	TYPE II
BACKING:	OSNABURG
LOCATION:	OPERABLE PARTITION

2. WP2 – WOOD PLANK SYSTEM

MFR:	ARMSTRONG
STYLE:	WOODWORKS GRILLE / VERTICAL PLANKS
COLOR:	CONSTANTS REDUX WOOD WHEAT; BACKER TO MATCH EP1
SIZE:	3 ¼"D X ½"W X 9'-11"H PLANKS CONTINUOUS FROM TOP OF BASE TO MEET TEGULAR GRID, NO BREAK. *SPACED 1 1/8" O.C. & CENTERED ON WIDTH OF HORIZONTAL CEILING SLAT
LOCATION:	CORRIDOR C105
NOTE:	SEE 16/A800 FOR DETAIL

3. WP3 – NOT USED

B. Added section detail **16/A800 "WP2 ATTACHMENT"** to A800.

C. 6/A800 – Removed top leader from WP2 and changed title to read CORRIDOR C105 WOOD WALL-CE.

PART 4 - OTHER ITEMS

4.01 NOT USED

A. NOT USED

PART 5 - QUESTION AND ANSWER

5.01 NOT USED

A. NOT USED

END OF ADDENDUM