

# March 4, 2022

## TIMOTHY BALL ELEMENTARY SCHOOL ADDITIONS, RENOVATIONS, AND RELATED WORK Crown Point, IN 46307

# **TO: ALL BIDDERS OF RECORD**

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications, and the Drawings dated February 7, 2022 by Gibraltar Design. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 3-1 through ADD 3-3 and attached Addendum No. 3 from Gibraltar Design dated March 3, 2022 and consisting of 10 pages, Specification Section 12 56 57 - Media Shelving and Furniture, Specification Section 23 52 16 - Condensing Boilers, and 81 drawings.

## A. SPECIFICATION SECTION 00 00 20 - TABLE OF CONTENTS

## 1. Add:

Specification Section 12 56 57 - Media Shelving and Furniture Specification Section 23 52 16 - Condensing Boilers

## 2. Remove:

Specification Section 23 62 13 - Air Cooled Liquid Chiller

## B. <u>SPECIFICATION SECTION 01 12 00 - MULTIPLE CONTRACT SUMMARY</u>

## 1. BID CATEGORY NO. 1 - GENERAL TRADES

### 1. Replace:

Clarification No. 24:

Reference the AD Drawings; the **Bid Category No. 2 Contractor** shall provide all work indicated on Note 51. The **Bid Category No. 4 Contractor** shall provide all work indicated on Note 1. The **Bid Category No. 5 Contractor** shall provide all work indicated on Note 58. All other notes are the responsibility of the **Bid Category No. 1 Contractor** unless otherwise noted.

## 2. BID CATEGORY NO. 2 - MASONRY

## 1. Add:

Clarification No. 6:

The **Bid Category No. 2 Contractor** shall provide all work associated with toothing, tuck pointing, and infilling masonry as indicated on the contract documents.

## 1. Replace:

Clarification No. 6:

Reference the AD Drawings; the **Bid Category No. 2 Contractor** shall provide all work indicated on Note 51. The **Bid Category No. 4 Contractor** shall provide all work indicated on Note 1. The **Bid Category No. 5 Contractor** shall provide all work indicated on Note 58. All other notes are the responsibility of the **Bid Category No. 1 Contractor** unless otherwise noted.

## 3. BID CATEGORY NO. 3 - ROOFING

## 1. **Add:**

Clarification No. 8:

The **Bid Category No. 3 Contractor** shall provide all work associated with removal of metal panels referenced in Alternates 3 and 4.

## 4. BID CATEGORY NO. 4 - ALUMINUM ENTRANCES & STOREFRONTS

## 1. Replace:

Clarification No. 6:

Reference the AD Drawings; the **Bid Category No. 2** Contractor shall provide all work indicated on Note 51. The **Bid Category No. 4** Contractor shall provide all work indicated on Note 1. The **Bid Category No. 5** Contractor shall provide all work indicated on Note 58. All other notes are the responsibility of the **Bid Category No. 1** Contractor unless otherwise noted.

## 5. BID CATEGORY NO. 5 - METAL STUDS, DRYWALL, & CEILINGS

## 1. Add:

Clarification No. 6:

Reference the AD Drawings; the **Bid Category No. 2 Contractor** shall provide all work indicated on Note 51. The **Bid Category No. 4 Contractor** shall provide all work indicated on Note 1. The **Bid Category No. 5 Contractor** shall provide all work indicated on Note 58. All other notes are the responsibility of the **Bid Category No. 1 Contractor** unless otherwise noted.

## 6. BID CATEGORY NO. 9 - CASEWORK

1. Add:

Specification Section 12 56 57 - Media Shelving and Furniture

## 7. BID CATEGORY NO. 13 - MECHANICAL

1. Add:

Specification Section 23 52 16 - Condensing Boilers

2. Delete:

Specification Section 23 62 13 - Air Cooled Liquid Chiller

## C. <u>SPECIFICATION 01 32 00 - SCHEDULES AND REPORTS</u>

## 1. Replace:

The original guideline schedule with the attached revised guideline schedule.

ctivity Name	Original Duration	Start	Finish	2022 2023	
					v De
Timothy Ball ES Additions and R	601	Feb-10-22 A	Jun-28-24	Timothy Ball ES Additions and Renovations	
Project Administration	601	Feb-10-22 A	Jun-28-24	Project Administration	÷
Bid Phase	20	Feb-10-22 A	Mar-09-22	Bid Phase	
Pre-Bid Meeting	1	Feb-18-22 A	Feb-18-22 A	🕱 Pre-Bid Meeting	
Bid Opening	0		Mar-09-22	◆ Bid Opening	
Recommend/Award	1	Mar-21-22	Mar-21-22	X Recommend/Award	
Submittals and Color Charts	120	Mar-22-22	Sep-08-22	✓ Submittals and Color Charts	
Notice to Proceed	0	Mar-22-22		◆ Notice to Proceed	
Procure Mechanical Units	100	Apr-05-22	Aug-24-22	$\nabla$ Procure Mechanical Units	
Procure Structural Steel Framing, Joists, and De	120	Apr-19-22	Oct-06-22	✓ V Procure Structural Steel Framing, Joists, and Deck	
Start Construction	0	May-02-22		♦ Start Construction	
Last Student Day 2021/2022 School Year	0		Jun-02-22*	<ul> <li>Last Student Day 2021/2022 School Year</li> </ul>	
Last Staff Day 2021/2022 School Year	0		Jun-03-22*	<ul> <li>Last Staff Day 2021/2022 School Year</li> </ul>	
First Staff Day 2022/2023 School Year	0	Aug-08-22*		<ul> <li>◆ First Staff Day 2022/2023 School Year</li> </ul>	
First Student Day 2022/2023 School Year	0	Aug-10-22*		<ul> <li>♦ First Student Day 2022/2023 School Year</li> </ul>	
Fall Break 2022/2023 School Year	5	Oct-17-22*	Oct-21-22	✓ Filst Student Day 2022/2023 School Year	
Thanksgiving Break 2022/2023 School Year	2	Nov-23-22*	Nov-28-22	1	
Winter Break 2022/2023	9	Dec-21-22*	Jan-04-23	Thanksgiving Break 2022/2023 School Year	
Spring Break 2022/2023 School Year	5	Mar-27-23*	Mar-31-23	Winter Break 2022/2023	
Gym Addition Turnover	0		Mar-29-23	Spring Break 2022/2023 School Year	
Pre-K Addition Turnover	0		May-03-23		
Last Student Day 2022/2023 School Year	0		May-26-23*	Pre-K Addition Turnover	
Last Staff Day 2022/2023 School Year	0		May-30-23*	◆ Last Student Day 2022/2023 Sch	
Summer 2023	0	Jun-05-23*		◆ Last Staff Day 2022/2023 Schoo	rea
Kindergarten Addition Turnover	0		Jun-14-23	Summer 2023	
Classroom Addition Turnover	0		Jun-15-23	◆ Kindergarten Addition Turnove	<u>r</u>
Cafeteria Tumover	0		Aug-03-23	Classroom Addition Turnover	
First Staff Day 2023/2024 School Year		Aug-07-23*	,	◆ Cafeteria Tumover	
First Student Day 2023/2024 School Year		Aug-09-23*		♦ First Staff Day 2023	
Mechanical Tumover	0	, ag 00 20	Aug-14-23	◆ First Student Day 2	- i
Fall Break 2023/2024 School Year	-	Oct-16-23*	Oct-20-23	♦ Mechanical Turno	
Classroom A Turnover	0	000 10 20	Oct-16-23	A Fall	
Kitchen Turnover	0		Oct-17-23	◆ Class	
Thanksgiving Break 2023/2024 School Year	-	Nov-23-23*	Nov-24-23	◆ Kitch	
Media Center Turnover	0		Dec-14-23		Th
	0		Dec-14-23		•
Actual Work				220210.03 Timothy Ball ES Additions and Renovations	
Remaining Work					
Critical Remaining Work				Schedule Update Mar-02-22	

Milestone

C Summary

\_ \_ . .

1 of 13

							2024					
Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov
			1			1		4				1
						 		ל				1 1 1
						' ' '						 , , ,
						   						1 1 1
						1						
						' '						L
						   						1
						   						1 1 1
						   						1 1 1
						1						1
						' ' '						L
						1 1 1						1 1 1
						   						1 1 1
						' ' '						L
choc	l Year					   						
iool \						   						1 1 1
						   						1 1 1
over						1						
er						' ' '						L
er						1						
	2024 S	chool	Year			   						
	23/202		1	ear								
nove						     						
	eak 2(	)23/20	24 Sc	hool Y	/ear	   						     
	omA					   						1 1 1
	h Turno					1 1 1						1
	Than		ig Bre	ak 202	23/202	24 Sch	ool Ye	ar				
-				Turno								
_							· · · · ·				. <u></u>	
				Sk	KILLN							
		C				772	5					

ctivity Name	Original	Start	Finish					)22											20	)23				
	Duration			Feb	Mar	Apr	May Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	No
Admin Tumover	0		Dec-21-23			1					r I I		1	1		- - 		1	1	1	1	-		:
Winter Break 2023/2024 School Year	10	Dec-25-23*	Jan-05-24										1			1	1							
Classroom B Turnover	0		Feb-05-24										-	1	-				1			- - - -		
Spring Break 2023/2024 School Year	5	Mar-25-24*	Mar-29-24													, , , ,								
Summer 2024	0	Jun-03-24*										1	1	1		1 1 1	1 1 1		1	1		1		I T
Classroom C Turnover	0		Jun-03-24								 , , ,		 ! !			     			 ! !			 ' '		
Stem/Art Turnover	0		Jun-14-24				1 I 1 I 1 I 1 I					1 1 1	1 1 1	   		1 1 1			   	1 1 1	1 1 1	- - - -		1
Final Punchlist Completion	10	Jun-17-24	Jun-28-24										- - -			     	1 1 1					     		1
Project Completion	0		Jun-28-24									- - -	- - -	1		1 1 1	1 1 1		1			- - -		1
Sitework	552	May-02-22	Jun-21-24			1				1	1   		1	1				Site	work	1				
Mobilize	1	May-02-22	May-02-22				Mobilize			+			÷									   		 ;
Erosion Control	1	May-02-22	May-02-22			1	Erosion C	ontrol					1			1 1 1	1 1 1			1 1 1		-		
Temporary Fencing	1	May-02-22	May-02-22			1	Temporal	1 1	ina			1 1 1	1 1 1	   	1	1 1 1	1		1	1 1 1	1 1 1	1 1 1		1
Strip and Demo	10	May-03-22	May-16-22			1	∠ ↓ \$trip a	i i	-			- - - -	- - -	     		1 1 1	1 1 1		     			- - - -		1
Underground Utilities	20	May-17-22	Jun-14-22					: :		Utilitie	s		-	1			1 1 1		1			- - -		
Barn Demo	10	Jun-01-22	Jun-14-22				T	Barn De					÷						+			   		
Grading	10	Jun-15-22	Jun-28-22					7 Grad			   		1	1			1		1					
Concrete Curbs and Walks	20	Jun-22-22	Jul-20-22				i i		-	ete Cu	rbs an	¦ nd Wa	lks	   		1 1 1	1 1 1		   	1 1 1	1	- - -		
Stone Base	10	Jun-29-22	Jul-13-22	_			i i	s		i i														
Binder West Lot	15	Jul-14-22	Aug-03-22							der W	est I o	, t	-	1					1			- - -		
Binder East Lot	10	Jun-05-23	Jun-16-23										÷			 , ,				Binder	East L	ot		
Topcoat Asphalt East Lot	5	Jun-19-23	Jun-23-23										1	1		1 1 1	1		1	1	1	1	ast Lo	ót
Finish Grades East Lot	5	Jun-26-23	Jun-30-23				1 I 1 I 1 I 1 I					1 1 1	1	   		1 1 1	1 1 1		i i	i	i i	i -	ast Lot	i
Landscaping East Lot	10	Jul-03-23	Jul-17-23										1										East L	
Topcoat Asphalt West Lot	5	Jun-03-24	Jun-07-24										-	1	-									
Finish Grades West Lot	5	Jun-10-24	Jun-14-24				+						÷			 , ,			+   					
Landscaping West Lot	5	Jun-17-24	Jun-21-24									1	1	1	1	1 1 1	1 1 1		1	1		1		1
Exterior Improvements	294	Jun-06-22	Jul-31-23								   	Exte	erior Im	prove	ments	\$	1 1 1			-	: <b>^</b>	-		:
West Playground	20	Jun-06-22	Jul-01-22					V Wes	st Play	aroun	d	- - - -	1	1	1	1 1 1	1 1 1	1	1	1	-	     		I.
Painting Existing Metal Panels/Alternate Bid	20	Mar-09-23	Apr-05-23						stria	giouri		- - - -	- - - -	1			D Pa	intina	Fyistin	¦ na Met	     Pan	_    elc/Δlt	ernate	Bid
Pre-K Playground	20	Jun-05-23	Jun-30-23				+			+			+						+	1=	K Play			
Dumpster Enclosure	5	Jun-05-23	Jun-09-23			1					   	1	1	1		1 1 1	1		i i	1	er Enc	-	i i	1
Existing Roof Replacement	40	Jun-05-23	Jul-31-23			1	1 I 1 I 1 I 1 I					1 1 1	1 1 1	1	1	     	1 1 1	1			i i	i -	oof Re	nlac
Pre-K Addition	256	May-02-22	May-03-23								Pre-K	Ådditio	n	   	1 1 1	1 1 1	1 1							l
Sitework	16	May-02-22	May-23-22				Sitework			1	1		1	1	-	1	1		- - -	1 1 1		-		

Actual Work	220210.03 Timothy Ball ES Additions and Renovations	
Remaining Work		
Critical Remaining Work	Schedule Update Mar-02-22	
♦ ♦ Milestone		
Summary	2 of 13	



ctivity Name	Original Start	Finish		2022					2023								2024			
	Duration		Feb Mar Apr May Jur	n Jul Aug Sep	Oct Nov De	c Jan	Feb Mar	Apr May	Jun Ju	I Aug	Sep Oc	t Nov	Dec Jar	n Feb M	ar Api	r May	Jun J	ul Aug	Sep Oct	N
Grading	1 May	-02-22 May-02-22	🛛 Grading																	
Site Utilities	5 May	-03-22 May-09-22	∠ Site Ut	ilities																
Concrete Curbs and Walks	5 May	-10-22 May-16-22	∆⊽ Çonc	rete Curbs and Wal	ks															
Site Furnishings	5 May	-17-22 May-23-22		Furnishings																
Building Core and Shell	175 May	-03-22 Jan-11-23		Building Core a	nd Shell															
Excavate Footings and Foundations	5 May	-03-22 May-09-22	∠ Excava	ate Footings and Fo	undations				+											
Form and Pour Footings	10 May	-10-22 May-23-22		n and Pour Footing																
Foundations	15 May	-24-22 Jun-14-22		Foundations																
Backfill	5 Jun-	15-22 Jun-21-22		7 Backfill	I I I I I I I I I I I I															
Underground Utilities	10 Jun-	22-22 Jul-06-22		Underground L	Itilities															
Slab-on-Grade Prep and Form	10 Jul-0	7-22 Jul-20-22		Slab-on-Gra		n'	·		1											
Pour Slab-on-Grade	2 Jul-2	1-22 Jul-22-22		Pour Slab-c	1 1 1															
Structural Steel Framing, Detailing, Joists, and	20 Oct-	07-22 Nov-03-22			∠ Structur	n Steel	Framing D	atailing lois	ts and Dev	*										
Exterior Metal Stud Walls with Densglass	15 Nov-	04-22 Nov-28-22			i i i	i i		alls with Der	i i	л										
Roofing	10 Nov-	04-22 Nov-17-22			AT Roof				is gia so											
Roofing Details	10 Nov-	18-22 Dec-05-22				oofing D	otoila		$\frac{1}{1}$ $\frac{1}{1}$											
Cavity Insulation and Veneer	30 Nov-	29-22 Jan-11-23					1	ion and Ver	hor											
Exterior Storefronts and Windows	10 Dec-	06-22 Dec-19-22					-	s and Wind												
Interior Buildout	110 Nov-	29-22 May-03-23				Interi	or Buildout		Jws											
In-Wall Electrical Rough-Ins	15 Nov-	29-22 Dec-19-22																		
Interior Metal Stud Framing	15 Nov-	29-22 Dec-19-22					Electrical F													
In-Wall Plumbing Rough-Ins	15 Nov-						Metal Stud													
Ductwork	15 Dec-				1 1 1		Plumbing	Rougin-Ins												
Above Ceiling Electrical and Technology	15 Dec-								<del>.</del>				1 1 1							
Above Ceiling Piping	15 Dec-				Δ			Electrical a	na iechnoi	ogy										
Drywall and Tape	20 Jan-						bove Ceilin		+											
Painting and Wall Coatings	20 Feb-							l and Tape												
Ceilings	15 Mar-		_					ainting and	Wall Coat	nġs										
Light Fixtures	15 Mar-							Ceilings												
Mechanical Trim	15 Mar-							Light Fixtur					     							
Electrical Devices and Trim	15 Mar-							Mechanica	÷											
Casework and Millwork	15 Mar-						1	Electrical D	1											
Markerboards and Tackboards	5 Mar-	· · ·						Casew												
Flooring	10 Mar-		_					7 Markerbo	1 1	ackboard	s									
Doors and Hardware	5 Apr-	· · ·					Z	🔽 Floorin												
Plumbing Fixtures	5 Apr-				· · · · · · · · · · · · · · · · · · ·				and Hardv											
	5 Apr-	Api-19-23							oing Fixture	s:						_	1	1		1
Actual Work			220210.0	3 Timothy Ball	ES Additions	s and <b>F</b>	<i>lenovatio</i>	ons												
Remaining Work     Critical Remaining Work				Schedule U	Update Mar-0	2-22									SKILL	MAN				
Milestone					-									A	7	ΠΠ				
🗅 Summary					3 of 13												5			

tivity Name	Original Start	Finish		22						2023							202			
	Duration		Feb Mar Apr May Jun	Jul Aug Sep	Oct N	lov Dec	Jan	Feb Mar Apr	<sup>-</sup> May Jur	n Jul	Aug Se	ep Oc	t Nov	Dec	Jan Fe	o Mar	Apr May Jun	Jul Aug Sep	Oct	Nov
Toilet Accessories	5 Apr-20-23	Apr-26-23							Toilet Acc	essorie	s									
Punchlist Completion	5 Apr-27-23	May-03-23						4	V Punchlis	st	letion									
Gym Addition	231 May-02-22	Mar-29-23		Gv	m Additio	'n														
Sitework	16 May-02-22	May-23-22	Sitework																	
Grading	1 May-02-22	May-02-22	⊠ Grading																	
Site Utilities	5 May-03-22	May-09-22	⊿ Site Utili	ies												1 1 1				
Concrete Curbs and Walks	5 May-10-22	May-16-22	∆ Concre	te Curbs and Wal	(S															
Site Furnishings	5 May-17-22	May-23-22	∆ Site F	umishings																
Building Core and Shell	165 May-10-22	Jan-04-23		Building Core a	nd Shell															
Excavate Footings and Foundations	10 May-10-22	May-23-22	Excav	vate Footings and	Foundatio	ons														
Form and Pour Footings	10 May-17-22	May-31-22		n and Pour Footin							I I I I I I									
Foundations	10 Jun-01-22	Jun-14-22		oundations							I I I I I I									
Backfill	2 Jun-15-22	Jun-16-22		Backfill			-													
Exterior CMU Walls	25 Jun-15-22	Jul-20-22		Exterior CM	UWalls															
Underground Utilities	5 Jun-17-22	Jun-23-22		Underground Utili											÷					
Slab-on-Grade Prep and Form	5 Jun-24-22	Jun-30-22		7 Slab-on-Grade I	1 1	Form														
Pour Slab-on-Grade	1 Jul-01-22	Jul-01-22		Pour Slab-on-G							I I I I I I					1				
Cavity Insulation and Veneer	20 Jul-21-22	Aug-17-22		∠ Cavity	1	n and Vene	er				I I I I I I									
Cold Formed Metal Framing	10 Jul-21-22	Aug-03-22		Cold For	i i	i i														
EIFS	15 Aug-18-22	Sep-08-22		Δ <u></u> Ε		<u> </u>									+					
Structural Steel Framing and Detailing	15 Nov-04-22	Nov-28-22			: :	V Struct	ural S	Steel Framing an	d Detailing											
Roofing	15 Nov-29-22	Dec-19-22						-												
Roofing Details	10 Dec-20-22	Jan-04-23				- i i		ofing Details			I I I I I I									
Interior Buildout	70 Dec-20-22	Mar-29-23					nterior	or Buildout												
Electrical Rough-Ins	10 Dec-20-22	Jan-04-23	·····				Flec	ctrical Rough-Ins							+					
Interior CMU Walls	10 Dec-20-22	Jan-04-23				1		erior CMU Walls												
Ductwork	10 Dec-20-22	Jan-04-23						twork												
Painting	10 Jan-05-23	Jan-18-23			1 I 1 I 1 I	- i i	- i	Painting			I I I I I I									
Light Fixtures	10 Jan-19-23	Feb-01-23					- i	7 Light Fixtures			I I I I I I									
Athletic Equipment	10 Feb-02-23	Feb-15-23						V Athletic Equ	upment:						+					
Acoustical Wall Panels	5 Feb-02-23	Feb-08-23					1	Acoustical W												
Scoreboards	5 Feb-02-23	Feb-08-23						Scoreboards												
Doors and Hardware	5 Feb-02-23	Feb-08-23						Doors and Ha	1 1		I I I I I I									
Athletic Flooring	20 Feb-09-23	Mar-08-23			I I I I I I		1	Athletic			I I I I I I									
Bleachers	10 Mar-09-23	Mar-22-23				$ \frac{1}{1} \frac{1}{1} - \frac{1}{1} - \frac{1}{1}$		Blea							+		· · · · · · ·			
Punchlist Completion	5 Mar-23-23	Mar-29-23							nchlist Com	pletion										
Actual Work			220210.03	Timothy Ball	ES Ad	ditions a	nd R			piotion					<u>i i</u>			; ; ;		
Remaining Work				·												S	KILLMAN			
Critical Remaining Work				Schedule U	U <b>pdate</b> 1	Mar-02-2	22								/	ЛЛ				
<ul> <li>Milestone</li> <li>Summary</li> </ul>					4 of 13												NN			

ctivity Name	Original Start	Finish	2022 2023 2024
	Duration		Feb       Mar       Apr       May       Jun       Jul       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Apr       May       Jun       Jul       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jul       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jul       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jun       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jun       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jun       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jun       Aug       Sep       Oct       Nov       Dec       Jan       Feb       Mar       Jun       Jun       Sep       Oct       Nov       Dec       J
Kindergarten Addition	286 May-02-22	Jun-14-23	Kindergarten Addition
Sitework	16 May-02-22	May-23-22	Sitework
Grading	1 May-02-22	May-02-22	🖾 Grading
Site Utilities	5 May-03-22	May-09-22	A Site Utilities
Concrete Curbs and Walks	5 May-10-22	May-16-22	In Concrete Curbs and Walks
Site Furnishings	5 May-17-22	May-23-22	▲ Site Furnishings
Building Core and Shell	200 May-24-22	Mar-08-23	Building Core and Shell
Excavate Footings and Foundations	5 May-24-22	May-31-22	₩ Excavate Footings and Foundations
Form and Pour Footings	10 Jun-01-22	Jun-14-22	<i>A</i> → Form and Pour Footings
Foundations	15 Jun-15-22	Jul-06-22	∠ Foundations
Backfill	5 Jul-07-22	Jul-13-22	
Underground Utilities	10 Jul-14-22	Jul-27-22	∠ Underground Utilities
Slab-on-Grade Prep and Form	10 Jul-28-22	Aug-10-22	Slab-on-Grade Prep and Form
Pour Slab-on-Grade	2 Aug-11-22	Aug-12-22	☑ Pour Slab-on-Grade
Structural Steel Framing, Detailing, Joists, and	20 Nov-29-22	Dec-27-22	∠ volution of the structural Steel Framing, Detailing, Joists, and Deck
Exterior Metal Stud Walls with Densglass	15 Dec-28-22	Jan-18-23	∠ Exterior Metal Stud Walls with Densglass
Roofing	10 Dec-28-22	Jan-11-23	$\Delta \nabla$ Roofing
Roofing Details	10 Jan-12-23	Jan-25-23	A Roofing Details
Cavity Insulation and Veneer	30 Jan-19-23	Mar-01-23	Cavity Insulation and Veneer
Exterior Storefronts and Windows	10 Jan-26-23	Feb-08-23	Exterior Storefronts and Windows
Composite Metal Panels	5 Mar-02-23	Mar-08-23	
Interior Buildout	105 Jan-19-23	Jun-14-23	
In-Wall Electrical Rough-Ins	15 Jan-19-23	Feb-08-23	/ ✓ In-Wall ⊟ectrical Rough-In's
Interior Metal Stud Framing	15 Jan-19-23	Feb-08-23	A Interior Metal Stud Framing
In-Wall Plumbing Rough-Ins	15 Jan-19-23	Feb-08-23	$\Delta \nabla$ In-Wall Plumbing Rough-Ins
Ductwork	15 Feb-09-23	Mar-01-23	∠ y nevral riding recent is
Above Ceiling Electrical and Technology	15 Feb-09-23	Mar-01-23	Above Ceiling Electrical and Technology
Above Ceiling Piping	15 Feb-16-23	Mar-08-23	$\Delta \nabla$ Above Ceiling Piping
Drywall and Tape	20 Mar-09-23	Apr-05-23	∠ Above Centing Fipling
Painting and Wall Coatings	20 Apr-06-23	May-03-23	$\Delta \rightarrow \nabla$ Dividing and Wall Coatings
Ceilings	15 Apr-20-23	May-10-23	
Light Fixtures	15 Apr-20-23	May-10-23	
Mechanical Trim	15 Apr-20-23	May-10-23	
Electrical Devices and Trim	15 Apr-20-23	May-10-23	Mechanical Trim
Casework and Millwork	15 May-11-23	May-31-23	Electrical Devices and Trim
Markerboards and Tackboards	5 May-11-23	May-17-23	△
V Actual Work		 	220210.03 Timothy Ball ES Additions and Renovations
Actual Work     Remaining Work			
Critical Remaining Work			Schedule Update Mar-02-22
♦ Milestone			5 of 13
△ Summary			5 of 13

Activity Name	Original Start	Finish	2022 2023 2024
	Duration		Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
Flooring	10 May-18-23	May-31-23	
Doors and Hardware	5 Jun-01-23	Jun-07-23	Doors and Hardware
Plumbing Fixtures	5 Jun-01-23	Jun-07-23	∠ Plumbing Fixtures
Toilet Accessories	5 Jun-01-23	Jun-07-23	Tojlet Accessories
Punchlist Completion	5 Jun-08-23	Jun-14-23	A Punchlist Completion
Classroom Addition	287 May-02-22	Jun-15-23	Classroom Addition
Sitework	16 May-02-22	May-23-22	Sitework
Grading	1 May-02-22	May-02-22	∑ Grading
Site Utilities	5 May-03-22	May-09-22	∆ Site Utilities
Concrete Curbs and Walks	5 May-10-22	May-16-22	Ø Concrete Curbs and Walks
Site Furnishings	5 May-17-22	May-23-22	Site Furnishings
Building Core and Shell	195 Jun-01-22	Mar-08-23	Building Core and Shell
Excavate Footings and Foundations	5 Jun-01-22	Jun-07-22	∑ Excavate Footings and Foundations
Form and Pour Footings	10 Jun-08-22	Jun-21-22	$\Delta \nabla$ Form and Pour Footings
Foundations	10 Jun-22-22	Jul-06-22	∠ Foundations
Backfill	5 Jul-07-22	Jul-13-22	Backfill
Underground Utilities	10 Jul-14-22	Jul-27-22	Underground Utilities
Exterior CMU Walls	25 Jul-21-22	Aug-24-22	Exterior CMU Walls
Slab-on-Grade Prep and Form	5 Jul-28-22	Aug-03-22	△ Slab-on-Ģrade Prep and Form
Pour Slab-on-Grade	1 Aug-04-22	Aug-04-22	∑ Pour Slab-on-Grade
Cavity Insulation and Veneer	30 Aug-25-22	Oct-06-22	Cavity Insulation and Veneer
Composite Metal Panels	15 Oct-07-22	Oct-27-22	Composite Metal Panels
Structural Steel Framing, Detailing, Joists, and	20 Dec-28-22	Jan-25-23	Structural Steel Framing, Detailing, Joists, and Deck
Roofing	10 Jan-26-23	Feb-08-23	$\Delta \nabla$ Roofing
Roofing Details	10 Feb-09-23	Feb-22-23	Roofing Details
Exterior Storefronts and Windows	10 Feb-23-23	Mar-08-23	Exterior Storefronts and Windows
Interior Buildout	101 Jan-26-23	Jun-15-23	
Slab-on-Deck Utility Rough-Ins	5 Jan-26-23	Feb-01-23	
Form and Prep Slab-on-Deck	5 Feb-02-23	Feb-08-23	→ Slab-on-Deck Utility Rough-Ins
Pour Slab-on-Deck	1 Feb-09-23	Feb-09-23	∠ Form and Prep Siab-on-Deck
In-Wall Electrical Rough-Ins	10 Feb-10-23	Feb-23-23	
Interior Metal Stud Framing	15 Feb-10-23	Mar-02-23	In-Wall ⊟ectrical Rough-Ins
Interior CMU Walls	10 Feb-10-23	Feb-23-23	
Ductwork	15 Mar-03-23	Mar-23-23	Interior CMU Walls
Above Ceiling Electrical and Technology	15 Mar-10-23	Mar-30-23	
Above Ceiling Piping	15 Mar-17-23	Apr-06-23	Above Ceiling Electrical and Technology
Actual Work	<u> </u>	·	220210.03 Timothy Ball ES Additions and Renovations
Actual Work			SKILLMA
Critical Remaining Work			Schedule Update Mar-02-22
Milestone			6 of 13
Summary			00/15

Activity Name	Original	Start	Finish		2	022					2023						2024			
	Duration			Feb Mar A	pr May Jur	Jul	Aug Sep	Oct	Nov Dec	Jan Feb Mar Apr	r May Jun Ju	I Aug Sep	Oct Nov D	ec Jan	Feb Ma	r Apr May	/ Jun Ji	ul Aug	Sep Oc	Nov
Drywall and Tape	20	Mar-24-23	Apr-20-23			1					Drywall and Tap	e							1	
Painting and Wall Coatings	20	Apr-07-23	May-04-23								■ Painting and	Wall Coatings								
Ceilings	15	Apr-14-23	May-04-23							Δ	Ceilings									
Light Fixtures	15	Apr-14-23	May-04-23								Light Fixtures									
Mechanical Trim	15	Apr-14-23	May-04-23								👿 Mechanical T	rim								
Electrical Devices and Trim	15	Apr-14-23	May-04-23								Electrical Dev	ices and Trim								
Casework and Millwork	15	May-05-23	May-25-23					· -    -         	· <del>,</del>		Casewor	k and Millwork				·		· · · · · · · · · · · · · · · · · · ·		
Markerboards and Tackboards	10	May-05-23	May-18-23						1	I         I         I         I           I         I         I         I         I           I         I         I         I         I           I         I         I         I         I	<u>∕</u> Markerboa		ards							
Lockers	10	May-05-23	May-18-23								∠ ↓ ockers									-
Flooring	10	May-19-23	Jun-01-23								∆ ↓ Theoring									
Doors and Hardware	5	Jun-02-23	Jun-08-23									and Hardware								
Punchlist Completion	5	Jun-09-23	Jun-15-23						· <del>;</del>			hlist Completion	ii							
Interior Renovations	523	Jun-06-22	Jun-14-24			1			1		Interior Renovatio	ns		1						
Above Ceiling Improvements	45	Jun-06-22	Aug-08-22		Above Ceil	n <mark>a Imp</mark> i	rovements		-											
Ceiling Removal	10	Jun-06-22	Jun-17-22			Ceiling	Removal													
Main Distribution Piping	35	Jun-20-22	Aug-08-22					istributior	n Dining											
Mechanical	85	Jun-05-23	Oct-02-23					istributio			М	echanical								
Demo	10	Jun-05-23	Jun-16-23								 ∆ Dem		1							
Underground Utilities	10	Jun-19-23	Jun-30-23									o nderground Utili	tion							
Mechanical Room Piping	5	Jul-03-23	Jul-10-23								1 1 1	Mechanical Ro								
Mechanical Equipment Pads	10	Jul-03-23	Jul-17-23								1 1 1	Mechanical E		-						
Electrical Rough-Ins	10	Jul-11-23	Jul-24-23		· + + +				· +					S :		·		 	· +	
Set Mechanical Equipment, Pumps, and Boile	10	Jul-18-23	Jul-31-23						1	I         I         I         I           I         I         I         I         I           I         I         I         I         I           I         I         I         I         I	-i i i	Electrical Ro								
Mechanical Trim		Jul-25-23	Jul-31-23									Set Mecha		nt, Pump	s, and Boil	ers				
Electrical Devices and Trim		Aug-01-23	Aug-07-23									✓ Mechanica								
Piping Insulation		Aug-01-23	Aug-07-23	_								Electrical		rim :						
Temperature Controls		Aug-08-23	Oct-02-23						·			Piping Ins								
Punchlist Completion		Aug-08-23	Aug-14-23										Temperature	Controls						
Cafeteria		Mar-30-23	Aug-03-23								Cafeteria	▲ Punchlis	t Completion							
Demo		Mar-30-23	May-03-23						1											
Ductwork		May-04-23	May-17-23	_							Demo									
Electrical and Technology Rough-Ins		May-18-23	May-31-23								Ductwork									
Interior CMU Walls		Jun-01-23	Jun-14-23						1			al and Technolo	gy Rough-Ins							
Paint		Jun-15-23	Jun-21-23									or CMU Walls								
Ceilings		Jun-22-23	Jul-06-23							I I I I I I I I I I I I I I I I	A Pai	1 1								
Light Fixtures		Jun-22-23	Jul-06-23									Ceilings								
		20 22 20			220210 0	3 Tim	othy Dal	1 6 4	dditiona	and Donovations		_ight Fixtures			_					
Actual Work					220210.0	5 I IM	oiny Bál	i es A	uailions	and Renovations										
Critical Remaining Work						S	chedule	Update	e Mar-02	2-22						SKILLMAN				
Milestone								7 - 6 1	2						RA	71	D			
Summary								7 of 1.	3											


ctivity Name	Original	Start Fini	sh				2022								2023							2024	4			
	Duration			Feb M	ar Apr	May	Jun J	ul Aug	Sep C	Oct Nov	Dec Jan F	-eb Mar	Apr N	May	Jun Ju	ul Aug	Sep O	ct Nov D	ec Jan Fe	eb Mar	Apr N	/lay Jun	Jul	Aug Sep	Oct	No
Mechanical Trim	10 、	Jun-22-23 Jul-	06-23				1									Mechar	nical Trim					1				
Electrical Devices and Trim	10 、	Jun-22-23 Jul-	06-23											     		Electrica	al Devices a	and Trim								
Acoustical Wall Panels	10 、	Jun-22-23 Jul-	06-23														al Wall Pa									:
Flooring	15 、	Jul-07-23 Jul-	27-23											-	1	Flo	-i - i -									1
Punchlist Completion	5	Jul-28-23 Aug	g-03-23											-	1		unchlist Cor	npletion								1
Kitchen	96 、	Jun-05-23 Oct	-17-23			·	·							 2		Kitche	en l	<u> </u>				·				
Demo	15 、	Jun-05-23 Jun	-23-23								1 I I I I I I I I			Z	Dei	moˈ										
Underground Utilities	15 、	Jun-26-23 Jul-	17-23													7 Ünde	rground Uti	lities								1
Ductwork	10 、	Jul-18-23 Jul-	31-23												i	; 🔽 Du	-									ļ
Concrete Slab Patching	5 /	Aug-01-23 Aug	g-07-23													1	1	ab Patching								
Electrical and Technology Rough-Ins	5 /	Aug-08-23 Aug	g-14-23				·				· • • • • • • • • • • • • • • • • • • •								gy Rough-Ir	ıs ¦		·				
Plumbing Rough-Ins	5 /	Aug-08-23 Aug	g-14-23														Plumbing F									
Set Cooler and Freezer	1 /	Aug-15-23 Aug	g-15-23								I I I I I I I I I			1				and Freeze	r							
Metal Stud Framing	5 /	Aug-16-23 Aug	g-22-23														Metal Stu	1						1		1
Interior CMU Walls	15 /	Aug-16-23 Sep	o-05-23															r CMU Walls	5							1
Drywall and Tape	5 /	Aug-16-23 Aug	g-22-23						+								7 Drywall ar									
Painting	5 /	Aug-23-23 Aug	g-29-23													1	Painting									
Ceilings	5 /	Aug-30-23 Sep	o-05-23								I I I I I I I I I						∠ ∠ Ceiling									
Light Fixtures	5 /	Aug-30-23 Sep	o-05-23								1 I I 1 I 1 I 1 I 1 I			1			⊥ Light F	- i - i -								
Mechanical Trim	5 /	Aug-30-23 Sep	o-05-23													1	Mecha	i i								1
Tie	10 \$	Sep-06-23 Sep	o-19-23						+		· <del> </del>						⊥ Tie					·				
Kitchen Equipment	15 \$	Sep-20-23 Oct	-10-23															Kitchen Eq	uipment							1
Punchlist Completion	5 (	Oct-11-23 Oct	-17-23															7 Punchlist								
Classroom A/Music/Applied Skills	95 、	Jun-05-23 Oct	-16-23			1					I I I I I I I I I I I			Cla	ssroom A	VMusic	Applied Sk									
Demo	10 、	Jun-05-23 Jun	-16-23								1 I I 1 I 1 I 1 I				🔽 Ďem											
Underground Utilities	5	Jun-19-23 Jun	-23-23			·	·		+		$\frac{1}{1}$						nd Utilities		· <del> </del>			·				
Ductwork	15	Jun-26-23 Jul-	17-23	_												7 Ductv										ł
Electrical and Technology Rough-Ins	15	Jun-26-23 Jul-	17-23												1			chhology Ro	uah-Ins							
Above Ceiling Piping	15	Jun-26-23 Jul-	17-23												i i	- i	e Ceiling Pi							   		
Metal Stud Framing	5	Jun-26-23 Jun	-30-23								I I I I I I I I I I I			1	1		ud Framing	9								1
Plumbing Rough-Ins	5	Jun-26-23 Jun	-30-23			·			+								Rough-Ins									
Drywall and Tape	5	Jul-18-23 Jul-	24-23											1			vall and Tap									1
Paint	10 、	Jul-25-23 Aug	g-07-23												i i	 ∠ F	-i - i -									-
Ceilings	10	Aug-08-23 Aug	g-21-23													1	Ceilings							,     		
Light Fixtures	10	Aug-08-23 Aug	g-21-23														Light Fixtu	Ires			, , , , , , , , , , , , , , , , , , ,					i
Mechanical Trim	10	Aug-08-23 Aug	g-21-23			·			+								Mechanic								• • • • • • • • • • •	 !
Actual Work					2	20210	).03 Ti	imothv	Ball E	S Addin	tions and Re	enovatio	ns		I										<u> </u>	
V Remaining Work					_			-												Sk	<b>KILLMA</b>					
Critical Remaining Work								Sched	ule Up	date M	ar-02-22															
Milestone									8 .	of 13										1/1/		NN				
Summary									00	·j 15																

Activity Name	Original	Start	Finish				2	022								2	2023							2024			
	Duration			Feb	Mar A	pr May	y Jun	Jul	Aug	Sep	Oct	Nov De	c Jan	Feb M	ar Apr	May Jun	Jul	Aug Se	ep Oct	Nov Dec	Jan Fel	b Mar	Apr Ma	y Jun	Jul Aug	Sep C	Oct Nov
Electrical Devices and Trim	10	Aug-08-23	Aug-21-23															<b>∆</b> ▼ Ele	ectrical D	evices and T	irim					1	
Set Unit Ventilators	1	Aug-08-23	Aug-08-23															🛛 Set U	Jnit Venti	ilators							
Casework and Millwork	10	Aug-22-23	Sep-04-23																Casewo	rk and Millwo	rk	1					
Markerboards and Tackboards	5	Sep-05-23	Sep-11-23																7 Marke	rboards and	Tackboards						
Lockers	10	Sep-05-23	Sep-18-23												     				V Locke	er¦s							
Flooring	15	Sep-19-23	Oct-09-23																	looring		1 1 1					
Doors and Hardware	5	Sep-19-23	Sep-25-23																	ors and Hard	vare						
Punchlist Completion	5	Oct-10-23	Oct-16-23																	Punchlist Co	mpletion	-					
Restrooms	65	Jun-19-23	Sep-18-23														Res	strooms									
Demo	5	Jun-19-23	Jun-23-23													Δ	7 Demo	0					· · · · · · · · · · · · · · · · · · ·				
Ductwork	5	Jun-26-23	Jun-30-23														🔽 Duc	1 1									
Underground Utilities	5	Jul-03-23	Jul-10-23				1									-	-	ndergrour	nd Utilitie	s							
Metal Stud Framing	10	Jul-11-23	Jul-24-23															Metal St									
Electrical and Technology Rough-Ins	5	Jul-11-23	Jul-17-23														i i	i i .	i i	nnology Rou	h-Ins	1					
Above Ceiling Piping	5	Jul-11-23	Jul-17-23				<mark> </mark>   			·						! <del>!</del> !		Above Ce						·			 I I I
Plumbing Rough-Ins	10	Jul-11-23	Jul-24-23														1	Plumbing		- T							
Drywall and Tape	5	Jul-25-23	Jul-31-23														-	Drywall				1 1 1					
Painting and Wall Coatings	5	Jul-25-23	Jul-31-23															1 1	1	/all Coatings							
Wal Tile	10	Aug-01-23	Aug-14-23														1	🗸 Wal									
Ceilings	5	Aug-15-23	Aug-21-23								·							∠ wa ∆⊽ Ce									
Light Fixtures		-	Aug-21-23															1	ht Fixtur								
Mechanical Trim			Aug-21-23																echanica								
Electrical Devices and Trim			Aug-21-23															: :				1 1 1					
Epoxy Flooring			Aug-28-23															1		evices and T	nm						
Plumbing Fixtures			Sep-04-23				<mark> </mark>												poxy Flo		· <del> </del>						
Toilet Accessories			Sep-11-23				1											1 1	1	ig Fixtures		-					
Toilet Partitions			Sep-11-23															1		Accessories		1					
Punchlist Completion			Sep-18-23															1 1		Partitions		1 1 1					
Media Center			Dec-14-23															N	Punc ledia Ce	hlist Complei	ion	1 1 1					
Demo			Aug-17-23											 		!  !		<mark> </mark>			+			·			
Ductwork		-	Sep-07-23															<b>∆</b> V Den	1								
Electrical and Technology Rough-Ins		-	Sep-28-23															1	Ductwo								
Above Ceiling Piping			Sep-28-23				1											1		ctrical and Te	1 1	kough-li	ns				
Metal Stud Framing			Oct-05-23															Δ	i i	ove Ceiling P	1 1						
Drywall and Tape			Oct-19-23								·					     		 		etal Stud Fra				·			
Paint			Nov-02-23		1 I 1 I 1 I					1 1 1								1 1 1 1 1 1 1	1	Drywall and	Таре						
	10						10.0	2 77.		D . 11		11:4:		D	4		1		Δ	V Paint						1	
Actual Work						2202	210.03	s Tim	othy .	Ball 1	ES A	dditions	s and I	kenova	tions												
Critical Remaining Work								S	Schedi	ule U	pdat	e Mar-0	)2-22									S	KILLMAN				
Milestone											-											(1.17		D			
Summary										9	9 of 1	13									$\mathcal{C}$						

Activity Name	Original	Start	Finish				2022		2023				20	24
	Duration			Feb N	/lar Apr	May Ju	un Jul Aug	Sep Oct Nov Dec Jan Feb Mar Apr May	ıy Jun Jul	Aug Sep	Oct Nov Dec	Jan Feb	Mar Apr May Ju	in Jul Aug Sep Oct No
Ceilings			Nov-16-23								🔽 Ceiling	js		
Light Fixtures	10		Nov-16-23								Light	Fixtures		
Mechanical Trim	10	Nov-03-23	Nov-16-23								🟧 Mech	anical Trim		
Electrical Devices and Trim	10	Nov-03-23	Nov-16-23			 I I I					└── Ėlectri	cal Devices a	and Trim	
Storefronts	10	Nov-03-23	Nov-16-23			1					└── Storef	ronts	I I I I I I I I I I I I I I I I	
Casework	5	Nov-17-23	Nov-23-23			1					🔊 Case	work	I I I I I I I I I I I I I I I I	
Flooring	10	Nov-24-23	Dec-07-23									ooring	I I I I I I I I I I I I I I I I	
Punchlist Completion	5	Dec-08-23	Dec-14-23									Punchlist Co	npletion	
Admin	143	Jun-05-23	Dec-21-23							Admir				
Demo	10	Aug-18-23	Aug-31-23							🕰 Dem	10			
Underground Utilities	10	Sep-01-23	Sep-14-23			1					ndergroundUtiliti	es	1 1 1 1 1 1 1 1 1 1 1 1 1 1	
Ductwork	15	Sep-08-23	Sep-28-23			1					Ductwork			
Electrical and Technology Rough-Ins	15	Sep-08-23	Sep-28-23								Electrical and Te	chnoloav Ro	uah-Ins	
Above Ceiling Piping	15	Sep-08-23	Sep-28-23			     	·		±		Above Ceiling P			· · · · · · · · · · · · · · · · · · ·
Plumbing Rough-Ins	5	Sep-08-23	Sep-14-23							i i i	lumbing Rough-Ir			
Metal Stud Framing	10	Sep-15-23	Sep-28-23								Metal Stud Fran	1		
Drywall and Tape	10	Sep-29-23	Oct-12-23								Drywall and	-		
Paint and Walcoverings	10	Oct-13-23	Oct-26-23								Paint and		<u>a</u>	
Wal Tile	10	Oct-13-23	Oct-26-23								Wall Tile			
Ceilings	10	Oct-27-23	Nov-09-23			1							I I I I I I I I I I I I I I I I	
Light Fixtures	10	Oct-27-23	Nov-09-23			1					Light Fi	1	I I I I I I I I I I I I I I I I	
Mechanical Trim	10	Oct-27-23	Nov-09-23								Mechai			
Electrical Devices and Trim	10	Oct-27-23	Nov-09-23										d Trim	
Casework and Millwork	10	Nov-10-23	Nov-23-23									ework and M	J	
Lockers	10	Nov-10-23	Nov-23-23			1						i i	WOR	
Epoxy Floors	5	Nov-10-23	Nov-16-23			1						1	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
Plumbing Fixtures	10	Nov-17-23	Nov-30-23									mbing Fixtur		
Markerboards and Tackboards			Nov-30-23	_		1						Ū		
Flooring			Dec-14-23							 			nd Tackboards	
Doors and Hardware			Nov-30-23									Flooring		
Punchlist Completion			Dec-21-23									ors and Hard		
Mechanical Mezzanine			Sep-25-23						Mechanica	Mezzanine		Punchlist C	Inbienou	
Demo			Jun-09-23											
Mechanical Equipment Pads			Jun-23-23					++++++++++++++++++++++++++++++++	Demo					
Mechanical Piping			Jun-30-23						1	anical Equip				
Set Mechanical Equipment, Pumps, and Boil			Jul-10-23							hanical Pipir	ig Il Equipment, Pur	nns and Bo	ers	
Actual Work	<u> </u>					20210	03 Timothy	Ball ES Additions and Renovations			a Equipment, Pur	прэ, ани во		
Remaining Work					-								SKILLMAN	
Critical Remaining Work							Schea	lule Update Mar-02-22						
Milestone								10 of 13						L
Summary								10 0j 13						

Activity Name	Original	Start	Finish					2	022								023									2024				
	Duration			Feb	Mar	Apr	May	y Jun	Jul	Aug	Sep Oc	t Nov	Dec Jan	Feb Ma	ar Apr	May Jun	Jul	Aug Se	ep O	ct Nov	Dec ,	Jan F	eb Ma	ar Api	May	Jun	Jul A	ug Se	ep Oc	t Nov
Electrical Rough-Ins			Jul-17-23						-								K I	Electrical F	Rough	Ins										
Mechanical Trim			Jul-24-23					, , , , ,		· · · · ·	   							Mechani	cal Trir	n			     		     	· · ·	, , ,	, , , ,	+	
Electrical Devices and Trim		Jul-25-23	Jul-31-23					1			     						Δ	7 Electrica	al Þevi	ceș and	Frim							1		
Piping Insulation	5	Jul-25-23	Jul-31-23								     						Δ	7 Piping I	Insulat	ion	1							1		
Temperature Controls	40	Aug-01-23	Sep-25-23																Те	mperatui	e Contr	ols								
Punchlist Completion	5	Aug-01-23	Aug-07-23								   							V Punch	nlist Co											
Classroom B	80	Oct-17-23	Feb-05-24																4		sroom	В								
Demo	10	Oct-17-23	Oct-30-23																4	Dem	0									
Ductwork	15	Oct-31-23	Nov-20-23																		Ductwo	rk								
Electrical and Technology Rough-Ins	15	Oct-31-23	Nov-20-23																		i.	i.	Fechnolo	oav Ro	uah-Ins					
Above Ceiling Piping	15	Oct-31-23	Nov-20-23																		1	1			0					
Metal Stud Framing	5	Oct-31-23	Nov-06-23																	⊥ ▲ Me	1	-								
Drywall and Tape	10	Nov-21-23	Dec-04-23					·				·	*			·					7 Dryw				· -					
Paint	10	Dec-05-23	Dec-18-23																	i	<u>∽</u> Pa		lape							
Ceilings	15	Dec-19-23	Jan-08-24																			7 Ceilii								
Light Fixtures	10	Dec-19-23	Jan-01-24					1			     										1	1	Fixtures					1		
Mechanical Trim	10	Dec-19-23	Jan-01-24																		1		anical Tri	-						
Electrical Devices and Trim	10	Dec-19-23	Jan-01-24			     		- <del> </del>			     		++ ++ 1 1		·			   		·	+-		cal Devi					   	+	
Lockers	10	Dec-19-23	Jan-01-24					1														Locke		ues an			-			
Set Unit Ventilators	1	Dec-19-23	Dec-19-23																		i	i i								
Casework and Millwork		Jan-02-24	Jan-15-24																		1		Ventilato	1						
Markerboards and Tackboards		Jan-02-24	Jan-08-24																			1	sework a		1					
Flooring		Jan-09-24	Jan-29-24			-			-i	+ 	·										+-		erboard			ards		 1 1		
Doors and Hardware		Jan-09-24	Jan-15-24					1														i i	looring	- i				1		
Punchlist Completion			Feb-05-24																		2	i i	ors and		i.					
Restrooms		Oct-17-23	Jan-22-24																	Res	rooms		Punchl	list Cor	npletion	1				
Demo			Oct-23-23																	1	1									
Ductwork			Oct-30-23								·		· · · · · · · · · · · · · · · · · · ·								+-									
Underground Utilities			Nov-13-23																		i									
Metal Stud Framing			Nov-27-23																	<b>↓</b> U		i.								
Electrical and Technology Rough-Ins			Nov-20-23					1												1	Metal									
Above Ceiling Piping			Nov-20-23	_				1 1 1												1	1		Technolo	ogy Ro	ugh-Ins			1		
			Nov-20-23								·					· · · · · · · · · · · · · · · · · · ·					Above (									·
Plumbing Rough-Ins													I I I I I I							i i	i.	- i -	ugh-Ins							
Drywall and Tape			Dec-04-23					1					1 I 1 I 1 I 1 I								7 Dryw	all and	Таре							
Painting and Wall Coatings			Dec-04-23								     										7 Paint	ting an	d Wall C	bating	s			1		
Wal Tile	10	Dec-05-23	Dec-18-23			   		1									1		   		V w	al Tile	   					1		-
Actual Work							2202	210.03	3 Tim	othy .	Ball ES	Addit	tions and	Renovat	tions															
Remaining Work     Critical Remaining Work									S	ched	ule Und	ate M	ar-02-22											SKILL	MAN					
Milestone									2				<b></b>										In		7 7					
											11 o	of 13										$\subset$				5				

Activity Name	Original Start	Finish				2022											20	023				
	Duration		Feb Mar	Apr N	lay .	lun Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct N	Nov [
Ceilings	5 Dec-19-23	Dec-25-23		· · · · · · · · · · · · · · · · · · ·			, , , ,				, , , , ,			, , , , ,	     	, , , ,	, , , , , ,					
Light Fixtures	5 Dec-19-23	Dec-25-23																				
Mechanical Trim	5 Dec-19-23	Dec-25-23										1			   	1						
Electrical Devices and Trim	5 Dec-19-23	Dec-25-23									1	1										
Epoxy Flooring	10 Dec-19-23	Jan-01-24									1	1		   		1 1 1						
Plumbing Fixtures	10 Dec-26-23	Jan-08-24								1 1 1	1 1 1	1 1 1	   			1 1 1						     
Toilet Accessories	5 Jan-09-24	Jan-15-24				1							1	   	     							
Toilet Partitions	5 Jan-09-24	Jan-15-24										1				1 1 1						-
Punchlist Completion	5 Jan-16-24	Jan-22-24										-										
Classroom C	80 Feb-13-24	Jun-03-24																				
Demo	10 Feb-13-24	Feb-26-24									1		1			1						
Ductwork	15 Feb-27-24	Mar-18-24				 I I I					+			r , ,	     							
Electrical and Technology Rough-Ins	15 Feb-27-24	Mar-18-24					- - -				1 1 1	1 1 1	1 1 1	1     	1 1 1	1 1 1	1					1
Above Ceiling Piping	15 Feb-27-24	Mar-18-24								1 1 1	     	     	   			     						
Metal Stud Framing	5 Feb-27-24	Mar-04-24									1					1						
Drywall and Tape	10 Mar-19-24	Apr-01-24									1					1						
Paint	10 Apr-02-24	Apr-15-24									÷			 , ,		   	+		i			
Ceilings	15 Apr-16-24	May-06-24																				
Light Fixtures	10 Apr-16-24	Apr-29-24									1	1	1			1						
Mechanical Trim	10 Apr-16-24	Apr-29-24									1 1 1	1				1 1 1	1					
Electrical Devices and Trim	10 Apr-16-24	Apr-29-24									1 1 1	1				1 1 1	1					
Lockers	10 Apr-16-24	Apr-29-24				   		- +			+ ! !			, , , ,	     	 '	+					
Set Unit Ventilators	1 Apr-16-24	Apr-16-24									1					1						
Casework and Millwork	10 Apr-30-24	May-13-24										- - - -										
Markerboards and Tackboards	5 Apr-30-24	May-06-24									1		1			1						- - - - -
Flooring	15 May-07-24	May-27-24								-	1 1 1	- - -	   			1 1 1						
Doors and Hardware	5 May-07-24	May-13-24	;;	++				- +			1 T		     	   	   	 	+					
Punchlist Completion	5 May-28-24	Jun-03-24								1 1 1	1 1 1	1 1 1	   			1 1 1						1 1 1
Restroooms	70 Feb-13-24	May-20-24														1						
Demo	5 Feb-13-24	Feb-19-24																				
Ductwork	5 Feb-20-24	Feb-26-24													   	1						
Underground Utilities	10 Feb-27-24	Mar-11-24									+				     		+					
Metal Stud Framing	10 Mar-12-24	Mar-25-24	_				-				1 1 1	1	1 1 1	1     	1 1 1	1	1					1
Electrical and Technology Rough-Ins	5 Mar-12-24	Mar-18-24									     	1 1 1				   						
Above Ceiling Piping	5 Mar-12-24	Mar-18-24										-				1						
Plumbing Rough-Ins	10 Mar-12-24	Mar-25-24	_								- - - -	-	     			- - - -						
Actual Work				22	0210	.03 Tim	othy	Rall	FC	1 1 1 1 1	ions	and	Dana	matio	14.6							
Remaining Work					0210	.05 111	ioiny	Duu		1000	ions	unu 1	Neno	vano	ms							
Critical Remaining Work						S	Sched	lule l	Upda	te Ma	a <b>r-0</b> 2	2-22										
Milestone									12 of	13												
Summary								1	1 4 UJ	13												



n 5 Mar-26-24 5 Mar-26-24 0 Apr-02-24 5 Apr 16 24	Apr-01-24 Apr-01-24	Feb Mar	Apr May J					20	23				2024
5 Mar-26-24 0 Apr-02-24				un Jul Aug	Sep Oct	Nov Dec Jan	Feb Mar Apr	May Jun	Jul A	ug Sep C	ct Nov	Dec Jan	Feb Mar Apr May Jun Jul Aug Sep Oct N
0 Apr-02-24	Apr-01-24												∠ Drywall and Tape
·	1,01,01,21												▲ Painting and Wall Coatings
E Apr 16 04	Apr-15-24						I I I I I I I I I I I						∠ Wal Tile
5 Apr-16-24	Apr-22-24												∠ Ceilings
5 Apr-16-24	Apr-22-24												∠ Light Fixtures
5 Apr-16-24	Apr-22-24												Mechanical Trim
5 Apr-16-24	Apr-22-24												∠ Electrical Devices and Trim
0 Apr-16-24	Apr-29-24	_											
0 Apr-23-24	May-06-24												$\Delta \nabla$ Plumbing Fixtures
5 May-07-24	May-13-24												∠ righting ricketes
5 May-07-24	May-13-24				- <del> </del>			·		·			∑ Toilet Accessories
5 May-14-24	May-20-24												$\Delta$ Punchlist Completion
5 Dec-25-23	Jun-14-24												Stem/Art
5 Dec-25-23	Jan-12-24						I I I I I I I I I I I I						
													Underground Utilities
		_										4	
												4	Electrical and Technology Rough-Ins
												4	Metal Stud Framing
												Δ	Plumbing Rough-Ins
								·		·			Above Ceiling Piping
							I I I I I I I I I I I I						Drywall and Tape
													A Paint
-		_											Ceilings
·	· ·	_											Light Fixtures
										·			Mechanical Trim
-		- 1											Electrical Devices and Trim
-													Casework and Millwork
													Storefronts
													Plumbing Fixtures
-							· · · · · · · · · · · · · · · · · · ·						Markerboards and Tackboards
-		_											Flooring
5 May-20-24	May-24-24 Jun-14-24	_											$\Delta \!$
5 Jun-10-24			i i i				i i i						
	<ul> <li>Apr-16-24</li> <li>Apr-16-24</li> <li>Apr-23-24</li> <li>May-07-24</li> <li>May-07-24</li> <li>May-14-24</li> </ul>	Apr-16-24         Apr-22-24           0         Apr-16-24         Apr-29-24           0         Apr-23-24         May-06-24           5         May-07-24         May-13-24           6         May-07-24         May-13-24           5         May-07-24         May-13-24           6         May-07-24         May-20-24           6         Dec-25-23         Jun-14-24           6         Dec-25-23         Jan-12-24           0         Jan-29-24         Feb-23-24           0         Jan-29-24         Feb-23-24           0         Jan-29-24         Feb-23-24           0         Feb-12-24         Apr-22-24           10         Feb-26-24         Mar-22-24           10         Apr-15-24         Apr-26-24           10         Apr-15-24         Apr-26-24           10	5       Apr-16-24       Apr-22-24         0       Apr-16-24       Apr-29-24         0       Apr-23-24       May-06-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-20-24         5       May-14-24       May-20-24         5       Dec-25-23       Jun-14-24         5       Dec-25-23       Jan-12-24         0       Jan-15-24       Jan-26-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-02-24         0       Jan-29-24       Feb-02-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Feb-12-24       Mar-22-24         0       Feb-12-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-29-24       May-17-24         0       Apr-29-24	5       Apr-16-24       Apr-22-24         0       Apr-16-24       Apr-29-24         0       Apr-23-24       May-06-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-20-24         5       May-14-24       May-20-24         5       Dec-25-23       Jan-14-24         6       Dec-25-23       Jan-12-24         7       Dec-25-23       Jan-26-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-02-24         0       Feb-26-24       Mar-22-24         5       Jan-29-24       Feb-02-24         0       Feb-26-24       Mar-22-24         10       Feb-26-24       Apr-26-24         10       Apr-15-24       Apr-26-24         10       Apr-15-24       Apr-26-24         10       Apr-15-24       Apr-26-24         10       Apr-29-24       May-17-24         10       Apr-29-24	Apr-16-24       Apr-22-24         Apr-16-24       Apr-29-24         Apr-23-24       May-06-24         Apr-23-24       May-06-24         May-07-24       May-13-24         May-07-24       May-13-24         May-14-24       May-20-24         May-14-24       May-20-24         Dec-25-23       Jan-14-24         Dec-25-23       Jan-12-24         Dec-25-23       Jan-12-24         Jan-15-24       Jan-26-24         Jan-29-24       Feb-23-24         Jan-29-24       Apr-26-24         Jan-29-24       Apr-26-24         Jan-25-24       Apr-26-24         Jan-15-24       Apr-26-24         Jan-29-24       May-17-24         Jan-29-24       May-10-24         Jan-29-24       May-10-24         Jan-29-24       May-17-24         Jan-29-24	Apr-16-24         Apr-22-24           Apr-23-24         Apr-29-24           Apr-23-24         May-06-24           May-07-24         May-13-24           May-07-24         May-13-24           May-07-24         May-13-24           May-07-24         May-13-24           May-07-24         May-13-24           May-07-24         May-20-24           Dec-25-23         Jan-12-24           Dec-25-23         Jan-12-24           Dec-25-23         Jan-26-24           Jan-29-24         Feb-23-24           Jan-29-24         Apr-26-24           Jan-29-24         Apr-26-24           Jan-29-24         Apr-26-24           Jan-29-24         Apr-26-24           Jan-29-24         Apr-26-24           Jan-29-24         May-10-24           Jan-29-24         May-10-24	5       Apr-16-24       Apr-29-24         0       Apr-16-24       Apr-29-24         0       Apr-23-24       May-06-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-14-24       May-20-24         5       Dec-25-23       Jun-14-24         6       Dec-25-23       Jun-14-24         7       Jan-15-24       Jan-26-24         9       Jan-29-24       Feb-23-24         0       Feb-12-24       Feb-23-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24	5         Apr-16-24         Apr-22-24           0         Apr-16-24         Apr-29-24           0         Apr-23-24         May-06-24           5         May-07-24         May-13-24           5         May-07-24         May-13-24           5         May-07-24         May-13-24           5         May-07-24         May-13-24           6         May-07-24         May-13-24           7         May-14-24         May-20-24           8         Deo-25-23         Jun-14-24           9         Deo-25-23         Jun-14-24           9         Jan-26-24         Feb-23-24           9         Jan-29-24         Feb-23-24           9         Jan-29-24         Feb-23-24           9         Feb-23-24         Apr-10-24           9         Apr-15-24         Apr-26-24           9         Apr-15-24         Apr-26-24           10         Apr-15-24         Apr-26-24 <t< td=""><td>5       Apr-16-24       Apr-22-24         0       Apr-16-24       Apr-29-24         0       Apr-32-24       May-06-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-14-24       May-20-24         6       May-14-24       May-20-24         7       Dec-25-23       Jun-14-24         0       Jan-12-24       Jan-26-24         0       Jan-26-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Feb-23-24       Feb-23-24         0       Feb-23-24       Feb-23-24         0       Feb-23-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-26-24       May-10-24         0       Apr-26-24       May-10-24         0       Apr-28-24</td><td>5       Apr:16:24       Apr:22:24         0       Apr:61:24       Apr:29:24         0       Apr:32       May:06:24         5       May:07:24       May:13:24         5       May:07:24       May:13:24         5       May:07:24       May:02:24         6       Deo:25:23       Jun:14:24         5       Deo:25:23       Jun:14:24         6       Deo:25:23       Jan:15:24         0       Jan:15:24       Jan:26:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Feb:22:4       Apr:12:44         0       Feb:22:4       Apr:20:44         0       Feb:22:4       Apr:20:41         0       Feb:22:4       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:20:24       May:10:24         0       Apr:20:24       May:10:24         0       May:20:24       Ma</td><td>5         Apr.16.24         Apr.22.24           0         Apr.23.24         May.06.24           5         May.07.24         May.13.24           6         May.14.24         May.20.24           7         May.14.24         May.20.24           8         Dec.25.23         Jan.14.24           9         Jan.15.24         Jan.22.44           9         Jan.25.24         Jan.26.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Feb.12.24         Feb.23.24           10         Jan.29.24         Feb.23.24           10         Jan.29.24         Mar.22.24           10         Apr.152.4         Apr.26.24           10         Apr.152.4         Apr.26.24           10         Apr.152.4         Apr.26.24</td><td>5       Apr.16.24       Apr.23.24         0       Apr.23.24       May06.24         5       May07.24       May13.24         6       May07.24       May13.24         7       May13.24       May20.24         8       May0.23       Jum.42         9       May1.24       May20.24         5       Dec.25.23       Jum.42         0       Jan.25.24       Jan.26.24         0       Jan.29.24       Feb.23.24         0       Jan.29.24       Apr.26.24         0       Apr.15.24       Apr.26.24         0       Apr.25.24       Apr.26.24         0       Apr.25.24       Apr.26.24<td>5       Apr:16:24       Apr:22:24         0       Apr:23:24       May:06:24         5       May:07:24       May:13:24         5       May:07:24       May:13:24         6       May:07:24       May:13:24         5       May:02:24       May:02:24         6       May:02:24       May:02:24         5       Dec:25:23       Jun:14:24         0       Jan:15:24       Jan:26:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Apr:26:24         0       Jan:29:24       Apr:26:24         0       Apr:15:24       Apr:26:24         0       Apr:26:24       Apr:26:24         0       Apr:26:24</td></td></t<>	5       Apr-16-24       Apr-22-24         0       Apr-16-24       Apr-29-24         0       Apr-32-24       May-06-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-07-24       May-13-24         5       May-14-24       May-20-24         6       May-14-24       May-20-24         7       Dec-25-23       Jun-14-24         0       Jan-12-24       Jan-26-24         0       Jan-26-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Jan-29-24       Feb-23-24         0       Feb-23-24       Feb-23-24         0       Feb-23-24       Feb-23-24         0       Feb-23-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-15-24       Apr-26-24         0       Apr-26-24       May-10-24         0       Apr-26-24       May-10-24         0       Apr-28-24	5       Apr:16:24       Apr:22:24         0       Apr:61:24       Apr:29:24         0       Apr:32       May:06:24         5       May:07:24       May:13:24         5       May:07:24       May:13:24         5       May:07:24       May:02:24         6       Deo:25:23       Jun:14:24         5       Deo:25:23       Jun:14:24         6       Deo:25:23       Jan:15:24         0       Jan:15:24       Jan:26:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Feb:23:24         0       Feb:22:4       Apr:12:44         0       Feb:22:4       Apr:20:44         0       Feb:22:4       Apr:20:41         0       Feb:22:4       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:15:24       Apr:20:24         0       Apr:20:24       May:10:24         0       Apr:20:24       May:10:24         0       May:20:24       Ma	5         Apr.16.24         Apr.22.24           0         Apr.23.24         May.06.24           5         May.07.24         May.13.24           6         May.14.24         May.20.24           7         May.14.24         May.20.24           8         Dec.25.23         Jan.14.24           9         Jan.15.24         Jan.22.44           9         Jan.25.24         Jan.26.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Jan.29.24         Feb.23.24           9         Feb.12.24         Feb.23.24           10         Jan.29.24         Feb.23.24           10         Jan.29.24         Mar.22.24           10         Apr.152.4         Apr.26.24           10         Apr.152.4         Apr.26.24           10         Apr.152.4         Apr.26.24	5       Apr.16.24       Apr.23.24         0       Apr.23.24       May06.24         5       May07.24       May13.24         6       May07.24       May13.24         7       May13.24       May20.24         8       May0.23       Jum.42         9       May1.24       May20.24         5       Dec.25.23       Jum.42         0       Jan.25.24       Jan.26.24         0       Jan.29.24       Feb.23.24         0       Jan.29.24       Apr.26.24         0       Apr.15.24       Apr.26.24         0       Apr.25.24       Apr.26.24         0       Apr.25.24       Apr.26.24 <td>5       Apr:16:24       Apr:22:24         0       Apr:23:24       May:06:24         5       May:07:24       May:13:24         5       May:07:24       May:13:24         6       May:07:24       May:13:24         5       May:02:24       May:02:24         6       May:02:24       May:02:24         5       Dec:25:23       Jun:14:24         0       Jan:15:24       Jan:26:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Apr:26:24         0       Jan:29:24       Apr:26:24         0       Apr:15:24       Apr:26:24         0       Apr:26:24       Apr:26:24         0       Apr:26:24</td>	5       Apr:16:24       Apr:22:24         0       Apr:23:24       May:06:24         5       May:07:24       May:13:24         5       May:07:24       May:13:24         6       May:07:24       May:13:24         5       May:02:24       May:02:24         6       May:02:24       May:02:24         5       Dec:25:23       Jun:14:24         0       Jan:15:24       Jan:26:24         0       Jan:29:24       Feb:23:24         0       Jan:29:24       Apr:26:24         0       Jan:29:24       Apr:26:24         0       Apr:15:24       Apr:26:24         0       Apr:26:24       Apr:26:24         0       Apr:26:24

Actual Work	220210.03 Timothy Ball ES Additions and Renovations	
Remaining Work     Critical Remaining Work	Schedule Update Mar-02-22	
<ul> <li>♦ ♦ Milestone</li> </ul>		
Summary	13 of 13	



# ADDENDUM THREE

Addendum Three (AD.03) to the drawings and specifications prepared by Gibraltar Design for Timothy Ball Elementary School Additions, Renovations, and Related Work for Crown Point Community School Corporation, Crown Point, Indiana.

All Contractors bidding on this project shall read all of the items covered below and shall comply with all of the requirements as set forth, including any necessary refinements or additions generated by this Addendum and required by the intent of the original contract documents. All Contractors shall acknowledge on their bid form that they have received this Addendum, Addendum One and Addendum Two, and include the appropriate content of same within their bid proposal.

# **SPECIFICATIONS**

## 1. Specification Section 00 01 10 Table of Contents

A. Add the following Specification Sections to the Table of Contents:

- 1. Section 12 56 57, Media Shelving and Furniture.
- 2. Section 23 52 16, Condensing Boilers.

## 2. Specification Section 07 24 00 Exterior Insulation and Finish System (EIFS)

- A. Add new Paragraph 1.1.B. to read: "B. EIFS Finish System for existing EIFS and Plaster surfaces."
- B. Add new Paragraph 2.1.T. to read: "T. Elastomeric Coating: Provide and install Elasto-Flex, as manufactured by Master Wall Inc., or approved equal, for installing on all existing EIFS and Plaster finishes. Confirm color selection with Architect prior to application."
- C. Add new Paragraph 3.2.H. to read: "H. Finish Coat on Existing EIFS and Plaster: Apply Elastomeric Coating on surface of existing EIFS and Plaster surfaces on Project."

## 3. Specification Section 03 30 00 Concrete

A. Revise Paragraph 2.4.H. 1. to read: "1. Basis-of-Design Product Subject to compliance with requirements and compatibility of Internal Curing Admixture, provide E5 system by Specification Products, Inc. consisting of E5 internal cure admixture @ 4oz/cwt and E5 catalyst sprayed on between 800-1,000 SF/ Gal over 15 Mil Glass A Vapor barrier"

## 4. Specification Section 08 41 00 Aluminum Entrances and Storefronts

- A. Revise Paragraph 2.3 D to read "Fixed Window Fame with Operable Windows: Window sub frame shall be equal to VG 451 UT framing system, nominal 2 inches wide by 4-1/2 inches deep, center glazing; as approved by the Architect."
- B. Revise Paragraph 2.3 D, 1. To read "Operable Units/ Lite/ Vent, Kawneer 8225 TL; Inward acting Hopper style (Project-in Window) with Insect Screen on exterior side. Insect screen mesh and frame to match window in color."

## 5. Specification Section 09 29 00 Gypsum Board

- A. Add new Paragraph 1.1.F. Spray Acoustical System.
- B. Add new Paragraph 2.4. Spray Acoustical System as follows:

"2.4 Spray Acoustical System

- A. Provide a spray-applied thermal and acoustical insulation system, K-13 Thermal Insulation, as manufactured by International Cellulose Corporation, or approved equal.
- B. Location: Where indicated on the Drawings.
- c. Color and Thickness: White, 2-inch thick."
- C. Add new Paragraph 3.2.T. as follows:
  - "T. Spray Acoustical System: Clean and prepare surface to be applied per Acoustical Spray manufacturers recommendations. Spray the indicated thickness in layers per manufacturer's instructions."

#### 6. Specification Section 09 51 00 Acoustical Ceilings

A. Delete Paragraphs 1.1.C., 2.3, and 3.2.S. in their entirety.

### 7. Specification Section 11 40 00 Foodservice Equipment

- A. Revise Paragraph 2.2.B.1. to read "Total of Two (2) Scoreboards required."
  - 1. Item #14 island work counter w/ prep sink
    - a. Delete all reference to "H. Stainless-steel u-channels for vertical cutting board storage"
    - b. Delete all reference to "I. Provide two (2) only 20" x 24" x 1/2" polyethylene cutting boards, white"
  - 2. Item #17 island work counter w/ prep sink
    - a. Delete all reference to "F. Stainless-steel u-channels for vertical cutting board storage"
    - b. Delete all reference to "G. Provide two (2) only 20" x 24" x ½" polyethylene cutting boards, white"
  - 3. Item #46 worktable
    - a. Delete all reference to "C. Open-base w/ stainless steel cross rails"
    - b. Item #69, 72, 79, 75, 82, 85 and 86 serving counters and cashier counters
    - c. Clarification: provide three (3) raised stainless steel tray slide runners on student side of counter top.
  - 4. Item #35 combi oven
    - a. Revise "F. One (1) only 60.75.752 combi-duo stacking kit and installation for ICC-6 full NG on top of ICC-6 full NG

#### 8. Specification Section 11 66 43 Scoreboards

A. Revise Paragraph 2.2.B.1. to read "Total of Two (2) Scoreboards required."

#### 9. Specification Section 12 56 57 Media Shelving and Furniture

A. Add new Specification Section 12 56 57, Media Shelving and Furniture, included in this Addendum, to the Project Manual.

#### 10. Specification Section 23 09 23Temperature Controls

- A. Add Paragraph 4.18 BUILDING RELIEF HOODS:
  - 1. Unoccupied: Relief hood automatic damper shall be closed.
  - 2. Occupied: Relief hood automatic dampers shall modulate as required to maintain



MARCH 3, 2022

positive building pressurization of 0.1" w.c. (adj).

- B. Add the following points to the Points List for Heating / Cooling Fan Coil units:
  - 1. Supply Fan: Start/Stop, Enable/Disable, Status, Alarm, Equip Alarm, Critical, Notification
  - 2. Discharge Air Temp: Temperature, High Limit, Low Limit
  - 3. Mixed Air Temp: Temperature
  - 4. Return Air Temp: Temperature, High Limit, Low Limit
  - 5. OA Dampers: Control
  - 6. Heating Valve: Control, Setpoint Adjustment
  - 7. Cooling Valve: Control, Setpoint Adjustment
  - 8. Low Limit Temperature: Alarm, Temperature, Critical, Notification
  - 9. Space Temperature: Setpoint Adjustment
  - 10. Space Humidity: Setpoint Adjustment

#### 11. Specification Section 23 21 13 Piping

A. Grooved Piping Systems: Remove "only within the confines of the mechanical rooms" from paragraph 2.07 A.

#### 12. Specification Section 23 52 16 Condensing Boilers

A. Add new Specification Section 23 52 16, Condensing Boilers, included in this Addendum, to the Project Manual.

#### 13. Specification Section 23 62 13Air Cooled Liquid Chiller

- A. Remove the following Specification Sections to the Table of Contents:
  - 1. Section 23 62 13, Air Cooled Liquid Chiller
- B. Remove the following Specification Section from Volume Three of the Specifications:
  - 1. Section 23 62 13, Air Cooled Liquid Chiller

## 14. Specification Section 23 74 14Rooftop HVAC Units (02-30 Tons)

- A. Remove "1 inch thick, 1 1/2 lb. density fiberglass insulation or" from 2.02 B 13.
- B. Revised paragraph 2.02 J 1. Change "digital scroll" to "variable speed inverter scroll".


#### 15. Specification Section 23 83 23 Unit Ventilators

A. Add the following sentence to end of Paragraph 2.02 K: "Provide painted closure panels and concealed support required for complete finished assembly."

#### 16. Specification Section 32 31 13 Chain Link Fences and Gates

- A. Delete Paragraph 1.3 E in its entirety.
- B. Delete Paragraph 1.9.A.4. in its entirety.
- C. Delete Paragraph 1.9.G. in its entirety.
- D. Revise Paragraph 2.2.A. to read "Install gates with fabric to match fence."







# DRAWINGS

## 17. Sheets C2.0

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add wood guard rail in south west corner of lot.
  - 2. Add call out for type of fence proposed around play areas.
  - 3. Removed "typical asphalt" from legend.
  - 4. Add "fence" to legend.

## 18. Sheets C3.0

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Remove 6" storm sewer line between MH/ OG #29 and west side of building.
  - 2. Added note regarding wall detail.

## 19. Sheets C4.0

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Removed detail for "Typical Asphalt Pavement Section"

#### 20. Sheets C4.2

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add detail for "Wood Guard Rail".
  - 2. Add and revise details for playground paving and playground outer barrier detail.
  - 3. Updated dumpster enclosure.

#### 21. Sheets S-201, S-202, S-203, S-205, S-206, S-207, S-208, S-209, S-401, S-402, S-403, S-411, S-412, S-413

A. Refer to revised, full-size drawing, included in this Addendum.

## 22. Sheet S-205

- A. Add the following note to Sheet S-205:
  - 1. Where existing duct work is removed exposing floor opening at new Air Handling Unit provide 16 Gauge cap flush to existing floor. Secure cap w/ 5" minimum brg all around opening. New concrete base/ pad shall be installed on top of 16 Gauge cap. Notify design team of conflicts prior to installation.

## 23. Sheets AD-101, AD-102, AD-103

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add plan note 59: Kitchen contractor shall demolish existing kitchen and all associated fixtures, equipment, kitchen related ductwork and accessories complete.
  - 2. Refer to Floor Plan for clouded revisions to plan notes in multiple locations.



## 24. Sheets A-101, A-102, A-103, A-104, A-

#### 105

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Refer to Floor Plan for clouded revisions to plan notes in multiple locations.

### 25. Sheet A-104

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add section cut 13/A212.
  - 2. Refer to Floor Plan for clouded revisions to wall types in multiple locations.

#### 26. Sheet A-105

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add section cut 14/A212.
  - 2. Refer to Floor Plan for clouded revisions to wall types in multiple locations.

#### 27. Sheet A-201

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add Note 30, "Extend roofing membrane up sloped roof 6'-0" and overlap new underlayment membrane and asphalt shingles 4'-0" onto roof membrane (transition to be 2'-0" up slope from change in angle)".

#### 28. Sheet A-212

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Revise roof plan details, typical details and wall sections.
  - 2. Refer to attached drawing for clouded revisions in multiple locations.

#### 29. Sheet A-401

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Add spray acoustical insulation

#### 30. Sheet A-417

A. Remove horizontal dimension indicating 10'-5" found on details 1/A417 and 2/A417 complete.

#### 31. Sheet A-704

Remove the words "BY OWNER" from Equipment Plan Notes 16, 17, 18 complete.

- 32. Sheet A-901, A-902, A-903, A-901, A-905
  - A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
    - 1. Revise note 8 to be "Existing plaster soffit to remain. Remove loose or water damaged plaster and patch cracks and/or holes with base coat. Apply



elastomeric coating on entire plaster soffit surface. (Estimate 75 linear feet of 6" wide cracked or loose surface that will need to be removed and replaced.)"

#### 33. Sheet A-903, A-904, A-905

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Remove note 8 from canopy locations indicated on attached drawings.

#### 34. Sheet K-602

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Detail "h"
    - a. Clarify note on s/s tray runners
  - 2. Detail "i"
    - a. Clarify note on s/s tray runners
  - 3. Detail "j"
  - 4. Clarify note on s/s tray runners

#### 35. Sheet M-001

- A. Refer to revised sheet for additional information:
  - 1. Added symbol to symbol list.

#### 36. Sheet MD-101

- A. Refer to revised sheet for additional information:
  - 1. Added sheet note 12.
  - 2. Added demo fin tube to classrooms.

#### 37. Sheet MD-102

- A. Refer to revised sheet for additional information:
  - 1. Added sheet note 15.
  - 2. Added demo fin tube to classrooms.
  - 3. Revised demo elevator exhaust to remain.
  - 4. Revised media center relief to remain.

#### 38. Sheet MD-102

- A. Add the following note to Sheet MD-102
  - 1. Demolish existing equipment and ductwork on floor and existing base/ pad near location of new Air Handling Unit complete. Existing base/ pad to remain.

#### 39. Sheet MD-103

- A. Refer to revised sheet for additional information:
  - 1. Added sheet note 10.
  - 2. Added demo fin tube to classrooms.

#### 40. Sheet MV-101

A. Refer to revised sheet for additional information:



- 2. Revised relief air in classroom A-117.
- 3. Added exhaust and transfer air in elev equip A-116.
- 4. Added H-1 and H-2.
- 5. Revised relief in stem A-144 and art room A-142.

### 41. Sheet MV-102

GIBRALTAR

DESIGN

- A. Refer to revised sheet for additional information:
  - 1. Added FC-3.
  - 2. Revised unit vent, heating coil, and ductwork in classroom A-304.
  - 3. Removed transfer grille in stair A-300.

#### 42. Sheet MV-102

- A. Add the following notes to MV 102
  - 1. New concrete base/ pad at AHU3. Pour pad level to top of existing base/ pad to remain.

#### 43. Sheet MP-101

- A. Refer to revised sheet for additional information:
  - 1. Added "H" to thermostats.
  - 2. Added co2 sensors to unit vents.

#### 44. Sheet MP-102

- A. Refer to revised sheet for additional information:
  - 1. t Added "H" to thermostats.
  - 2. Added CO2 sensors to unit vents.
  - 3. Revised unit vent and connection note in classroom A-304.
  - 4. Added condensate drain to ac-1 in tr a-308.

#### 45. Sheet MP-103

- A. Refer to revised sheet for additional information:
  - 1. Added "H" to thermostats.
  - 2. Added CO2 sensors to unit vents.
  - 3. Added CO2 sensor to return path for RT-2A and RT-2B.
  - 4. Clarified gas pipe size.
  - 5. Added condensate drain to AC-2.

#### 46. Sheet MP-104

- A. Refer to revised sheet for additional information:
  - 1. t Added "H" to thermostats.
  - 2. Added CO2 sensors to unit vents.

#### 47. Sheet MP-105

A. Refer to revised sheet for additional information:



- 1. Added "H" to thermostats.
- 2. Added CO2 sensors to unit vents.

## 48. Sheet M-201

- A. Refer to revised sheet for additional information:
  - 1. Removed RH-4 and RH-5.
  - 2. Added exhaust for H-1.

## 49. Sheet M-501

- A. Refer to revised sheet for additional information:
  - 1. Added FC-3, GEF-3, H-1, and H-2 to schedule.
  - 2. Added note 14 to schedule notes.

## 50. Sheet P-001

A. Revise S-1 model number to ELKAY #LRADQ-221945. Description shall be "1-Compartment Stainless Steel Sink, 22"x19-1/2"x4-1/2".

## 51. Sheet E-002

- A. Refer to revised sheet for additional information:
  - 1. Revised general note.
  - 2. Revised locations of site lighting fixtures.
  - 3. Revised site lighting fixture tags.
  - 4. Added site lighting fixture.

## 52. Sheet EL-101

- A. Refer to revised sheet for additional information:
  - 1. Revised locations of lighting fixtures.

## 53. Sheet EL-103

- A. Refer to revised sheet for additional information:
  - 1. Revised locations of lighting fixtures.
  - 2. Revised locations of site lighting fixtures.
  - 3. Revised lighting fixture types.
  - 4. Added lighting fixtures.

## 54. Sheet EL-104

- A. Refer to revised sheet for additional information:
  - 1. Revised lighting fixture type.
  - 2. Added lighting fixture.

## 55. Sheet EP-101

- A. Refer to revised sheet for additional information:
  - 1. Added electrical connections to mechanical equipment.
  - 2. Revised locations of devices.



## 56. Sheet EP-102

- A. Refer to revised sheet for additional information:
  - 1. Added electrical connection to mechanical equipment.
  - 2. Revised locations of site lighting fixtures.

## 57. Sheet EP-104

- A. Refer to revised sheet for additional information:
  - 1. Clarified stage floor box symbol.

#### 58. Sheet E-502

- A. Refer to revised sheet for additional information:
  - 1. Removed fixture type.
  - 2. Added approved equals.
  - 3. Revised site lighting fixture specifications.
  - 4. Added fixture type EA6.

#### 59. Sheet E-601

- A. Refer to revised sheet for additional information:
  - 1. Added FC-3, GEF-3, H-1, and H-2 to mechanical equipment connection schedule.

#### 60. Sheet E-604

- A. Refer to revised sheet for additional information:
  - 1. Added circuits to panels 1L1, BCP-1 and BCP-2.

#### 61. Sheet T-001

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Changed the text for telecom symbol 2D/LI to note that the A/V cabling is future

#### 62. Sheet TD100

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Demo Plan Note #7 language revised, this revised note applies to all demo sheets issued with the Project

#### 63. Sheet T-101

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Room A-101A, Re-located outlets on the east wall and added "LI" to data outlet.
  - 2. Room A-145, Re-located outlets on the west wall and added "LI" to data outlet..
  - 3. Room A-151, added "LI" to data outlet.

#### 64. Sheet T-102

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Room A-325, added "LI" to data outlet



2. Room A-330, added "LI" to data outlet

## 65. Sheet T-103

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Room B-212, Moved TV location, added a data outlet with "LI".
  - 2. Room B-216, added "LI" to data outlet.
  - 3. Room B-184, added a data outlet with "LI".
  - 4. Room B-172, Added TV outlet.
  - 5. Room B-172, added "LI" to data outlet.
  - 6. Room B-154, added "LI" to data outlet

#### 66. Sheet T-104

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Room C-240, added a data outlet with "LI".

#### 67. Sheet T-105

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Room D-256, added "LI" to data outlet.

#### 68. Sheet T-501

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Detail #10 added additional security camera symbols.

#### 69. Sheet T-502

- A. Refer to revised, full-size drawing, included in this Addendum, for the following revisions:
  - 1. Detail #1 and 2 deleted the requirements for the HDMI and USB jacks and cables.

Pages 1 through 10, inclusive, and Full Specification Sections 12 56 57 and 23 52 16 (and Eighty-One 81) Full-Size Drawings, constitute the total makeup of **Addendum Three**.



Y:\21-112 Crown Point CSC - Timothy Ball ES Addition and Renovations\Specs\AddendumTHREE\AD03.doc



# SECTION 12 56 57 MEDIA SHELVING AND FURNITURE

# 1 General

## 1.1 Section Includes

A. Wood media shelving.

## 1.2 Related Sections

- A. Section 06 20 00 Finish Carpentry: Circulation desk.
- B. Section 09 29 00 Gypsum Board: Gypsum board bulkheads.
- C. Division 26 Electrical service fittings.

## 1.3 References

- A. Perform all work and furnish all material in accordance with the following references.
  - 1. AWI Quality Standards of Architectural Woodwork Institute.
  - 2. PS (Product Standards) 51 Hardwood and Decorative Plywood.
  - 3. NEMA LD-3 High Pressure Decorative Laminates.
  - 4. ADA Accessibility Guidelines for Buildings and Facilities, Appendix A, Part 36, Standards for Access Design.
  - 5. Indiana Handicapped Accessibility Code.

## 1.4 Submittals

- A. Submit shop drawings, product data, and samples under provisions of Division 1. Include component dimensions, configurations, elevations, construction details, joint details, attachments, bulkhead dimensions (length, depth, height above floor), complete Shelving and Furniture Schedule and all rough-ins.
  - 1. Provide two 4 inch by 6 inch finished stain samples.

## 1.5 Delivery, Storage, And Handling

- A. Deliver products to site and store products on site under provisions of Division 1.
- B. Do not deliver products to site until destination space is ready to receive it.
- C. Coordinate size of access and route to place of installation.



# 2 Products

## 2.1 Acceptable Manufacturers

- A. Wood Shelving:
  - 1. Basis of Design: The Worden Company, Holland, Michigan.
  - 2. Brodart Company, Williamsport, Pennsylvania.
  - 3. William Hermann & Son, Indianapolis, Indiana.
  - 4. Euronique Inc., Elberfield, Indiana
  - 5. Liat Furniture, Troutman, North Carolina.

## 2.2 Materials

- A. Wood Shelving:
  - 1. General: Graded in accordance with the requirements of AWI.
  - 2. Lumber: All woods used in the construction of this equipment shall be selected from thoroughly air seasoned stock, free from imperfections, and kiln dried to have a moisture content, at time of assembly, of from 5 percent to 7 percent.
    - a. All exposed solid woods shall be select northern grown red oak, plain sawn and selected for uniformity of figure and grain.
    - b. Woods used in the unexposed parts shall be suitable hardwoods, sound throughout, but unselected as to color.
    - c. Use 3/4 inch thick, 45 pound density particle core plywood as minimum standard.
  - 3. Exposed Veneers: Plain sliced red oak, Grade "A tight and smooth, selected for uniformity, even grain, beauty, and color.
    - a. Provide face veneer with cathedral grain figure, faces must be book matched and balanced.
    - b. Provide faces free of wild grain, wide heart, and gross figure on either side of cathedral figure.
  - 4. Shelving Tops and Fascias: Hardwood plywood.
    - a. Continuous Tops: Three-ply particle construction plywood with 0.050 inch high pressure laminate face and 0.028 inch backer on underside, with hardwood fascia.



- 5. Shelving, Finished Ends, Uprights, and Backs: Select hardwood and hardwood plywood backing.
- 6. Vertical and Horizontal grade high pressure plastic laminate for exterior countertop surfaces, satin or textured finish, minimum 0.050 inch thickness with heavy gage neutral colored backing sheet for balanced construction. Color: refer to Finish Legend on Drawings.
- 7. High Density Fiberboard or plywood of thickness indicated on the Drawings.

#### 2.3 Hardware

A. Shelf Standards and Clips: Manufacturer's standard.

#### 2.4 Fabrication - General

- A. Fabricate furniture, shelving, and millwork in accordance with recommendations of AWI; custom grade, except as shown or noted otherwise.
  - 1. Wood Grain, Color, and Finish: Uniform and consistent in appearance.
  - 2. Wood Shelving:
    - 1) End Panel: 1 inch thick particle core with select hardwood face veneer with all exposed edges of not less than 3/16 inch bonded with solid edge strip.
    - Intermediate Upright: 3/4 inch thick particle core with hardwood veneer with all exposed edges of not less than 3/16 inch bonded with solid hardwood edge strip.
    - 3) Island or Peninsula End Panels: 1 inch thick solid hardwood.
    - 4) Top and Fascia: 3/4 inch thick three-ply hardwood veneer with hardwood veneer and 3/4 inch by 2 1/4 inch solid hardwood fascia.
    - 5) Base: 4 inches high by 1/2 inch thick solid hardwood.
    - 6) Base Shelf: 3/4 inch thick solid hardwood hardwood.
    - 7) Adjustable Shelves: 3/4 inch by 36 inches long, maximum, solid hardwood with 2 inch nosing of solid hardwood.
    - 8) Back Panels: 1/4 inch thick three-ply hardwood veneer core plywood with select rotary cut face veneer on all exposed faces.



9) Countertops: 3/4 inch by width indicated on drawings with selfedge and matching vertical faces on edges. Refer to Drawings for locations and Finish Legend on Drawings for selected color and texture.

## 2.5 Finishes

- A. Wood:
  - 1. Plane and sand all exposed wood surfaces thoroughly and set exposed fasteners.
    - a. Apply wood filler in exposed fastener indentations.
  - 2. Exterior Surfaces: Apply stain or lacquer sealer, sand, and apply two coats of lacquer.
  - 3. Stain, color, and finish selected by the Architect and Owner from full range of stain options of manufacturer. **Refer to Finish Legend for intent.**

## 3 Execution

#### 3.1 Inspection

- A. Obtain and verify dimensions affecting work of this Section from site.
- B. Beginning of installation means acceptance of existing conditions.

#### 3.2 Installation

- A. Set and secure shelving and casework in place rigid, plumb, and level.
- B. Use purpose designed fixture attachments for wall mounted components.
- C. Use threaded steel concealed joint fasteners to align and secure adjoining wall shelving and millwork units.
- D. Permanently fix wall shelving and millwork to floor or wall using appropriate angles and anchorages.
- E. Carefully scribe shelving and casework which abuts other building materials leaving gaps of 1/32 inch maximum.
  - 1. Overlay trim may be used for this purpose.
- F. Coordinate work with others.

#### 3.3 Adjusting And Cleaning


- A. Adjust doors, drawers, hardware, fixtures, and other moving or operating parts to function smoothly and correctly.
- B. Clean furniture, shelving, millwork, hardware, fittings, and fixtures.



## 3.4 Media Shelving And Furniture Schedule

- A. Refer to Drawings for Media Shelving Schedules.
- B. For convenience, the Model numbers shown on Drawings are taken from the catalogs furnished by the Worden Company and other companies as noted in the equipment schedule, and are used for reference only.

# END OF SECTION





#### DIVISION 23 – MECHANICAL Section 23 52 16 – Condensing Boilers and Accessories

#### 1.00 PART 1 – GENERAL

#### 1.01 DESCRIPTION OF WORK:

A. Work Included: This Section of work includes the furnishing and installing of gas-fired condensing hot water heating boilers and related accessories as required for a complete operating system.

#### 1.02 QUALITY ASSURANCE:

- A. Equipment or components of this contract document section shall meet or exceed the requirements and quality of the items as denoted on the contract documents.
- B. Units shall be A.G.A. certified and conform to latest ANSI standards.
- C. Boilers shall be constructed in accordance with the provisions of Section IV of ASME Boiler and Pressure Vessel Code and shall be stamped with the required official ASME symbol. Boilers shall comply with CSD-1 boiler code requirements, and also be CSA design certified.
- D. Boilers and control components shall be tested in accordance with the requirements of the American National Standard Institute, Specification No. ANSI Z21.13b.
- E. Test and inspect boilers according to the ASME Boiler and Pressure Vessel Code, Section IV. Boilers shall be test fired in the factory with a report attached permanently to the exterior cabinet of the boiler for field reference.
- F. Gas train and safety controls shall conform to requirements of UL 795,CSD-1, IRI and FM.
- G. Provide two (2) year warranty on boilers and accessories including parts and labor necessary to repair or replace the same.

#### 1.03 PRODUCT HANDLING:

- A. Protection: Use means necessary to protect boiler(s) before, during, and after installation.
- B. Replacement and Repair: Scratched, dented, and otherwise damaged units shall be repaired or replaced.

#### 1.04 SHOP DRAWING SUBMITTALS:

- A. Submittals shall be required for the following items, and for additional items where required for a complete and operational system:
  - 1. Boiler product data
  - 2. Boiler Controller
  - 3. Neutralization Basin

#### CONDENSING BOILERS AND ACCESSORIES



4. Manufacturer's Start-up Report

#### 2.00 PART 2 – PRODUCTS

- 2.01 MANUFACTURERS
  - A. Boilers are to be as manufactured by Camus (Avenger Condensing Series), Fulton (Endura Series), RBI (FlexCore), and Cleaver Brooks (ClearFire C Series).

#### 2.02 GENERAL:

- A. The boiler shall be designed so that thermal efficiency increases as the boiler firing rate decreases. Boiler efficiency shall have a minimum efficiency of 85% at maximum fire and 180 deg F return water temperature and 95% at minimum fire and 100 deg F return water temperature.
- B. Factory-packaged unit, complete with jacket, gas manifold, burner and controls mounted and wired, as specified in this Section.
- C. The complete boiler shall be factory fire tested by the manufacturer and a copy of the firetest report shall be supplied with the unit.
- D. All boiler pressure parts shall be constructed in accordance with the latest revision of the ASME Boiler and Pressure Vessel Code, Section IV, and shall be so stamped.

#### 2.03 HEAT EXCHANGER:

A. STAINLESS FIRE TUBE: The pressure vessel shall be constructed of SA53 carbon steel. The heat exchangers shall be constructed of 316L stainless steel fire tubes and tube sheets with one-pass combustion gas flow.

#### 2.04 BOILER JACKET:

- A. Entire boiler jacket shall be readily removable and reinstalled if necessary.
- B. The unit shall be able to operate with jacket panels removed during inspection or maintenance periods.
- C. Jacket shall be designed to accommodate negative pressure.

#### 2.05 GAS BURNER AND TRAIN

- A. Gas train shall be UL/FM/CSD-1 compliant.
- B. The gas train shall be certified to take a maximum of 2 psi natural gas.
- C. Burner shall be capable of modulating the firing rate without loss of combustion efficiency or staging of gas valves.
- D. Burner shall have hot surface or spark ignition with safeguard.
- E. Burner shall be forced draft gas integral with the boiler.

#### CONDENSING BOILERS AND ACCESSORIES



- F. Combustion chamber shall be suitable for sealed combustion.
- G. Burner emissions shall be low NOX.
- H. An observation port shall be provided for flame observation.
- I. The combustion air blower shall have sufficient capacity at the rated firing rate to provide air for stoichiometric combustion plus the necessary excess air.
- J. The combustion air blower shall be controlled by VFD.

#### 2.06 CONTROLS:

- A. Boiler System Controller:
  - 1. Provide a self-contained, factory furnished control system and LON or BACNET interface. The system shall be indexed from summer/winter modes of operation from the FMS and shall be operated based on input from the FMS.
  - 2. Boilers shall be provided with an integral controller having a minimum of 4-line LCD display. Boiler controller shall have the following features:
    - a. Multiple level of password protection
    - b. Central heating control with outdoor reset control
    - c. Capable of receiving signal from FMS to modulate boiler firing rate to maintain boiler loop water temperature
    - d. Remote setting and troubleshooting
    - e. USB connection for setting, troubleshooting, and trending boiler operation
- B. Boiler Control Sequence:
  - 1. The boilers shall be indexed on and off and indexed into modes of operation by the FMS.
  - 2. Unit mode of operation shall be as follows:
    - a. Lead and lag boilers shall be determined by the FMS.
    - b. Primary loop water reset temperature schedule shall be determined by the FMS. Boilers shall receive a signal from the FMS to modulate power burner(s) to maintain primary loop water temperature set point.

#### 2.07 WATER TRIM

- A. Provide ASME rated pressure relief valve set at 100 psig.
- B. Provide water flow switch to prevent burner operation during low water flow conditions.



C. Provide an adjustable high limit temperature controller with a manual reset to prevent water temperature from exceeding safe system temperature.

#### 2.08 VENTING AND INTAKE SYSTEM

- A. Provide motorized intake damper to stop combustion air flow through boiler when boiler is not firing.
- B. Air intake piping shall be PVC or galvanized pipe that is sealed and pressure tight.
- C. Boiler shall be certified for installation with Category IV venting as defined in NFPA 54 (ANSI Z221), latest edition. Use tapered termination or exhaust cones at exhaust outlet to alleviate any restriction of lower temp flues gasses.
- D. Extend corrosion resistant piping from vent drain to nearest floor drain complete as required. Provide model FMC J-12-58 neutralizer in drainpipe.

#### 2.09 NEUTRALIZATION BASIN

- A. Provide 25 gallon neutralization basin, with neutralizing agent, for each boiler. Inlet and outlet of neutralization basin shall be located below connection to boiler condensate drain.
- B. Condensate drain piping shall be corrosion resistant and provide condensate trap (minimum 4" deep) between boiler and neutralization basin. Route drain lines from neutralization basin to nearest floor drain.

#### 3.00 PART 3 EXECUTION

#### 3.01 WARRANTY AND MAINTENANCE:

- A. During the warranty and maintenance period, the boiler/burner package inclusive of accessories shall be lined-up, adjusted and started by a qualified representative of the boiler manufacturer for the intended operating conditions and shall be left in first class working condition ready for continuous and satisfactory operation at the beginning of each heating season. Start-up shall be performed with Owner's maintenance personnel present.
- B. During the warranty and maintenance period, the boiler/burner package inclusive of every accessory shall be shut-down by a qualified representative of the boiler manufacturer. Shut down shall be performed with Owner's maintenance personnel present.

#### 3.02 INSTALLATION:

- A. Equipment Installation:
  - 1. Provide permanent placard attached to unit identifying unit number.
  - 2. Install all field-installed options shipped loose with equipment per manufacturer's recommendations.




- 3. Install boilers level and plumb, according to manufacturer's written instructions and referenced standards.
- 4. Install electrical devices furnished with boiler, but not specified to be factory mounted.
- 5. Install loose trim furnished with boilers per manufacturer's recommendations.
- 6. Remove burrs, dirt, and construction debris and repair damaged finished including chips, scratches, and abrasions with manufacturer's touchup paint.
- B. Piping Installation:
  - 1. Install hot water supply and return, gas and condensate piping as required for a complete and operational system. Provide accessories as required based on actual field pipe routing and system requirements.
  - 2. Piping shall be brought to equipment connections in such a manner so as to prevent the possibility of loads or stresses being applied to the connections.
  - 3. Install a 1" drain valve on the outlet piping prior to the first shut off valve.
  - 4. Provide neutralization basin for condensate drain.
  - 5. Connect hot-water piping to supply and return boiler connections with shut off valve and union or flange at each connection.
  - 6. Install piping from safety-relief valves to nearest floor drain.
  - 7. Provide gas vent piping out to atmosphere for pilot pressure relief valve, main gas pressure relief valve, electric solenoid valves and gas pressure switches, etc.
- C. Control System:
  - 1. Control wiring is to be in accordance with local, federal, state, and national electric wiring codes.
  - 2. Unit is to be controlled by the FMS. Coordinate installation of thermostats, sensors, alarms, burner modulation controls, etc. with FMS requirements.
- D. Boiler Vent:
  - 1. Connect stack to boiler outlet, full size of outlet. The boiler shall operate under positive (Category IV) stack pressure. Vent material must be listed AL29-4C Stainless Double Wall Stack for condensing appliances. Route flue condensate drain piping from base of stack to the neutralization basin. Manufacturer to verify exhaust vent termination is installed per manufacturer's recommendations.
  - 2. Connect combustion air intake, full size of outlet. Combustion air intake material to be schedule 40 PVC pipe.




- E. Manufacturer Start-up:
  - 1. Arrange and pay for tests and start-up fee required for installation of equipment.
  - 2. Equipment manufacturer shall furnish required control devices, panels, sensors, wiring diagrams, etc. for the installation. Manufacturer shall work with the FMS contractor and assist in the initial equipment controls set up for a complete and operational system and to verify that required temperature control sequences (lead lag control, hot water reset, burner modulation, etc.) are operational.
  - 3. Engage a factory-authorized service representative to provide startup service. Start up to be performed only after complete boiler room operation is field verified to offer a substantial load, and complete system circulation. Coordinate start-up with temperature control manufacturer's representative.
  - 4. Manufacturer's representative shall instruct the maintenance personnel in the care and operation of the equipment.
  - 5. Submit manufacturer's start-up report for review. As a minimum, start up report shall contain the following information:
    - a. Electrical connections and terminals have been connected and are tight.
    - b. Gas piping has been checked for leaks.
    - c. Maintenance personnel have been instructed in the care and operation of the equipment.
    - d. Field supplied options shipped loose have been installed per manufacturer's recommendations.
    - e. Heating capacity control functions properly.
    - f. Boilers have been flushed and clean upon completion of installation, according to manufacturer's written instructions.
    - g. Temperature control points are communicating with FMS system.
    - h. Boiler exhaust termination meets manufacturer's recommendations.

END OF SECTION 23 52 16





	1	
CONSULTING ENGINEERS & LAND SUPPEYORS 907 RIGES FRAD MUNISTER, INI 46321 T: (219) 836–818 F: (219) 836–1138 CONSULTING ENGINEERS & LAND SUPPEYORM PIOL N. Meridian SL, Ste. 300 Indianapolis, INI 46260 Homepage www.GibratorDesign.com Email info@GibrattorDesign.com Email info@Gi	D ARCHITECTURE • E PROJECT TIMOT ES AD AND AND RENO CROWN POINT SCHOOL CORF	ESIGN NGINEERING • INTERIOR DESIGN THY BALL DITION
9102 N. Meridian St., Ste. 300         Indianapolis, IN 46260         Homepage www.GibratarDesign.com         PROJECT         21-112         DATE         02/07/22         COORDINATED BY         DCT         DRAWN BY         DCT EM         CHECKED BY         DCT         DRAWN BY         DCT EM         CHECKED BY         DCT         THIS DOCHWAT ARE THE PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIAL PLAN         DENAWING         SITE PLAN         PROJECT         TIMOTHY BALL ES ADDITIONS AND RENOVATIONS         Q GIBRALTAR DESIGN       SHEET	CONSULTING ENGIN 907 RIDGE ROAD MUNSTER, IN 4632 T: (219) 836-89	LAND SURVEYORS
9102 N. Meridian St., Ste. 300         Indianapolis, IN 46260         Homepage www.GibratarDesign.com         PROJECT         21-112         DATE         02/07/22         COORDINATED BY         DCT         DRAWN BY         DCT EM         CHECKED BY         DCT         DRAWN BY         DCT EM         CHECKED BY         DCT         THIS DOCHWAT ARE THE PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROPERTY OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROPERTY OF COMPARISON SHALL BE USED BY MANY PERSON ON FROM FOR ANY PURPOSE WITHOUT THE EXPRESS WITHEN CONSENT OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROPERTY OF ANY PERSON ON FROM FOR ANY PURPOSE WITHOUT THE EXPRESS WITHEN CONSENT OF GIRRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROPERTY OF ANY PERSON ON FROM FOR ANY PERSON ON FROM FOR THIS INCOMMENT ARE THE OWNER MART PERSON ONLY WITH THIS SPECIFIC PURPOSE WITHOUT THE EXPRESS WITHOUT THE THIS SPECIFIC PURPOSE WITHOUT THE EXPRESS WITHOUT THE THE CONSENT OF ANY PURPOSE WITHOUT THE EXPRESS WITHOUT THE THIS DOCUMENT AND REFERENCE IN CONNECTION ONLY WITH THIS SPECIFIC PURPOSE WITHOUT THE THE CONSENT OF ANY PURPOSE WITHOUT THE EXPRESS WITHOUT THE THE CONSENT OF ANY PURPOSE WITHOUT THE EXPRESS WITHOUT THE THE CONSENT OF ANY PURPOSE WITHOUT THE THE CONSENT OF ANY PURPOSE WITHOUT THE THE CONSENT OF ANY PURPOSE AND THE THE CONSENT OF ANY PURPOSE AND THE THE CONSENT OF ANY PURPOSE AND THE THE CONSENT OF ANY PURPOSE		
Phone 317.580.5777 Fox 317.580.5778 PROJECT 21-112 DATE 02/07/22 COORDINATED BY DCT DRAWN BY DCT EM CHECKED BY DCT COPYRIGHT NOTICE: THE CONCEPTS, DESIGNE, PLANS, DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON AND THIS DECIMIENT ARE THE DOMPETIT OF DETAILS, ETC, SHOWN ON AND THIS DECIMIENT ARE DESIGN. REVISIONS MARK DATE ISSUED FOR AD-1 2-17-22 ADDENDUM NO. 1 AD-3 3-3-22 ADDENDUM NO. 3	9102 N. Meridiar Indianapolis, IN 4 Homepage www.G	n St., Ste. 300 16260 SibraltarDesign.com
COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, PLANS, DETAILS, ETC. SHOWN ON THIS DOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND WERE CRAFTED FOR USE ON THIS SPECIFIC PROJECT. NONE OF THE INFORMATION SHILL BE USE DETAILS PERSON OF RIM PROJECT. REVISIONS MARK DATE ISSUED FOR AD-1 2-17-22 ADDENDUM NO. 1 AD-3 3-3-22 ADDENDUM NO. 3 INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS PROJECT. DETAILS IN INFORMATION OF INFORMATION ONLY WITH THIS PROJECT. DRAWING SITE PLAN © GIBRALTAR DESIGN SHEET CONSECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS SHEET CONSECT SHEET	Phone 317.580.5 PROJECT 21-112 DATE 02/07/22 COORDINATED BY DCT DRAWN BY DCT EM CHECKED BY	777 Fax 317.580.5778
MARK       DATE       ISSUED FOR         AD-1       2-17-22       ADDENDUM NO. 1         AD-3       3-3-22       ADDENDUM NO. 3         I       I       I         <	COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, THIS DOCUMENT ARE THE WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITHO OF GIBRALTAR DESIGN. TH INFORMATION AND REFERE PROJECT.	PLANS, DETAILS, ETC, SHOWN ON PROPERTY OF GIBRALTAR DESIGN AND ON THIS SPECIFIC PROJECT. NONE OF BE USED BY ANY PERSON OR FIRM UT THE EXPRESS WRITTEN CONSENT E OWNER MAY RETAIN COPIES FOR
PROJECT   TIMOTHY BALL ES ADDITIONS AND   PROVATIONS	MARK DATE	
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET	AD-3 3-3-22	ADDENDUM NO. 3
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
TIMOTHY BALL ES ADDITIONS AND RENOVATIONS © GIBRALTAR DESIGN SHEET		
©gibraltar design SHEET	TIMOTHY BALL	
	© GIBRALTAR DESIGN	





058 Timothy, Bolly dimov 2021-5058 SB dimo 271772022 7538:44 AM


















1. All sanitary sewer pipe, branches, and fittings shall conform to the following, Poly-vinyl chloride, SDR 26 (ASTM D-3034), with push-on rubber gasket joints (ASTM C-3212).

2. All sanitary sewer manholes shall be standard 48" diameter precast concrete units (ASTM C-478) conforming with the standard detail sheets of these plans. Mortar joints are not allowed on manholes, all joints must be rubber gaskets.

3. The completed sanitary sewer system shall be tested for infiltration and shall have a maximum infiltration of 3 gallons per hour per 100 feet of sewer pipe. The City of Crown Point shall be notified when the system (or portion thereof) is ready for testing. Mandrel testing shall be performed on all P.V.C. materials placed. The Contractor shall be responsible for supplying testing materials and appurtenances.

4. The Developer is responsible for the preparation of "As Built" construction drawings showing actual sizes and lengths of pipe installed (i.e. from manhole to manhole or tee to valve, etc.), location of service taps and any structures added or omitted in comparison with these engineering plans. The Developer shall supply the City of Crown Point with one reproducible drawing certified by a Professional Engineer or Land Surveyor and 2 copies thereof prior to and as a condition of the final acceptance.

5. All water main pipe shall be Ductile Iron Pipe (AWWA C-151, C-52) with bell and spigot push-on rubber gasket joints (AWWA CIII). All water main pipe shall be installed with a minimum cover of 5.0 feet from the top of the curb to the top of the pipe. All water mains shall be chlorinated at the time of installation and shall be subject to a test for pressure and purity. The Contractor shall notify the City of Crown Point when the water main system (or portion thereof) is ready for testing. All fire hydrants, tees, bends and fittings shall be suitable harnessed or thrust blocked with concrete.

6. All improvements installed across paved or future paved areas, driveways and sidewalks shall backfilled with graded stone aggregate to the subgrade line. Compaction shall be done in 8" maximum depth lifts to 95% maximum density.

7. Care should be taken in parkway areas to assure compaction acceptable for the stability of proposed driveways and sidewalks. While special backfill is not required, it shall be the responsibility of the contractor to protect against substantial future settlement of backfilled areas.

8. Air pressure test shall be performed on all completed Sanitary Manholes and existing manholes where the proposed sanitary system will connect to, in accordance with ASTM C 1244-93, Standard Test Method for Concrete Sewer Manholes by Negative Air Pressure (Vacuum) Test. The tests shall be conducted prior to backfill to demonstrate the integrity of the installed materials. The manhole shall pass if the test time meets or exceeds the required minimum test times as specified in ASTM C 1244-93 for the vacuum reading to drop from 10 inches of mercury to 9 inches of mercury. If the manhole fails the initial test, necessary repairs shall be made, and the test shall be repeated. The contractor shall be responsible for supplying all testing materials and appurtenances. The City of Crown Point shall be notified when the manholes (or portion thereof) are ready for testing.


9. Deflection tests shall be performed on all flexible pipe materials placed. The contractor shall be responsible for supplying testing materials and appurtenances. The tests shall be conducted after the final backfill has been in place at least 30 days. No pipe shall exceed a deflection of 5%. If the deflection test is to be run using a rigid ball or mandrel, it shall have a diameter equal to 95% of the inside diameter of the pipe. The test shall be performed without mechanical pulling devices. The City of Crown Point shall be notified when the system (or portion thereof) is ready for testing.

10. All sewers shall be laid at least 10 feet (3.0 m) horizontally from any existing or proposed water main. The distance shall be measured edge to edge. All sewers crossing water mains shall be laid to provide a minimum vertical distance of 18 inches (46 cm) between the outside of the water main and the outside of the sewer. This shall be the case where the water main is either above or below the sewer. The crossing shall be arranged so that the sewer joints will be equi distant and as far as possible from the water main joints. Where a water main crosses under a sewer, adequate structural support shall be provided for the sewer to prevent damage to the water main. When it is impossible to obtain proper horizontal and vertical separation as stipulated above, the sewer shall be designed and constructed equal to water pipe.

11. The newly installed force main (or portions thereof) shall be subjected to a pressure and leakage test, using hydrostatic testing. Test pressure shall not be less than 1.25 times the working pressure or exceed pipe design pressure. Pressure shall not vary by more than ±5 PSI for a minimum of a 2 hour duration test. The exposed pipe and joints shall be examined carefully during the test, and any damaged or defective pipe or joints shall be replaced, and the test shall be repeated. The allowable leakage shall not exceed 11.65 gpd/mi/in of nominal pipe diameter at a pressure of 150 PSI. All visible leaks are to be repaired regardless of the amount of leakage. The contractor shall be responsible for supplying all testing materials and appurtenances. The City of Crown Point shall be notified when the force main (or portion thereof) is ready for testing. Force Main shall be Polyvinyl Chloride, PVC C-900 conforming to AWWA C-900, Class 200 and all testing shall be in accordance with AWWA Standard C-600-93. The Force Main shall be installed with a minimum cover of 5.0 feet (60") to the top of the pipe.

12. All Force Main bends and fittings shall be suitably restrained with reaction blocking, restrained joints or clamps with concrete. Reaction Blocking shall be designed for a minimum internal pipe pressure of 150 psi. U.S. pipe field "A-LOK" Gasket system or approved equal shall prevail for concrete blocking on 4-inch through 12-inch pipe.

13. No sanitary sewer manhole shall be within eight (8) feet of a water main as measured from the outside edge of the sanitary sewer manhole to the outside edge of the water main.



## SPECIFICATIONS FOR STORM SEWERS

1. All work shall be performed in accordance with the Codes, Ordinances and Standards of the City of Crown Point, Lake County, Indiana.

2. All storm sewer pipe, branches and fittings shall conform to either of the following: Poly Vinyl Chloride Pipe (AASHTO M252), Polyethelene Pipe (ASHTO M252 or AASHTO M294), Concrete Pipe (AASHTO M170).

3. All storm sewer manholes shall conform to either of the following : (A) Standard precast concrete units (ASTM C-478) and/or (B) Poly-Vinyl Chloride (PVC) Structure Nyloplast or equal conforming with the standard detail sheet of these plans. Mortar joints are not allowed on manholes, all joints must be rubber gaskets.

4. All improvements installed across paved or future paved areas driveways, and sidewalks shall backfilled with graded stone aggregate to the subgrade line. Compaction shall be done in 8" maximum depth lifts to 95% maximum density.

5. Care should be taken in parkway areas to assure compaction acceptable for the stability of proposed driveways and sidewalks. While special backfill is not required, it shall be the responsibility of the contractor to protect against substantial future settlement of backfilled areas.

6. The Developer is responsible for the preparation of "As Built" construction drawings showing actual sizes and lengths of pipe installed (i.e. from manhole to manhole or tee to valve, etc.), location of service taps and any structures added or omitted in comparison with these engineering plans. The Developer shall supply the City of Crown Point with one reproducible drawing certified by a Professional Engineer or Land Surveyor and 2 copies thereof prior to and as a condition of the final acceptance.

7. All sewers shall be laid at least 10 feet (3.0 m) horizontally from any existing or proposed water main. The distance shall be measured edge to edge. All sewers crossing water mains shall be laid to provide a minimum vertical distance of 18 inches (46 cm) between the outside of the water main and the outside of the sewer. This shall be the case where the water main is either above or below the sewer. The crossing shall be arranged so that the sewer joints will be equidistant and as far as possible from the water main joints. Where a water main crosses under a sewer, adequate structural support shall be provided for the sewer to prevent damage to the water main. When it is impossible to obtain proper horizontal and vertical separation as stipulated above, the sewer shall be designed and constructed equal to water pipe

8. No storm sewer manhole shall be within eight (8) feet of a water main as measured from the outside edge of the sanitary sewer manhole to the outside edge of the water main.

9. All storm sewer installed under pavement shall be SDR26 grade


## GENERAL SPECIFICATIONS


1. In areas of unsuitable soil, the contractor shall be responsible removal, replacement, and disposal of the soil.


2. Replacement and addition of structural soil under roads, pavement and building shall be done in lifts not to exceed 8-inches, with a required compaction of at least 95% of their maximum dry density can be obtained, in accordance with the Indiana Department of Transportation Standard Specifications.


3. The contractor shall provide full depth saw cuts where existing pavement concrete or asphalt is to be removed. The contractor shall provide adequate compacted material/gravel at saw cut edge to shore up and prevent the degradation of existing pavement to remain. Damage to existing pavement will be repaired at the contractor's expense.


4. The Occupational Safety and Health Administration recommends that walking surfaces have a static coefficient of friction of 0.5. A research project sponsored by the Architectural and Transportation Barriers Compliance Board (Access Board) conducted tests with persons with disabilities and concluded that a higher coefficient of friction was needed by such persons. A static coefficient of friction of 0.6 is recommended for accessible routes and 0.8 for ramps.



















2" O.C.	ES Al RE CRO	ECT MO S AC ND S AC ND ENC WN POIN	A COMMUNITY PORATION T, INDIANA
	CONS 907 I MUNS T: (2		321 918
	9102 Indian Home Email	N. Meridic apolis, IN page www. info@Gibro	.GibraltarDesign.com altarDesign.com
	PROJE 21– DATE 02/ COORI DCT DRAWI EM	-112 (07/22 Dinated By	No. 19868
	THE CON THIS DOO WERE CR THIS INF FOR ANY OF GIBRA	CUMENT ARE TH LEATED FOR USE DRMATION SHALL PURPOSE WITH ALTAR DESIGN. 1 TION AND REFER	S, PLANS, DETAILS, ETC, SHOWN ON E PROPERTY OF GIBRALTAR DESIGN AND E ON THIS SPECIFIC PROJECT. NONE OF L BE USED BY ANY PERSON OR FIRM OUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS
	MARK AD-1 AD-3	DATE 2–17–22 3–3–22	ISSUED FOR ADDENDUM NO. 1 ADDENDUM NO. 3
	DRAW DET		SPECIFICATIONS
	REN		L ES ADDITIONS AND S
	UD GID KAL	ULUUN	<b>C-4.2</b>

















## FOUNDATION PLAN NOTES

1. REF. S-001 FOR STRUCTURAL NOTES, DESIGN DATA & SCHEDULES. 2. ALL CONTRACTORS ARE REQUIRED TO COORDINATE THEIR WORK WITH ALL DISCIPLINES TO AVOID CONFLICTS. THE MECHANICAL, ELECTRICAL, AND PLUMBING ASPECTS ARE NOT IN THE SCOPE OF THESE DRAWINGS. THEREFORE, ALL REQUIRED MATERIALS AND WORK MAY NOT BE INDICATED.

3. COORDINATE EXACT SIZE & LOCATION OF ALL MECHANICAL OPENINGS IN FOUNDATION WALLS WITH THE MECHANICAL, ELECTRICAL & PLUMBING CONTRACTORS.

4. ALL ELEVATIONS ARE REFERENCED FROM THE FIRST FLOOR FINISH FLOOR ELEVATION 100'-0". REFER TO THE SITE/CIVIL DWGS. FOR EXACT U.S.G.S. ELEVATION.

5. REF. ARCH. DRAWINGS FOR ALL DIMENSIONS NOT SHOWN. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION AND IMMEDIATELY NOTIFY ARCHITECT/ENGINEER OF ANY DISCREPANCIES.

6. REF. S-401 FOR TYPICAL FOUNDATION DETAILS.

7. NOTE: PERIMETER WALL AND COLUMN FOOTINGS SHALL BE LOWERED AND/OR SLEEVED TO PASS BELOW PLUMBING LINES (I.E. SANITARY & STORM SEWERS, WATER LINES, ETC.) SHOWN ON THE PLUMBING DRAWINGS. PROVIDE FOOTING STEPS AS REQUIRED PER THE TYPICAL DETAILS ON S-401.

8. ALL SLAB RECESSES SHALL BE LOCATED PER THE ARCHITECTURAL DRAWINGS. COORDINATE DEPTHS OF ALL SLAB RECESSES WITH THE ARCHITECTURAL DRAWINGS AND/OR THE FLOORING SUPPLIER.

9. COORDINATE REINFORCING DOWELS FOR CMU VERTICAL REINFORCING WITH REINF. NOTED ON PLANS & SECTIONS.

10. GROUT ALL CORES OF CMU BELOW FINISH FLOOR SOLID.

11. COLUMN FOOTINGS, TRENCH FOOTINGS AND WALL FOOTINGS SHALL BEAR ON APPROVED SOIL. UNDERCUT AS REQ'D TO SUITABLE BEARING MATERIAL AS DETERMINED BY THE GEOTECHNICAL TESTING AGENCY. REF. TYPICAL FOOTING UNDERCUT DETAIL ON SHEET S-401. UNDERCUTTING TO SUITABLE BRG. MATERIAL IS NOT REQUIRED FOR GRADE BEAMS. REFERENCE ELEVATIONS IN PARENTHESES (-XX'-X") FOR APPROXIMATE ELEVATION TO SUITABLE BEARING STRATA TO BE USE FOR BIDDING PURPOSES.


12. COLUMN FOOTINGS SUPPORTING MORE THAN ONE COLUMN SHALL BE CENTERED AT THE MIDPOINT BETWEEN THE COLUMNS, UNLESS NOTED OTHERWISE ON PLAN.

13. ALL EX. CONSTRUCTION SHOWN IN PLAN AND/OR SECTION WAS DERIVED FROM EXISTING DRAWINGS AND MUST BE FIELD VERIFIED. IF ANY DISCREPANCIES ARE DISCOVERED BETWEEN INFO. SHOWN ON THE DRAWINGS AND ACTUAL CONDITIONS IMMEDIATELY CONTACT ARCHITECT/ENGINEER FOR DIRECTION BEFORE PROCEEDING WITH THE WORK.


14. PROVIDE THICKENED SLAB UNDER ALL INTERIOR CMU WALLS WITHOUT FOOTINGS. SEE SHEET S-401 FOR THICKENED SLAB DETAIL. LAYOUT THICKENED SLABS FROM DIMENSIONS ON THE ARCHITECT FLOOR PLANS.

15. PROVIDE CONTROL/CONTRACTION JOINTS IN SLABS ON GRADE (REF. THE TYPICAL DETAILS ON SHEET S-401). ALL JOINTS IN SLABS TO RECEIVE THIN OR THICK-SET TERRAZZO, CERAMIC OR PORCELAIN TILE, VINYL-COMPOSITION TILE (VCT) OR VINYL SHEET GOODS, EPOXY OR SIMILAR THIN-FILM FINISH FLOORING SHALL BE CAREFULLY COORDINATED WITH THE FLOORING CONTRACTOR. THE CONTRACTOR SHALL SUBMIT SLAB JOINT LAYOUT TO ARCHITECT/ENGINEER FOR REVIEW PRIOR TO PLACING SLABS.

16. DENOTES VOID SLAB AT EXTERIOR ENTRANCES. SEE DETAILS ON SHEET S-402. 17. PLAN LEGEND:




OVER 6" COMPACTED GRANULAR FILL (INDOT No. 53 OR APPROVED EQUIV.).




DENOTES 4" CONC. SLAB ON GRADE w/ "FIBERFORCE 300" FIBERS @ 2.0 LB/C.Y. (OR EQUAL) & E5 SYSTEM BY SPECIFICATION PRODUCTS, INC. CONSISTING OF: E5 INTERNAL CURE ADMIXTURE @ 4 OZ/CWT & E5 CATALYST SPRAYED ON BETWEEN 800-1,000 SF/GAL **OVER 15-MIL CLASS A VAPOR BARRIER** OVER 6" COMPACTED GRANULAR FILL (INDOT No. 53 OR APPROVED EQUIV.). TOP OF SLAB AND CONTROL JOINT REQUIREMENTS TO BE COORDINATED w/ WOOD FLOOR SUPPLIER


NOTES: 1. CENTER FOOTINGS BENEATH COLUMNS, U.N.O. 2. ALL FOOTINGS MUST BE BOARD-FORMED, UNLESS APPROVED. 3. INCREASE FOOTING DEPTH WHERE REQ'D TO ENCASE COLUMN ANCHOR RODS NOTE: WF STEEL COLUMN SHOWN, TUBES, PIPES, C.I.P. CONCRETE,


ᡣᠬ᠇ᠬ᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇᠇






AD-3


































**1** ROOF FRAMING PLAN - UNIT A



























AD-3



REINFORCED MASONRY DETAIL

3/4" = 1'-0"

CMU CONTROL JOINT-SEE


ARCH. DWGS. FOR LOC'N.


OFFSET & LAP JAMB


JAMB BAR - FULL HT.


PLATE SCHEDULE						
EMENTS	REINFORCING					
EP x 24" LONG	NONE UNLESS LOCATED AT DISCONTIN. END OF WALL. EXTEND GROUT FULL HT. & REINF. SIM. TO MARK "B"					

LATE SCHEDULE							
NTS	REINFORCING						
24" LONG	2 VERTICALS FULL HEIGHT OF WALL. SEE PLANS & DETAILS FOR SIZE.						













SUPPLIER.














	<ul> <li>31 REMOVE FIRE EXTINGUISHER CABINET AND FIRE EXTINGUISHER. SALVAGE FIRE EXTINGUISHERS FOR INSTALLATION IN NEW CABINETS OR RELOCATED EXISTING CABINETS. COORDINATE ON SIGHT.</li> <li>32 REMOVE CURTAIN TRACK AND CURTAIN IN THEIR ENTIRETY.</li> </ul>	A.	ENERAL DEMOLITION NOTES: FOR GENERAL PROJECT NOTES, MATERIAL INDICATIONS LEGEND, SYME LEGEND, ABBREVIATIONS, ETC., REFER TO GI SERIES SHEETS. UNLESS NOTED OTHERWISE ON THIS SHEET, THE GENERAL CONTRACT RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL WORK INDICATED (
	33       DEMOLISH EXISTING TERRAZZO, CONCRETE SLAB AND INSULATION TO BASE         SLAB BELOW COMPLETE.         34       DEMOLISH BRICK, MASONRY AND CONCRETE STOOP COMPLETE.	C.	THIS SHEET. CONTRACTORS ENCOUNTERING EXISTING MATERIAL WHICH IS SUSPECT CONTAINING ASBESTOS SHALL STOP WORK IMMEDIATELY AND NOTIFY
	<ul> <li>[35] EXISTING DOOR FRAME TO REMAIN. REMOVE DOOR, TRANSOM AND HARDWARE.</li> <li>[36] REMOVE HOLLOW METAL FRAME AND GLAZING IN ITS ENTIRETY.</li> </ul>	D.	OWNER AND THE OWNERS REPRESENTATIVE. BOLD DASHED LINES INDICATE EXISTING ITEMS TO BE REMOVED UNLI
	<ul> <li>REMOVE ACOUSTICAL PANELS IN THEIR ENTIRETY. PATCH AND REPAIR WALLS AS REQUIRED TO RECEIVE NEW FINISHES.</li> <li>REMOVE CERAMIC TILE WALL SYSTEM IN ITS ENTIRETY. PREPARE EXISTING WALL AS REQUIRED TO RECEIVE NEW FINISHES.</li> </ul>	_	OTHERWISE NOTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR I VERIFYING THE EXTENT OF DEMOLITION WORK PRIOR TO BIDDING AN COORDINATING THE EXTENT OF DEMOLITION WITH THE INSTALLATION ( SYSTEMS. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION
	<ul> <li><u>ALTERNATE</u>: DEMOLISH, PATCH AND REPAIR WALL CONSTRUCTION TO RECEIVE NEW DOOR. GRIND AND PREPARE FLOOR AS REQUIRED.</li> <li>REMOVE BRICK BENCH IN ITS ENTIRETY. PREPARE FLOOR AND WALL AS</li> </ul>		APPLICABLE TO THEIR SCOPE OF WORK AND AS REQUIRED FOR INSTALLATION OF NEW WORK WHETHER OR NOT IT IS SPECIFICALLY INDICATED OR NOTED IN THESE DOCUMENTS.
	<ul> <li>(40) REQUIRED.</li> <li>(41) BUSH HAMMER EXISTING TERRAZZO AS REQUIRED FOR NEW LEVEL FLOOR FINISHES. PROVIDE LEVELING COMPOUND AS REQUIRED.</li> <li>(42) REMOVE WOOD TRIM, TACKABLE WALL COMPLETE.</li> </ul>	F.	REMOVE ALL ITEMS AND FINISHES MADE OBSOLETE BY NEW CONSTRU- VERIFY ITEMS DEEMED OBSOLETE WITH ARCHITECT PRIOR TO REMOVA REFER TO NEW CONSTRUCTION DRAWINGS FOR DEMOLITION REQUIRED SHOWN ON DEMOLITION PLANS.
	43 REMOVE TACKABLE WALL PANEL COMPLETE. 44 <u>ALTERNATE</u> : REMOVE MASONRY WALL AS REQUIRED FOR NEW	G.	EACH CONTRACTOR SHALL BE RESPONSIBLE FOR OFF SITE REMOVAL ALL DEMOLITION MATERIALS AND/OR ITEMS UNLESS NOTED OTHERWIS DIRECTED BY THE OWNER.
	<ul> <li>CONSTRUCTION. PATCH AND REPAIR FLOOR AND WALL AS REQUIRED TO ACCEPT NEW FINISHES.</li> <li>REMOVE PORTION OF EXISTING LIMESTONE PANEL AS REQUIRED FOR NEW</li> </ul>	Н.	PRIOR TO STARTING DEMOLITION, CONSTRUCT DUST CONTROL BARRIE REQUIRED TO PREVENT THE SPREAD OF DUST INTO SURROUNDING A (WHERE APPLICABLE).
	CONSRTUCTION. 46 REMOVE PORTION OF EXISTING BULKHEAD FRAMING TO MATCH NEW 9'-0" BULKHEAD.	١.	· · ·
	47 REMOVE EXISTING BULKHEAD EXTENSION FROM PREVIOUS PROJECT, PREPARE FOR RE FRAMING TO MATCH NEW 9'-0" BULKHEAD.	J.	PUBLIC. RELOCATED ITEMS SHALL BE CLEANED AND PLACED IN STORAGE, PE OWNERS' DIRECTION, UNTIL ITEMS ARE READY TO BE INSTALLED. IF
	48 ALTERNATE: EXISTING DOOR FRAME TO REMAIN. REMOVE EXISTING DOOR, HARDWARE, AND TRANSOM TO ACCEPT NEW DOOR AND HARDWARE 49 REMOVE EXISTING CANOPY IN ITS ENTIRETY INCLUDING STEEL FRAMING,		ARE DAMAGED DURING DEMOLITION OR RELOCATION, THEY SHALL BE REPAIRED OR REPLACED WITH NEW ITEMS AS APPROVED.
	ROOFING AND CONCRETE FOOTINGS AS REQUIRED FOR NEW CONSTRUCTION.	К.	DEMOLITION SHALL BE PERFORMED WITHOUT DAMAGE TO EXISTING CONSTRUCTION TO REMAIN. WHERE SUCH DAMAGE OCCURS, PATCH, OR RESTORE WALLS, FLOORS, CEILING, ETC. NEATLY TO MATCH EXIS ADJACENT SURFACE. PROVIDE SHORING, BRACING, OR SUPPORT AS
	ROD ASSEMBLY HAS MINIMUM OF 3 SAG RODS PER RUN AND SPACED AT MAXIMUM OF 48" APART. INSTALL NEW SAG ROD AND CHANNEL ASSEMBLY TO ENSURE WALL STABILITY ABOVE.		REQUIRED TO PREVENT MOVEMENT OR SETTLEMENT OF EXISTING STRUCTURES.
<u>)-2</u>	<ul> <li>51 REMOVE PORTION OF BRICK AND MASONRY WALL TO RECEIVE NEW LOUVER. TOOTH IN SALVAGED BRICK AS REQUIRED.</li> <li>52 DEMOLISH EXISTING SAG ROD ASSEMBLY TO ACCOMMODATE NEW CONSTRUCTION.</li> </ul>		EACH CONTRACTOR IS RESPONSIBLE FOR CUTTING, PATCHING, AND DISCONNECTION OF ITEMS APPLICABLE TO THEIR SCOPE OF WORK. V EXISTING SERVICES ARE ABANDONED, CAP AT LEAST 1" BEHIND NEW FINISHES AND/OR EXISTING SURFACE AND PATCH AS REQUIRED TO I NEW FINISHES OR MATCH EXISTING FINISH.
	53 REMOVE CONTINUOUS BACK SPLASH AND WALL CABINETS COMPLETELY. 54 DEMOLISH EXISTING TERRAZZO AND INFILL WITH LIGHTWEIGHT CONCRETE.	М.	ON WALLS THAT ARE TO RECEIVE NEW FINISHES, REMOVE AND REINS EXISTING EQUIPMENT TO REMAIN AS REQUIRED FOR INSTALLATION OF FINISHES.
	PREP AND DOWEL EXISTING AND NEW SLAB, REFER TO STRUCTURAL         DRAWINCS         55         DEMOLISH EXISTING TERRAZZO AND CONCRETE SLAB COMPLETE.	N.	WHERE WALLS OR BULKHEADS ARE REMOVED, PATCH FLOORS, CEILIN AND ADJACENT WALLS AS REQUIRED TO MATCH EXISTING OR RECEIVIN FINISHES WHERE APPLICABLE. WHERE EXISTING DUCTWORK, PIPING, (
	56 LINE OF SLAB DEMOLITION. 57 REMOVE EXISTING COOLER FREEZER IN ITS ENTIRETY. 58 MODIFY METAL STUD AND GYPSUM BOARD WALL ASSEMBLY TO RECEIVE NEW VUV CONSTRUCTION.		EQUIPMENT IS REMOVED, PATCH OPENINGS AND/OR SURFACES AS REQUIRED TO MATCH ADJACENT SURFACES OR RECEIVE NEW FINISHE WHERE APPLICABLE. REFER TO ALL DEMOLITION DRAWINGS FOR EXT OF ITEMS TO REMOVED.
-2	59 DEMOLISH EXISTING KITCHEN AND ALL ASSOCIATED FIXTURES, EQUIPMENT, KITCHEN RELATED DUCTWORK AND ACCESSORIES COMPLETE.	0.	OVER CUT NEW OPENINGS IN EXISTING WALL AS REQUIRED FOR NEW CONSTRUCTION. PATCH AND REPAIR WALLS AS REQUIRED TO MATCH EXISTING. WHERE APPLICABLE, TOOTH NEW MASONRY INTO EXISTING MASONRY.
-3	60 SELECTIVELY DEMOLISH EXISTING ROOF STRUCTURE AND DECKING COMPLETE TO ACCEPT NEW BUILDING CONSTRUCTION. REFER TO NEW CONSTRUCTION. REFER TO NEW CONSTRUCTION FOR ADDITIONAL INFORMATION.	Ρ.	ALL EQUIPMENT AND FURNITURE WHICH ARE CONSIDERED LOOSE FURNISHING SHALL BE REMOVED BY THE OWNER PRIOR TO DEMOLITI
	<ul> <li>61 SELECTIVELY DEMOLISH EXISTING BUILDING FASCIA, COPING, METAL PANEL SYSTEM AND SOFFIT COMPLETE TO ACCEPT NEW BUILDING CONSTRUCTION. REFER TO NEW CONSTRUCTION FOR ADDITIONAL INFORMATION.</li> <li>62 DEMOLISH ENTIRE CANOPY COMPLETE. REMOVE STRUCTURE AND CONCRETE FOOTINGS COMPLETE TO ACCEPT NEW CONSTRUCTION.</li> </ul>	Q.	MASONRY WALLS TO BE REMOVED SHALL BE REMOVED TO A POINT MINIMUM BELOW THE EXISTING FLOOR SLAB UNLESS SETTING ON A OR SPECIFICALLY NOTED OTHERWISE. PATCH WITH NEW CONCRETE TO FLUSH WITH THE EXISTING FLOOR SLAB.
		- R.	EACH CONTRACTOR SHALL BE RESPONSIBLE FOR GENERAL REVIEW O DEMOLITION NOTES AND GENERAL DEMOLITION NOTES AS THEY APPLY THEIR SCOPE OF WORK.
		S.	THE OWNER SHALL RESERVE THE RIGHT TO CLAIM ANY MATERIALS T ARE BEING DEMOLISHED PRIOR TO THE CONTRACTOR DISPOSING OF OFF SITE.
		Т.	REFER TO THE STRUCTURAL, MECHANICAL, PLUMBING, ELECTRICAL AN TECHNOLOGY DOCUMENTS FOR COMPLETE SCOPE OF DEMOLITION WO
		U.	"FLOORING" DENOTES FLOOR COVERING MATERIALS INCLUDING BACKIN ADHESIVES, AND BASES DOWN TO BUT EXCLUSIVE OF FLOOR SLABS STRUCTURAL MATERIALS UNLESS NOTED OTHERWISE.
		۷.	DEMOLITION IS TO FOLLOW ESTABLISHED CONSTRUCTION SEQUENCE. TO SPECIFICATIONS AND DRAWINGS FOR REQUIREMENTS AND SPECIAL
		W.	CONDITIONS. WHERE APPLICABLE SALVAGE EXISTING MASONRY (FACE BRICK, GLAZI CMU, FACING TILE) AS REQUIRED FOR PATCHING AND INFILL IN REM
		Х.	AREAS WHERE INDICATED. DISCARD UNUSED PORTION OFF SITE. PROVIDE TOPPING SLAB AND FLOOR LEVEL AS REQUIRED FOR APPLI OF NEW_CONDITIONS.
		F	NEW CMU CONSTRUCTION SHALL NOT BEAR ON EXISTING TERRAZZO CONCRETE TOPPING SLAB. DEMOLISH TERRAZZO AND EXISTING CONC
	AD-2		SLAB BELOW WHERE OCCURRING. EMOLITION PLAN NOTES:
		(AL	L PLAN NOTES MAY NOT BE INDICATED ON THIS SHEET.)  REMOVE ALUMINUM WINDOW AND/OR STOREFRONT FRAMING, DOORS HARDWARE IN ITS ENTIRETY. REPAIR JAMB AND FLOOR AS REQUIRED
		2	NEW FINISH. REMOVE ACOUSTICAL BOARD CEILING SYSTEM IN ITS ENTIRETY. REMOVE CARPET FLOORING SYSTEM AND BASE IN ITS ENTIRETY. PR
		4	<ul> <li>EXISTING CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES.</li> <li>DEMOLISH AND PREPARE EXISTING CONCRETE SURFACE TREATMENT RECEIVE NEW CONSTRUCTION.</li> </ul>
		5	- CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES.
		7	<ul> <li>EXISTING CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES.</li> <li>PROVIDE LEVELING COMPOUND AS REQUIRED.</li> <li>REMOVE DISPLAY WALL, CHALK, MARKER, AND/OR TACKBOARDS IN TENDER</li> </ul>
		8	-
		10	REMOVE PLUMBING FIXTURES COMPLETE. REFER TO PLUMBING DRAV WHERE PIPING IS REQUIRED TO BE CAPPED, CAP BELOW AND/OR FINISHED SURFACE.
		1 <sup>-</sup> 12	
		13	REMOVE HOLLOW METAL FRAME, TRANSOM, DOOR AND HARDWARE IN ENTIRETY.
		14	REMOVE CONCRETE SHOWER CURB. PATCH AND REPAIR FLOOR AS REQUIRED TO ACCEPT NEW FINISHES.
		16	$^{\prime}$ NEW CONSTRUCTION. PATCH AND REPAIR FLOOR AND WALLS AS RE $^{\prime}_{\rm N}$ TO ACCEPT NEW FINISHES.
		17	REMOVE EXISTING BLEACHERS IN THEIR ENTIRETY. REMOVE METAL LOCKERS. REMOVE CONCRETE BASE AS REQUIRED FOR NEW CONSTRUCTION.
		19 20	REMOVE MEDIA SHELVING IN ITS ENTIRETY.
		2 22 23	-
		24	REMOVE VOID SLAB/STOOP/STEPS/RAMP AS REQUIRED FOR NEW CONSTRUCTION.
	/	20	
	AD-2	2	REMOVE WALL COVERING IN ITS ENTIRETY. PREPARE WALL FOR NEW FINISHES.
		28	CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES. PROVIDE LEVELING COMPOUND AS REQUIRED.
		29 30	-










# UNIT "B" ARCHITECTURAL MEZZANIN


SCALE: 1/8" = 1'-0"


31 REMOVE FIRE EXTINGUISHER CABINET AND FIRE EXTINGUISHER. SALVAGE FIRE EXTINGUISHERS FOR INSTALLATION IN NEW CABINETS OR RELOCATED	A. FOR GENERAL DEMOLITION NOTES:
EXISTING CABINETS. COORDINATE ON SIGHT. 32 REMOVE CURTAIN TRACK AND CURTAIN IN THEIR ENTIRETY.	LEGEND, ABBREVIATIONS, ETC., REFER TO GI SERIES SHEETS. B. UNLESS NOTED OTHERWISE ON THIS SHEET, THE GENERAL CONTRA
33 DEMOLISH EXISTING TERRAZZO, CONCRETE SLAB AND INSULATION TO BASE SLAB BELOW COMPLETE.	RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL WORK INDICATED THIS SHEET.
34 DEMOLISH BRICK, MASONRY AND CONCRETE STOOP COMPLETE. 35 EXISTING DOOR FRAME TO REMAIN. REMOVE DOOR, TRANSOM AND	C. CONTRACTORS ENCOUNTERING EXISTING MATERIAL WHICH IS SUSPECT CONTAINING ASBESTOS SHALL STOP WORK IMMEDIATELY AND NOTIFY
HARDWARE. 36 REMOVE HOLLOW METAL FRAME AND GLAZING IN ITS ENTIRETY.	OWNER AND THE OWNERS REPRESENTATIVE. D. BOLD DASHED LINES INDICATE EXISTING ITEMS TO BE REMOVED UN
<ul> <li>REMOVE ACOUSTICAL PANELS IN THEIR ENTIRETY. PATCH AND REPAIR WALLS AS REQUIRED TO RECEIVE NEW FINISHES.</li> <li>REMOVE CERAMIC TILE WALL SYSTEM IN ITS ENTIRETY. PREPARE EXISTING</li> </ul>	OTHERWISE NOTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXTENT OF DEMOLITION WORK PRIOR TO BIDDING A COORDINATING THE EXTENT OF DEMOLITION WITH THE INSTALLATION SYSTEMS.
WALL AS REQUIRED TO RECEIVE NEW FINISHES. 39 <u>ALTERNATE</u> : DEMOLISH, PATCH AND REPAIR WALL CONSTRUCTION TO RECEIVE NEW DOOR. GRIND AND PREPARE FLOOR AS REQUIRED.	E. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DEMOLITION APPLICABLE TO THEIR SCOPE OF WORK AND AS REQUIRED FOR INSTALLATION OF NEW WORK WHETHER OR NOT IT IS SPECIFICALLY INDICATED OR NOTED IN THESE DOCUMENTS.
<ul> <li>40 REMOVE BRICK BENCH IN ITS ENTIRETY. PREPARE FLOOR AND WALL AS REQUIRED.</li> <li>41 BUSH HAMMER EXISTING TERRAZZO AS REQUIRED FOR NEW LEVEL FLOOR FINISHES. PROVIDE LEVELING COMPOUND AS REQUIRED.</li> </ul>	F. REMOVE ALL ITEMS AND FINISHES MADE OBSOLETE BY NEW CONST VERIFY ITEMS DEEMED OBSOLETE WITH ARCHITECT PRIOR TO REMOV REFER TO NEW CONSTRUCTION DRAWINGS FOR DEMOLITION REQUIR
<ul><li>42 REMOVE WOOD TRIM, TACKABLE WALL COMPLETE.</li><li>43 REMOVE TACKABLE WALL PANEL COMPLETE.</li></ul>	SHOWN ON DEMOLITION PLANS. G. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR OFF SITE REMOVA ALL DEMOLITION MATERIALS AND/OR ITEMS UNLESS NOTED OTHERW
44 <u>ALTERNATE</u> : REMOVE MASONRY WALL AS REQUIRED FOR NEW CONSTRUCTION. PATCH AND REPAIR FLOOR AND WALL AS REQUIRED TO ACCEPT NEW FINISHES.	DIRECTED BY THE OWNER. H. PRIOR TO STARTING DEMOLITION, CONSTRUCT DUST CONTROL BARR REQUIRED TO PREVENT THE SPREAD OF DUST INTO SURROUNDING
<ul> <li>45 REMOVE PORTION OF EXISTING LIMESTONE PANEL AS REQUIRED FOR NEW CONSRTUCTION.</li> <li>46 REMOVE PORTION OF EXISTING BULKHEAD FRAMING TO MATCH NEW 9'-0" BULKHEAD.</li> </ul>	<ul> <li>(WHERE APPLICABLE).</li> <li>I. WHERE BUILDING EGRESS IS REQUIRED TO PASS THROUGH DEMOLI AREAS, PROVIDE APPROVED BARRIERS, ETC. TO ENSURE SAFETY OF</li> </ul>
47 REMOVE EXISTING BULKHEAD EXTENSION FROM PREVIOUS PROJECT, PREPARE FOR RE FRAMING TO MATCH NEW 9'-0" BULKHEAD.	PUBLIC. J. RELOCATED ITEMS SHALL BE CLEANED AND PLACED IN STORAGE, F OWNERS' DIRECTION, UNTIL ITEMS ARE READY TO BE INSTALLED. IF
48 ALTERNATE: EXISTING DOOR FRAME TO REMAIN. REMOVE EXISTING DOOR, HARDWARE, AND TRANSOM TO ACCEPT NEW DOOR AND HARDWARE 49 REMOVE EXISTING CANOPY IN ITS ENTIRETY INCLUDING STEEL FRAMING, ROOFING AND CONCRETE FOOTINGS AS REQUIRED FOR NEW CONSTRUCTION.	ARE DAMAGED DURING DEMOLITION OR RELOCATION, THEY SHALL B REPAIRED OR REPLACED WITH NEW ITEMS AS APPROVED. K. DEMOLITION SHALL BE PERFORMED WITHOUT DAMAGE TO EXISTING
50 AREA OF MODIFIED SAG ROD ASSEMBLY TO ACCOMMODATE NEW CONSTRUCTION. REMOVE PORTIONS OF EXISTING CHANNEL. ENSURE SAG ROD ASSEMBLY HAS MINIMUM OF 3 SAG RODS PER RUN AND SPACED AT	CONSTRUCTION TO REMAIN. WHERE SUCH DAMAGE OCCURS, PATCH OR RESTORE WALLS, FLOORS, CEILING, ETC. NEATLY TO MATCH EX ADJACENT SURFACE. PROVIDE SHORING, BRACING, OR SUPPORT AS REQUIRED TO PREVENT MOVEMENT OR SETTLEMENT OF EXISTING
AD-2 MAXIMUM OF 48" APART. INSTALL NEW SAG ROD AND CHANNEL ASSEMBLY TO ENSURE WALL STABILITY ABOVE. 51 REMOVE PORTION OF BRICK AND MASONRY WALL TO RECEIVE NEW LOUVER.	L. EACH CONTRACTOR IS RESPONSIBLE FOR CUTTING, PATCHING, AND DISCONNECTION OF ITEMS APPLICABLE TO THEIR SCOPE OF WORK.
TOOTH IN SALVAGED BRICK AS REQUIRED. 52 DEMOLISH EXISTING SAG ROD ASSEMBLY TO ACCOMMODATE NEW CONSTRUCTION.	EXISTING SERVICES ARE ABANDONED, CAP AT LEAST 1" BEHIND NE FINISHES AND/OR EXISTING SURFACE AND PATCH AS REQUIRED TO NEW FINISHES OR MATCH EXISTING FINISH.
53 REMOVE CONTINUOUS BACK SPLASH AND WALL CABINETS COMPLETELY. 54 DEMOLISH EXISTING TERRAZZO AND INFILL WITH LIGHTWEIGHT CONCRETE. PREP AND DOWEL EXISTING AND NEW SLAB, REFER TO STRUCTURAL	M. ON WALLS THAT ARE TO RECEIVE NEW FINISHES, REMOVE AND REIL EXISTING EQUIPMENT TO REMAIN AS REQUIRED FOR INSTALLATION ( FINISHES.
55 DEMOLISH EXISTING TERRAZZO AND CONCRETE SLAB COMPLETE. 56 LINE OF SLAB DEMOLITION.	N. WHERE WALLS OR BULKHEADS ARE REMOVED, PATCH FLOORS, CEIL AND ADJACENT WALLS AS REQUIRED TO MATCH EXISTING OR RECE FINISHES WHERE APPLICABLE. WHERE EXISTING DUCTWORK, PIPING, EQUIPMENT IS REMOVED, PATCH OPENINGS AND/OR SURFACES AS
AD-2 57 REMOVE EXISTING COOLER FREEZER IN ITS ENTIRETY. 58 MODIFY METAL STUD AND GYPSUM BOARD WALL ASSEMBLY TO RECEIVE NEW VUV CONSTRUCTION.	REQUIRED TO MATCH ADJACENT SURFACES OR RECEIVE NEW FINISH WHERE APPLICABLE. REFER TO ALL DEMOLITION DRAWINGS FOR E OF ITEMS TO REMOVED.
59       DEMOLISH EXISTING KITCHEN AND ALL ASSOCIATED FIXTURES, EQUIPMENT,         KITCHEN RELATED DUCTWORK AND ACCESSORIES COMPLETE.         60         SELECTIVELY DEMOLISH EXISTING ROOF STRUCTURE AND DECKING COMPLETE	O. OVER CUT NEW OPENINGS IN EXISTING WALL AS REQUIRED FOR NE CONSTRUCTION. PATCH AND REPAIR WALLS AS REQUIRED TO MATCH EXISTING. WHERE APPLICABLE, TOOTH NEW MASONRY INTO EXISTING MASONRY.
TO ACCEPT NEW BUILDING CONSTRUCTION. REFER TO NEW CONSTRUCTION. REFER TO NEW CONSTRUCTION FOR ADDITIONAL INFORMATION. 61 SELECTIVELY DEMOLISH EXISTING BUILDING FASCIA, COPING, METAL PANEL	P. ALL EQUIPMENT AND FURNITURE WHICH ARE CONSIDERED LOOSE FURNISHING SHALL BE REMOVED BY THE OWNER PRIOR TO DEMOL
<ul> <li>SYSTEM AND SOFFIT COMPLETE TO ACCEPT NEW BUILDING CONSTRUCTION. REFER TO NEW CONSTRUCTION FOR ADDITIONAL INFORMATION.</li> <li>DEMOLISH ENTIRE CANOPY COMPLETE. REMOVE STRUCTURE AND CONCRETE FOOTINGS COMPLETE TO ACCEPT NEW CONSTRUCTION.</li> </ul>	Q. MASONRY WALLS TO BE REMOVED SHALL BE REMOVED TO A POINT MINIMUM BELOW THE EXISTING FLOOR SLAB UNLESS SETTING ON A OR SPECIFICALLY NOTED OTHERWISE. PATCH WITH NEW CONCRETE FLUSH WITH THE EXISTING FLOOR SLAB.
	R. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR GENERAL REVIEW DEMOLITION NOTES AND GENERAL DEMOLITION NOTES AS THEY APP THEIR SCOPE OF WORK.
	S. THE OWNER SHALL RESERVE THE RIGHT TO CLAIM ANY MATERIALS ARE BEING DEMOLISHED PRIOR TO THE CONTRACTOR DISPOSING OI OFF SITE.
	T. REFER TO THE STRUCTURAL, MECHANICAL, PLUMBING, ELECTRICAL A TECHNOLOGY DOCUMENTS FOR COMPLETE SCOPE OF DEMOLITION V
	U. "FLOORING" DENOTES FLOOR COVERING MATERIALS INCLUDING BACK ADHESIVES, AND BASES DOWN TO BUT EXCLUSIVE OF FLOOR SLAB STRUCTURAL MATERIALS UNLESS NOTED OTHERWISE.
	V. DEMOLITION IS TO FOLLOW ESTABLISHED CONSTRUCTION SEQUENCE TO SPECIFICATIONS AND DRAWINGS FOR REQUIREMENTS AND SPECI CONDITIONS.
	W. WHERE APPLICABLE SALVAGE EXISTING MASONRY (FACE BRICK, GLA CMU, FACING TILE) AS REQUIRED FOR PATCHING AND INFILL IN RE AREAS WHERE INDICATED. DISCARD UNUSED PORTION OFF SITE.
	<ul> <li>X. PROVIDE TOPPING SLAB AND FLOOR LEVEL AS REQUIRED FOR APP OF NEW CONDITIONS.</li> <li>Y. NEW CMU CONSTRUCTION SHALL NOT BEAR ON EXISTING TERRAZZO</li> </ul>
AD-2	CONCRETE TOPPING SLAB. DEMOLISH TERRAZZO AND EXISTING CON SLAB BELOW WHERE OCCURRING.
	DEMOLITION PLAN NOTES: (ALL PLAN NOTES MAY NOT BE INDICATED ON THIS SHEET.)
	<ol> <li>REMOVE ALUMINUM WINDOW AND/OR STOREFRONT FRAMING, DOOR HARDWARE IN ITS ENTIRETY. REPAIR JAMB AND FLOOR AS REQUIR NEW FINISH.</li> <li>REMOVE ACOUSTICAL BOARD CEILING SYSTEM IN ITS ENTIRETY.</li> </ol>
	3 REMOVE CARPET FLOORING SYSTEM AND BASE IN ITS ENTIRETY. F EXISTING CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHE 4 DEMOLISH AND PREPARE EXISTING CONCRETE SURFACE TREATMEN
	RECEIVE NEW CONSTRUCTION.         5       REMOVE VINYL TILE FLOORING SYSTEM IN ITS ENTIRETY. PREPARE CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES.
	6 REMOVE CERAMIC TILE FLOORING SYSTEM IN ITS ENTIRETY. PREPA EXISTING CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHE PROVIDE LEVELING COMPOUND AS REQUIRED.
	<ul> <li>REMOVE DISPLAY WALL, CHALK, MARKER, AND/OR TACKBOARDS IN ENTIRETY.</li> <li>REMOVE EXISTING BUILT-IN CASEWORK.</li> </ul>
	<ul> <li>9 REMOVE PORTION OF MASONRY WALL AS REQUIRED TO INSTALL N</li> <li>10 REMOVE PLUMBING FIXTURES COMPLETE. REFER TO PLUMBING DR</li> <li>WHERE PIPING IS REQUIRED TO BE CAPPED, CAP BELOW AND/OR</li> </ul>
	FINISHED SURFACE.          11       REMOVE TOILET PARTITIONS IN THEIR ENTIRETY.         12       REMOVE MASONRY WALL (AS REQUIRED FOR NEW CONSTRUCTION.)
	AND REPAIR FLOOR AND WALL AS REQUIRED TO ACCEPT NEW FIN 13 REMOVE HOLLOW METAL FRAME, TRANSOM, DOOR AND HARDWARE ENTIRETY.
	14       REMOVE EXISTING LOCKERS IN THEIR ENTIRETY.         15       REMOVE CONCRETE SHOWER CURB. PATCH AND REPAIR FLOOR AS REQUIRED TO ACCEPT NEW FINISHES.         16       REMOVE METAL STUDS AND CYPSUM BOARD WALL AS REQUIRED FOR AND CYPSUM BOARD WALL BOARD WALL AS REQUIRED FOR AND CYPSUM BOARD FOR AND FOR AN
	<ul> <li>[16] REMOVE METAL STUDS AND GYPSUM BOARD WALL AS REQUIRED F NEW CONSTRUCTION. PATCH AND REPAIR FLOOR AND WALLS AS F TO ACCEPT NEW FINISHES.</li> <li>[17] REMOVE EXISTING BLEACHERS IN THEIR ENTIRETY.</li> </ul>
	18REMOVE METAL LOCKERS. REMOVE CONCRETE BASE AS REQUIRED NEW CONSTRUCTION.19REMOVE DISPLAY CASE IN ITS ENTIRETY.
	<ul> <li>20 REMOVE MEDIA SHELVING IN ITS ENTIRETY.</li> <li>21 REMOVE BASKETBALL GOALS IN THEIR ENTIRETY.</li> <li>22 REMOVE EXISTING FLOOR DRAIN. REFER TO PLUMBING DRAWINGS.</li> </ul>
	23 REMOVE SCOREBOARD AND TURN OVER TO OWNER. 24 REMOVE VOID SLAB/STOOP/STEPS/RAMP AS REQUIRED FOR NEW
	25 REMOVE OKREVIN METAL STUD DULKHEAD COMPLETE. 26 REMOVE METAL BOOKSHELVES AND CASEWORK COMPLETE. PATCH
AD-2	REPAIR WALL TO MAKE LIKE NEW CONDITION.         27         REMOVE WALL COVERING IN ITS ENTIRETY. PREPARE WALL FOR NEW
	FINISHES. 28 REMOVE TERRAZZO FLOORING SYSTEM IN ITS ENTIRETY. PREPARE CONCRETE SLAB AS REQUIRED TO RECEIVE NEW FINISHES. PROVID
NE FLOOR DEMOLITION PLAN	LEVELING COMPOUND AS REQUIRED. 29 REMOVE MECHANICAL UNIT. REFER TO MECHANICAL DRAWINGS.
	[30] REMOVE CEILING MOUNTED MECHANICAL UNIT IN ITS ENTIRETY. RE MECHANICAL DRAWINGS.
















ע הא ש - LAST SAVED TIMOTHY BALL | 112 DRAWINGS\0 Thursday, 3/3/2022 - 8:42 AM -Y:\21-112 CROWN POINT CSC - T ADDITION AND RENOVATIONS\21-11: ARCH\A-102.DWG























Thursday, 3/3/2022 - 8:51 AM - LAST SAVED BY: Y:\21-112 CROWN POINT CSC - TIMOTHY BALL ES ADDITION AND RENOVATIONS\21-112 DRAWINGS\05 ARCH\A-401.DWG






	****		 XXXX	<u>~~~</u>		 	 	 XXXX		 XXXX		 XXXX	 XXXX		 XXXX	 XXXX	 XXXX			 XXXX		 XXXX			 XXXX		<u></u>
	- 0			0				0				- 0		5731Kaskasaa		0				0				0			с
		X			C L A		SRC		4	X								X				ASS (5)	RC	NO	1	X	
	- 0			0		0	S	0				0				0				0		<u>(</u> S		0			- (
		X			A(	CT- 7-4	∙1 ."			X								X				AC				X	
	- 0			0				0				- 0				0				0				0			- (
	175522015		Horiz R.					, eiserte trade									<u>asy</u>				1 			 2445			
2412 504												).  -  -														$\square$	
	0				(S) (O)	0					0		RF		<u>DR</u>	0		9'—	0"_	\$ 0	0					0	
					<b>O</b>			Д					ACT 9'-	 1 "_									/9'·				
									30,000 12	* ******			9 -	· 4						$\mathbf{k}$	2					<u>ا</u>	
											5.25-29-0				7			ALCONT OF	<u></u>		3.58,649						<u> </u>
				╎┍					0			- 0				0				0		-		0			┢
	_ 0																					14474488					Ļ
			$\vdash$	-	-	-				Щ			C	LAS	SSF		)M	囚		_						Щ	┝
		0	Р											-304								010 AV'W					-
	0	AC1	$\frac{1}{1-1}$	; , ,					0			- 0				0				0				0			
			Ļ	╷┖											(S) 1												-
			<b>FAII</b> 300)	<b>R</b>									9	CT- )'-4	"							57785428					
										X								X									_
	- 0				0 -				0			0				0				0		1912 S.S.S.		0		Д	
																						30000000					
							Ø																			1	








(S) ○ −0" ○ −0" ○ ⊂(T−2 (CT−2 (-4") ○
4 BO BO B 19 C B 19
С С С С С С С С С С С С С С
50 177) -1 -4" -4" -4" -4" -4" -4" -4" -4"

UNIT "B" FIRST FLOOR REFLECTED CEILING PLAN






# GENERAL REFLECTED CEILING PLAN NOTES:


- A. FOR GENERAL PROJECT NOTES, MATERIAL INDICATIONS LEGEND, SYMBOL
- LEGEND, ABBREVIATIONS, ETC., REFER TO GI SERIES SHEETS. B. THE ARCHITECTURAL REFLECTED CEILING PLAN GOVERN THE LAYOUT OF ALL
- CEILING ELEMENTS AND PENETRATIONS. C. BULKHEAD FRAMING SHALL BE ATTACHED TO STRUCTURAL SUPPORTS AND
- NOT THE ROOF DECK. D. REFER TO FLOOR PLANS FOR WALL TYPES
- REFER TO ELECTRICAL DRAWINGS FOR ADDITIONAL CEILING MOUNTED
- ELECTRICAL ITEMS. REFER TO TECHNOLOGY DRAWINGS FOR ADDITIONAL CEILING MOUNTED
- TECHNOLOGY ITEMS.
- REFER TO MECHANICAL DRAWINGS FOR LOCATION OF CEILING DIFFUSERS, RETURN AIR GRILLS, AND CEILING CABINET HEATERS.
- PROVIDE RADIUS PERIMETER ANGLE TRIM CORNERS AT BULLNOSE CONCI MASONRY UNIT CORNERS.
- PAINT BULKHEADS P2, UNLESS NOTED OTHERWISE.


### REFLECTED CEILING PLAN LEGEND: O LED LIGHT GYPSUM BOARD 1×4 LIGHT FIXTURE BULKHEAD/CEILING \_\_\_\_\_ 2x4 LIGHT FIXTURE EFS SOFFIT PENDANT LIGHT FIXTURE (S) SPEAKER O OCCUPANCY SENSOR 2'-0" x 2'-0" ACST. BD. CEILING SEE FINISH LEGEND SUPPLY AIR DIFFUSER RETURN, EXHAUST, AND TRANSFER AIR GRILLE

## **REFLECTED CEILING PLAN NOTES:**

- (ALL PLAN NOTES MAY NOT BE INDICATED ON THIS SHEET.) ) GYPSUM BOARD BULKHEAD. —
- (A-905) 2) 2" W. SOFFIT VENT. LENGTH AS INDICATED.
- 3) SOFFIT "V" JOINT
- 4) OPEN TO STRUCTURE ABOVE NO CEILING REQUIRED
- 5) PAINT BULKHEAD P5. (6) GYM EQUIPMENT, REFER TO EQUIPMENT DRAWINGS.
- ) 4"X4" STAINLESS STEEL CLOSURE TRIM BETWEEN FACE OF COOLER AND CEILING GRID REFER TO KITCHEN EQUIPMENT DRAWINGS
- 8) EXISTING PLASTER SOFFIT TO REMAIN. REMOVE LOOSE OR WATER DAMAGED PLASTER AND PATCH CRACKS AND/OR HOLES WITH BASE COAT. APPLY ELASTOMERIC ODATING ON ENTIRE PLASTER SOFFIT SURFACE. (ESTIMATE 75/LINEAR FEET OF 6" WIDE CRACKED OR LOOSE SURFACE THAT WILL NEED TO BE REMOVED AND REPLACED.)
- (10) GYPSUM BØARD BULKHEAD REFRAMING OF EXISTING BULKHEAD. 11) GYPSUM BOARD BULKHEAD CAP OF EXISTING BULKHEAD AFTER REMOVAL OF EXISTING BULKHEAD EXTENSION.









# UNIT "C" ARCHITECTURAL FIRST FLOOR PLAN

	GENERAL REFLECTED CEILING PLAN NOTE         A. FOR GENERAL PROJECT NOTES, MATERIAL INDICATIONS LEGEND, SYMBULEGEND, ABBREVIATIONS, ETC., REFER TO GI SERIES SHEETS.         B. THE ARCHITECTURAL REFLECTED CEILING PLAN GOVERN THE LAYOUT OF CEILING ELEMENTS AND PENETRATIONS.         C. BULKHEAD FRAMING SHALL BE ATTACHED TO STRUCTURAL SUPPORTS NOT THE ROOF DECK.         D. REFER TO FLOOR PLANS FOR WALL TYPES         E. REFER TO TECHNOLOGY DRAWINGS FOR ADDITIONAL CEILING MOUNTED ELECTRICAL ITEMS.         F. REFER TO TECHNOLOGY DRAWINGS FOR ADDITIONAL CEILING MOUNTED TECHNOLOGY ITEMS.         G. REFER TO MECHANICAL DRAWINGS FOR LOCATION OF CEILING MOUNTED TECHNOLOGY ITEMS.         R. REFER TO MECHANICAL DRAWINGS FOR LOCATION OF CEILING DIFFUSE RETURN AIR GRILLS, AND CEILING CABINET HEATERS.         H. PROVIDE RADIUS PERIMETER ANGLE TRIM CORNERS AT BULLINOSE COMMASONRY UNIT CORNERS.         I. PRINT BULKHEADS P2, UNLESS NOTED OTHERWISE. <b>REFER TO MECHANICAL DRAWINGS FOR LOCATION OF CEILING DIFFUSE MEDILECTED CEILING PLAN LEGEND:</b> Image: Soffit         Image: Soffit         Image: Soffit         Image: Soffit         Image: Soffit         Image: Soffit         Image: Soffit Tor Soft Soft Tor SUPPLY AIR DIFFUSER <b>REFELECTED CEILING PLAN NOTES:</b> (ALL PLAN NOTES MAY NOT BE INDICATED ON THIS SHEET.)         Image: Soffit Tor SINCURE ABOVE - NO CEILING REQUIRED
	<ul> <li>DAMAGED PLASTER AND PATCH CRACKS AND/OR HOLES WITH BASE APPLY ELASTOMERIC COATING ON ENTIRE PLASTER SOFFIT SURFACE (ESTIMATE 75 LINEAR FEET OF 6" WIDE CRACKED OR LOOSE SURF THAT WILL NEED TO BE REMOVED AND REPLACED.)</li> <li> <ul> <li></li></ul></li></ul>
ACT-1 $g'-4"$ $g'-4$	
REFLECTED CELLING PLAN NOTES ADDED IN ADDENDUM 2	






Wednesday, 3/2/2022 - 4:45 PM - LAST SAVED BY:JONATHAN NIKIEL G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-PLAN.DWG


	GENE	RAL SYMBOL LEGEND		DR
			SHEET	DRAWING NAM
		EQUIPMENT ITEM NUMBER	K-100 K-101	FOODSERVICE E
			K102 K-200	FOODSERVICE E
(к700)-		ENLARGED PLAN CALL OUT	K-300 K-301	FOODSERVICE E
			K-400 K-500	WALK-IN COOLE
		EQUIPMENT ELEVATION CALL OUT	K-501 K-502	EXHAUST VENTI
			K-600	FOODSERVICE E
	L	EQUIPMENT DETAIL CALL OUT	K-601 K-602	FOODSERVICE E
K7	00		K-603	FOODSERVICE E
1 K700		EQUIPMENT SECTION CALL OUT		
E	1	SPOT LOCATION CALL OUT		
	Р	LUMBING LEGEND		
H	SINGLE HOT	WATER CONNECTION		
C	SINGLE COLI	WATER CONNECTION		
H C	DOUBLE HO.	F & COLD WATER CONNECTION		
 		TE CONNECTION		
	INDIRECT WAS			
		"x12" FLOOR SINK		
	INDIRECT 12	"x12" FLOOR SINK WITH HALF GRATE		
G	GAS CONNE	CTION		
S	STEAM SUPF	PLY CONNECTION		
R	STEAM RETU	IRN CONNECTION		
A	COMPRESSE	D AIR CONNECTION		
		ECTRICAL/PLUMBING SCHEDULES NFORMATION ON THIS EQUIPMENT		AB
	EI	ECTRICAL LEGEND	AFF AGA	ABOVE FINISHEE
	DEDICATED	ELECTRICAL CONNECTION	AMPS ARCH	AMPERAGE ARCHITECTURAL
<b>•</b>		ELECTRICAL CONNECTION (DFA)	BLDG BTU	BUILDING BRITISH THERM
_			CLG CMU	CEILING CONCRETE MAS
		ELECTRICAL CONNECTION (STUB)	CONN CONST	CONNECTION CONSTRUCTION
<u> </u>	DUPLEX CON	IVENIENCE OUTLET	CW DCO	COLD WATER
	SPECIAL PUR	POSE CONVENIENCE OUTLET	DFA	DROP FROM AB
- <b>u</b>	FIRE SUPPRE	SSION SYSTEM PULL STATION	DIM DWG	DIMENSION DRAWING
J	JUNCTION B	OX LOCATED ON EQUIPMENT	EC ED	ELECTRICAL CON
D	DISCONNEC	SWITCH LOCATED ON EQUIPMENT	ELEC EXIST	ELECTRIC, ELECT EXISTING
Т	DEFROST TIN	/IE CLOCK LOCATED ON EQUIPMENT	FLR DRN FLR SINK	FLOOR DRAIN FLOOR SINK
ц	EQUIPMENT	MOUNTED RECEPTACLE	FLR TRGH GA	FLOOR TROUGH
D	TELEPHONE,	DATA CONNECTION		CONTRACTOR
•		ECTRICAL/PLUMBING SCHEDULES NFORMATION ON THIS EQUIPMENT	0	OTHERS
			HP	HORSEPOWER
	NO	TE CALLOUT LEGEND	HVAC HW	HEATING, VENTI HOT WATER
$\bigcirc$			ID KEC	INSIDE DIAMETE KITCHEN EQUIPI
(A)		REQUIRING WATER FILTRATION	KW MAX	KILOWATT MAXIMUM
B	STAINLESS S	TEEL UTILITY CHASE	MBTU MC	1,000 BTU'S MECHANICAL CO
C	FIRE SUPPRE	MD	MECHANICAL DI	
D	WALK-IN CO	MECH MFG	MECHANICAL MANUFACTURE	
			MIN MISC	MINIMUM MISCELLANEOU
			NIC NTS	NOT IN CONTRA NOT TO SCALE
			OC OD	ON CENTER OUTSIDE DIAME
			PC PD	PLUMBING CON
			РН	PHASE
			PSI R	POUNDS PER SO RADIUS
			ST STL SHT	STAINLESS STEEL
			S/S STD	STAINLESS STEEL
			STUB TYP	STUB UP FROM
			V	VOLTAGE
			VOLT	VOLTAGE

# **RAWING SHEET INDEX**

## **GENERAL DRAWING SET NOTES**

ME EQUIPMENT GENERAL NOTES & SHEET INDEX EQUIPMENT SPECIAL CONDITIONS PLAN EQUIPMENT SPECIAL CONDITION SCHEDULES EQUIPMENT SPECIAL CONDITION SCHEDULES EQUIPMENT ELECTRICAL PLAN EEQUIPMENT ELECTRICAL PLAN EEQUIPMENT ELECTRICAL PLAN EEQUIPMENT SYSTEM DRAWING, DETAILS & SCHEDULE TITATION SYSTEM DRAWING, DETAILS & SCHEDULE EQUIPMENT DETAILS, ELEVATIONS & SECTIONS EQU	THEY DEALWISE ANY EFFERIDULTS USING A GRIVEN ASSAULTMENT OF FULLIMENT HIGH DATA THE MERGING THAT AND MAY THE MERGING THE ASSAULTMENT HIGH DATA THE MERGING THAT AND MAY THE MERGING THE ASSAULTMENT HIGH DATA THE MERGING THAT AND MAY THE MERGIN
IPMENT CONTRACTOR	GENERAL EQUIPMENT NOTES
CONTRACTOR DIVISION	1. EQUIPMENT WHICH IS FIXED AND WHERE IT ABUTTS OTHER FIXED EQUIPMENT, BUILDING WALLS OR FLOOR SHALL SEALED THERETO WITH SILICONE. GAPS BETWEEN EQUIPMENT EXCEEDING 1/8" IN WIDTH MUST BE TRIMMED OU WITH STAINLESS STEEL ANGLED TRIM OR MATCHING MATERIAL TRIM PRIOR TO BEING SEALED.
RER DUS RACT E METER DNTRACTOR VISION SQUARE INCH EEL EEL	<ul> <li>WITH STAINLESS STEEL ANGLED TRIM OR MATCHING MATERIAL TRIM PRIOR TO BEING SEALED.</li> <li>HOT WATER SUPPLY TO ALL FOOD PREPARATION AND THREE COMPARTMENT SINKS SHALL BE 120 DEGREES MINIM HOT WATER SUPPLY TO ALL DISHMACHINES SHALL BE 140 DEGREES MINIMUM.</li> <li>ALL COUNTERS ARE TO BE FABRICATED PROPERLY TO SUPPORT THE SPECIFIED COUNTER TOP MATERIAL IN ACCORDANCE WITH THE MATERIAL MANUFACTURER'S GUIDELINES. ALL "DROP-IN" EQUIPMENT AND OTHER EQUIPMENT "ATTACHED TO", "SET ON" OR "BUILT-IN" TO THE COUNTER TOP MATERIAL TO BE INSTALLED IN ACCORDANCE WITH THE MATERIAL MANUFACTURER'S GUIDELINES AND TECHNICAL BULLETINS FOR THE INSTALLA OF COMMERCIAL FOOD SERVICE EQUIPMENT.</li> <li>ALL FOOD SERVICE EQUIPMENT SHALL BE MANUFACTURED, FABRICATED, FURNISHED &amp; INSTALLED IN STRICT ACCORDANCE WITH, AND BEAR THE EMBLEM OF, THE NATIONAL SANITATION FOUNDATION (NSF) AS WELL AS AN' FEDERAL, STATE &amp; LOCAL CODE REQUIREMENTS.</li> <li>ALL REFRIGERATION EQUIPMENT SHALL HAVE A THERMOMETER WHICH IS EASILY READABLE IN PROPER WORKING CONDITION.</li> </ul>







Wednesday, 3/2/2022 - 4:36 PM - LAST SAVED BY:JONAT G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-PLAN.DWG

FOODSERVICE EQUIPMENT PLAN

В

(34) (13) (13)			EQUIPMEN	T SCHEDULI	
	ITEM	QTY		MANUFACTURER	MODEL
	1 2	1	WALK-IN COOLER/FREEZER WALK-IN COOLER COIL	KOLPAK PART OF ITEM #1	CUSTOM
	3	1 LOT	WALK-IN COOLER COMPRESSOR HI-DENSITY TOP TRACK COOLER SHELVING	PART OF ITEM #1 INTERMETRO	METROMAX Q
	5 6	1	COOLER DUNNAGE RACK COOLER MOBILE SHELVING UNIT	INTERMETRO INTERMETRO	HP2248PDMB METROMAX Q
	7 8	1	WALK-IN FREEZER COIL WALK-IN FREEZER COMPRESSOR	PART OF ITEM #1 PART OF ITEM #1	
	9 10	6	FREEZER MOBILE SHELVING UNIT FREEZER DUNNAGE RACK	INTERMETRO INTERMETRO	METROMAX Q HP22**PDMB
	11	LOT	HI-DENSITY TOP TRACK DRY STORAGE SHELVING	INTERMETRO	METROMAX Q
	12 13	2	DRY STORAGE DUNNAGE RACK DRY STORAGE MOBILE SHELVING UNIT	INTERMETRO INTERMETRO	HP22**PDMB METROMAX Q
	14 15	1 4	ISLAND WORKTABLE W/ 2 COMP SINK WALL MOUNT HAND SINK	CUSTOM JOHN BOOS	ST. STL. PBHS-W-1410-1-SSLR
	16 17	4	HAND SINK FAUCET ISLAND WORKTABLE W/ PREP SINKS	T&S BRASS CUSTOM	5EF-1D-WG ST. STL.
	18 19	2 1	SPLASH MOUNT FAUCET GARBAGE DISPOSAL SYSTEM	T&S BRASS	MPZ-8WLN-08-CR SS-200-7-AS101
	20 21	*6	HEAVY-DUTY BUN PAN RACK COUNTERTOP MIXER W/ STAND	CHANNEL HOBART CORPORATION	401A HL200-1STD
	22	1	SLICER	HOBART	HS8-1
	23 24	1	MOBILE WORKTABLE ICE MAKER W/ BIN	CUSTOM MANITOWOC ICE	CUSTOM IYT0420A
	25 26	1 1	WORKTABLE MICROWAVE	CUSTOM PANASONIC	ST. STL. NE-1064F
	27 28	2 2	KITCHEN MOBILE SHELVING UNIT SINGLE DOOR PASS THRU HEATED CABINET	INTERMETRO TRAULSEN	METROMAX Q AHF132WP-FHG
	29 30	2	SINGLE DOOR PASS THRU REFRIGERATOR	TRAULSEN CUSTOM	AHT132WPUT-FHG CUSTOM
	31 32	1	FIRE SUPPRESSION SYSTEM	PART OF ITEM #30 PART OF ITEM #30	
	33	1	COOKLINE EXHAUST FAN	PART OF ITEM #30	
	34 35	1	COOKLINE MAKE UP AIR FAN COMBI OVEN/STEAMER (STACKED)	PART OF ITEM #30 RATIONAL	ICC 10-FULL/ICC 6-FULL
	36 37	1	COMBI OVEN/STEAMER FILTER 40 GALLON TILT SKILLET	RATIONAL CLEVELAND	1900.1150US SGL40T1
	38 39	1	FLOOR TROUGH FOUR BURNER RANGE WITH OVEN BASE	CUSTOM MONTAGUE	ST. STL. 124-5
	40 41	1	DOUBLE STACKED CONVECTION OVEN SPARE NUMBER	SOUTHBEND	SLGB/22SC
	42		SPARE NUMBER		
92	43 44		SPARE NUMBER SPARE NUMBER		
91	45 46	1	THREE COMPARTMENT SINK WALL SHELF	CUSTOM CUSTOM	ST. STL. ST. STL.
	47 48	2 2	SPLASH MOUNT FAUCET SPLASH MOUNT PRE-RINSE FAUCET	T&S BRASS T&S BRASS	B-0290 B-0133-CR-B-SWV
	49 50	1	GARBAGE DISPOSAL SYSTEM SOILED DISH TABLE	INSINKERATOR CUSTOM	SS-200-7-AS101 CUSTOM
	51 52	1	DISH MACHINE W/BOOSTER HEATER DISH MACHINE BLOWER DRYER	HOBART	CL44EN-BAS+BUILDUP BDELRAB-HTSDOM
	53	2	DISH MACHINE VENT COWL	PART OF ITEM #54	
	54 55	1	DISH MACHINE EXHAUST FAN CLEAN DISH TABLE	CUSTOM CUSTOM	CUSTOM CUSTOM
	56 57	1	WALL SHELF MOBILE DRYING RACK	CUSTOM INTERMETRO	CUSTOM PR36VX2-XDR
	58 59	1	MOBILE DRYING RACK MOBILE DRYING RACK	INTERMETRO INTERMETRO	PR36VX3-XDR PR48VX4-XDR
	60 61	LOT	TRASH CONTAINERS SPARE NUMBER	BY OWNER	NOT IN KEC CONTRACT
	62	1	SPARE NUMBER JANITORIAL MOP SINK		9-OP-20
	63 64	1	CHEMICAL SHELVING UNIT	ADVANCE TABCO INTERMETRO	SEC53C
	65 66	1	WASHER/DRYER STAINLESS STEEL WALL CABINET	BY OWNER ADVANCE TABCO	NOT IN KEC CONTRACT WCH-15-60
	67 68	6 1	LOCKERS (FULL SIZE) MILK COOLER	BY ARCHITECT TRUE	NOT IN KEC CONTRACT TMC-49-DS-HC
	69 70	1	MOBILE HOT SERVING COUNTER DROP-IN HOT/COLD WELL UNIT	CUSTOM LTI	ST. STL./MILLWORK DI-QSCHP-4
	71 72	1	SELF-SERVE BREATH GUARD W/LIGHTS MOBILE COLD SERVING COUNTER	VERSA GARD CUSTOM	VG7 ST. STL./MILLWORK
	73	1	DROP-IN COLD WELL UNIT	LTI	DI-2063TA
	74 75	1	SELF-SERVE BREATH GUARD W/LIGHTS MOBILE DRY GOODS SERVING COUNTER	VERSA GARD CUSTOM	VG7 ST. STL./MILLWORK
	76 77	1 6*	ICE CREAM FREEZER MOBILE TRAY DISPENSERS	BEVERAGE AIR DELFIELD	NC28HC-1-W TT-1014
	78 79	1	MILK COOLER MOBILE HOT SERVING COUNTER	TRUE CUSTOM	TMC-49-DS-HC ST. STL./MILLWORK
	80 81	1	DROP-IN HOT/COLD WELL UNIT SELF-SERVE BREATH GUARD W/LIGHTS	LTI VERSA GARD	DI-QSCHP-4 VG7
	82 83	1	MOBILE COLD SERVING COUNTER DROP-IN COLD WELL UNIT	CUSTOM LTI	CUSTOM DI-2063TA
	84	1	SELF-SERVE BREATH GUARD W/LIGHTS	VERSA GARD	VG7
	85 86	1 2	MOBILE DRY GOODS SERVING COUNTER MOBILE DOUBLE-SIDED CASHIER COUNTER	CUSTOM CUSTOM	ST. STL./MILLWORK
	87 88	2 4	POINT OF SALE SYSTEM SILVERWARE DISPENSER	BY OWNER VOLLRATH	NOT IN KEC CONTRACT 52644
	89 90	1	MOBILE CONDIMENT COUNTER DROP-IN ICED COLD WELL UNIT	CUSTOM HATCO	CUSTOM IWB-2
	91 92	1	MOBILE CONDIMENT COUNTER DROP-IN ICED COLD WELL UNIT	CUSTOM HATCO	ST. STL./MILLWORK
	93	1*	MANUAL CAN OPENER	EDLUND	S-11
	94 95	1* 1*	ELECTRIC CAN OPENER DIGITAL SCALE	EDLUND EDLUND	270/115V WSC-10
	96 97	4*	HEAVY-DUTY UTILITY CART	LAKESIDE	744
	98 99				
	100				
	101 102				
	103				
	103				
	104 105				





Wednesday, 3/2/2022 - 4:37 PM - LAST SAVED BY:JO G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-PLAN.C


10	)

# **SPECIAL CONDITIONS LAYOUT NOTES**

**KITCHEN EQUIPMENT CONTRACTOR:** 


1. PROVIDE 16 GAUGE STAINLESS STEEL CORNER GUARDS AS SHOWN ON PLAN OR AS NECESSARY IN FOOD PRODUCTION AREAS AND CORRIDORS, ON EVERY EXPOSED OUTSIDE CORNER OF CONSTRUCTION, WALK-IN CABINET AND VERTICAL/HORIZONTAL GAPS AND CREVICES. BREAK CORNER GUARDS 90° (+/-) FOR TIGHT FIT AND APPLY WITH MASTIC ADHESIVE. SEAL ALL CORNER GUARDS TO BUILDING WALLS WITH CLEAR SILICONE. GENERAL DIVISION:

- RECESS AND TRANSIT LEVEL ENTIRE WALK-IN COOLER/FREEZER AREA TO A DEPTH OF 8" TO RECEIVE WALK-IN COOLER/FREEZER INSULATED FLOOR PANELS. DEPRESSION TO BE CONSTRUCTED AS TO PROVIDE A LEVEL TRANSITION FROM FLOOR FINISH IN KITCHEN AREA TO THE FLOOR FINISH IN WALK-IN COOLER/FREEZER. (VERIFY REQUIRED DEPRESSION THICKNESS WITH WALK-IN MANUFACTURER'S SHOP DRAWING AND ARCHITECTURAL FLOOR FINISH SCHEDULE)
- PROPERLY REINFORCE ALL WALLS AND/OR CEILINGS TO SUPPORT ALL WALL AND/OR CEILING SUPPORTED EQUIPMENT. ALL WALL BLOCKING TO BE MINIMUM 3/4" MARINE GRADE PLYWOOD OR 14 GAUGE GALVANIZED STEEL. WALL BLOCKING LENGTHS SHOWN ARE MINIMUM AND WALL BLOCKING SHALL ALWAYS EXTEND TO NEXT STUD OVER IN EACH DIRECTION.
- 4. PROVIDE BOX OUT IN CEILING GRID LAYOUT FOR EXHAUST SYSTEM HOODS AS SHOWN. (REFER TO EXHAUST VENTILATION SYSTEM DRAWINGS FOR MORE INFORMATION)
- 5. PROVIDE BOX OUT IN FLOOR AREA AS SHOWN FOR FLOOR TROUGH INSTALLATION PRIOR TO POURING CONCRETE. (REFER TO FLOOR TROUGH DETAIL DRAWING FOR MORE INFORMATION) ELECTRICAL DIVISION:
- 6. PROVIDE 2" DIAMETER RACEWAY FOR RUN OF COMPUTER GRADE CONDUIT FROM POINT OF SALE SYSTEMS IN SERVERY AREA TO COMPUTER LOCATED IN KITCHEN MANAGER'S OFFICE FOR COMMUNICATION PURPOSES.





QUIPMENT		MECHAI	NICAL			EL	ECTRIC	CAL	EC	UIPMENT		MECHANICAL		EL	ECTRIC	CAL	
DESCRIPTION	SOURCE		GAS		REMARKS			REMARKS		DESCRIPTION	SOURCE	GAS	REMARKS				REMARKS
		, z		ш		TAGE	S		  BER NTIT					TAGE	Sd	S.	
(NIKEC= NOT IN KITCHEN EQUIPMENT CONTRACT)	НОТ	COLE AFF CON	AFF	WAST	AFF		AMP HP	PHASE CONN. AFF	NUM NUM	(NIKEC= NOT IN KITCHEN EQUIPMENT CONTRACT)	HOT	COLD AFF CONN SIZE M BTL AFF	MAS: AFF	VOLTA KW	AMP	PHASE CONN. AFF	
WALK-IN COOLER/FREEZER				-		L20		1 D DFA CIRCUIT REQUIRED AT EACH DOOR	51 1	DISH MACHINE	HOBART 0.50	0 0.50 14	2.00 FS 120° MINIMUM HOT WATER REQ. W/ 70°	480		3 D 60	
WALK-IN COOLER	CUSTOM PART OF ITEM #1			FD						W/BOOSTER HEATER DISH MACHINE	CL44EN-BAS HOBART		RISE BOOSTER. DRAIN TO FLOOR SINK	480	15.7	3 D 60	
COIL WALK-IN COOLER	PART OF ITEM #1					L20	5.0	1 D DFA	52 1	BLOWER DRYER DISH MACHINE VENT COWL	BDELRAB-HTSDOM PART OF			400	15.7	5 0 00	
COMPRESSOR	PART OF ITEM #1				2	208	10.9 1.50	3 D ROOF	53 2		ITEM #54						
HI-DENSITY TOP TRACK COOLER SHELVING UNIT	INTERMETRO METROMAX Q								54 1	DISH MACHINE EXHAUST FAN	CUSTOM ST. STL.		SEE SHEET K500 FOR ADDITIONAL INFO				SEE SHEET K500 FOR ADDITIONAL IN
COOLER DUNNAGE	INTERMETRO								55 1	CLEAN DISH TABLE	CUSTOM						
RACK COOLER MOBILE	HP2248PDMB INTERMETRO									WALL SHELF	ST. STL. CUSTOM						
SHELVING UNIT	METROMAX Q					208	9.0		56 1		ST. STL.						
WALK-IN FREEZER COIL	PART OF ITEM #1			FD		120	15.0	1DDFAREFER TO COOLER/FREEZER DWG. K4001P96FOR DRAIN LINE HEAT TAPE. NEMA 5-15P	57 1	MOBILE DRYING RACK	INTERMETRO PR36VX2-XDR						
WALK-IN FREEZER COMPRESSOR	PART OF ITEM #1				2	208	19.5 3.50	1 D ROOF REFER TO COOLER/FREEZER DWG. K400	58 1	MOBILE DRYING RACK	INTERMETRO PR36VX3-XDR						
FREEZER MOBILE	INTERMETRO									MOBILE DRYING	INTERMETRO						
SHELVING UNIT FREEZER DUNNAGE	METROMAX Q INTERMETRO								60 LOT	RACK TRASH CONTAINERS	PR36VX4-XDR BY OWNER						
RACK HI-DENSITY TOP TRACK DRY	HP2260PDMB INTERMETRO									SPARE NUMBER	NIKEC						
STORAGE SHELVING UNIT	METROMAX Q								61								
SPARE NUMBER									62	SPARE NUMBER							
DRY STORAGE MOBILE SHELVING UNIT	INTERMETRO METROMAX Q								63 1	JANITORIAL MOP SINK	ADVANCE TABCO 9-OP-20 0.50	0 0.50 42	3.00 0				
ISLAND WORKTABLE W/	CUSTOM			2.00	FS DRAIN TO FLOOR SINK	120	16.0	1     P     SU   FIXTURE MOUNTED DCO - 4 LOCATIONS	64 1	CHEMICAL SHELVING	INTERMETRO						
2 COMP PREP SINK WALL MOUNT	ST.STL.									UNIT WASHER & DRYER	SEC53C BY OWNER						
HAND SINK	PBHS-W-1410-SSLR			1.50 1	18				65 1		NIKEC						
HAND SINK FAUCET	T&S BRASS 5EF-1D-WG	0.50 18			1	120		1 P 16	66 1	STAINLESS STEEL WALL CABINET	ADVANCE TABCO WCH-15-60						
ISLAND WORKTABLE W/ PREP SINKS	CUSTOM ST.STL.			2.00 F	FS DRAIN TO FLOOR SINK 1	L20	16.0	1 P SU FIXTURE MOUNTED DCO - 4 LOCATIONS	67 6	LOCKERS (FULL SIZE)	BY ARCHITECT NIKEC						
SPLASH MOUNT	T&S BRASS	0.50 DFA							68 1	MILK COOLER	TRUE			120	2.70	1 P SU	NEMA 5-15P POVIDE FLUSH MOUN
FAUCET GARBAGE DISPOSAL	B-0231-CR IN-SINK-ERATOR			2.00	BRANCH CW FROM FAUCET ITEM #18			2 D SUL EXTEND SERVICE TO K.E.C. FURNISHED		MOBILE HOT SERVING	TMC-49-HC CUSTOM					1 P SU	RECEPTACLE IN FLOOR
SYSTEM	SS-200-7/AS-101	0.50 DFA		2.00 5	SU THRU SOLENOIDS & VACUUM BREAKER	208	3.20	3 D SU CONTROL PANEL.	69 1	COUNTER	ST. STL./ MILLWORK			120			
HEAVY-DUTY BUN PAN RACK	CHANNEL 401A								70 1	DROP-IN HOT/COLD UNIT	DI-QSCHP-4		0.75 FD DRAIN TO FLOOR DRAIN 120	0/280	14.4	1 P SU	NEMA 14-20P
COUNTERTOP MIXER W/ STAND	HOBART HL200-1STD				1	120	8.00	1 P * *PLUG INTO ISLAND WORKTABLE	71 1	SELF-SERVE BREATH GUARD W/LIGHTS	VERSA-GARD VG7			120	6.00	1 D SU	
SLICER	HOBART				1	120	5.40	1 P * *PLUG INTO ISLAND WORKTABLE		MOBILE COLD SERVING	CUSTOM			120	16.0	1 P SU	DCO
MOBILE WORKTABLE	HS8-1 CUSTOM									COUNTER DROP-IN COLD WELL UNIT	ST. STL./ MILLWORK						NEMA 5-15P
	ST. STL.										DI-2063TA		0.75 FD	120	8.50	1 P SU	
ICE MAKER W/ BIN	MANITOWOC IYT0420A	0.50 60		0.75 F	FD DRAIN TO FLOOR DRAIN 1	L20	11.5	1 D 66	74 1	SELF-SERVE BREATH GUARD W/LIGHTS	VERSA-GARD VG7			120	6.00	1 D SU	
WORKTABLE	CUSTOM ST. STL.								75 1	DRY GOODS SERVING COUNTER	CUSTOM ST. STL./ MILLWORK			120	16.0	1 P SU	DCO
MICROWAVE	PANASONIC				1	L20	13.4	1 P 24 NEMA 5-15P	76 1	ICE CREAM FREEZER	BEVERAGE AIR			120	2.00	1 P SU	NEMA 5-15P PROVIDE FLUSH MOUI
KITCHEN MOBILE	NE-1064F INTERMETRO									MOBILE TRAY	NC28HC-1-W DELFIELD						RECEPTACLE IN FLOOR
SHELVING UNIT	METROMAX Q									DISPENSERS	TT-1014						
SINGLE DOOR REACH-IN HEATED CABINET	TRAULSEN AHF132W-FHS				2	208		1 P 78 NEMA L14-20P MOUNTED IN SOFFIT ABOVE	78 1	MILK COOLER	TRUE TMC-49-HC			120			NEMA 5-15P
SINGLE DOOR REACH-IN REFRIGERATOR	TRAULSEN AHT132WUT-FHS				1	L20	7.00	1 P 78 NEMA 5-15P MOUNTED IN SOFFIT ABOVE	79 1	MOBILE HOT SERVING COUNTER	CUSTOM ST. STL./ MILLWORK			120	16.0	1 P SU	DCO
EXHAUST HOOD	CUSTOM				SEE SHEET K500 FOR ADDITIONAL INFO			SEE SHEET K500 FOR ADDITIONAL INFO	80 1	DROP-IN HOT/COLD UNIT	LTI		0.75 FD DRAIN TO FLOOR DRAIN 120	0/280	14.4	1 P SU	NEMA 14-20P
FIRE SUPPRESSION SYSTEM	ST. STL. PART OF				SEE SHEET K500 FOR ADDITIONAL INFO			SEE SHEET K500 FOR ADDITIONAL INFO	81 1	SELF-SERVE BREATH	DI-QSCHP-4 VERSA-GARD			120		1 D SU	
FIRE PULL BOX	ITEM #30 PART OF				SEE SHEET K500 FOR ADDITIONAL INFO			SEE SHEET K500 FOR ADDITIONAL INFO		GUARD W/LIGHTS MOBILE COLD SERVING	VG7 CUSTOM						
	ITEM #30								82 1	COUNTER	ST. STL./ MILLWORK			120		1 P SU	
COOKLINE EXHAUST FAN	PART OF ITEM #30				SEE SHEET K500 FOR ADDITIONAL INFO			SEE SHEET K500 FOR ADDITIONAL INFO	83 1	DROP-IN COLD WELL UNIT	LTI DI-2063TA		0.75 FD DRAIN TO FLOOR DRAIN	120	8.50	1 P SU	NEMA 5-15P
COOKLINE MAKE UP AIR FAN	PART OF ITEM #30				SEE SHEET K500 FOR ADDITIONAL INFO			SEE SHEET K500 FOR ADDITIONAL INFO	84 1	SELF-SERVE BREATH GUARD W/LIGHTS	VERSA-GARD VG7			120	6.00	1 D SU	
COMBI OVEN/STEAMER	RATIONAL	(2)0.75 36 0.7	5 107 48	2.00	FS DIVIDE C.W. USING MANIFOLD AND EXTEND 2 ONE LINE THRU KEC FURNISHED FILTER. 2	208	15.0	1 D 48	85 1	DRY GOODS SERVING	CUSTOM			120	16.0	1 P SU	DCO
DBL STACK COMBI OVEN/STEAMER	ICC 6-FULL/ICC 6-FULL PART OF		b 107 24		ONE LINE THRU KEC FURNISHED FILTER.         2           *INTERCONNECT CW CONNECTION WITH	208	15.0	1 D 24		COUNTER MOBILE DOUBLE-SIDED	ST. STL./ MILLWORK			-			
FILTER	ITEM #35	* 60			COMBI UNIT ITEM #35				86 2	CASHIER COUNTER	ST. STL./ MILLWORK						
40 GALLON TILT SKILLET	SGL40T1 0.5	0.50 14 0.7	5 200 24	2.00 F	FT FT 1	120	10.0	1 P 16 NEMA 5-15P	87 2	POINT OF SALE SYSTEM	BY OWNER NIKEC			120	16.0	1 P SU	DCO. DATA LINE REQUIRED.
FLOOR TROUGH	CUSTOM ST. STL.			4.00	0 TRAP BELOW FLOOR FOR FLOOR TROUGH DRAIN FURNISHED BY KEC				88 4	SILVERWARE DISPENSER	VOLLRATH 52644						
FOUR BURNER RANGE	MONTAGUE	1.2	5 140 24						89 1		CUSTOM						
WITH OVEN BASE DOUBLE STACKED	124-5     SOUTHBEND		5 144 24			120	7.90	1     P     16   NEMA 5-15P (1) REQUIRED PER OVEN	90 1	COUNTER DROP-IN ICED COLD	ST. STL./ MILLWORK						
CONVECTION OVEN SPARE NUMBER	SLGB/22SC	0.7	<u>+</u> 24		<sup>1</sup>		,			WELL UNIT MOBILE CONDIMENT	IWB-2 CUSTOM						
									91 1	COUNTER	ST. STL./ MILLWORK						
SPARE NUMBER										DROP-IN ICED COLD WELL UNIT	HATCO IWB-2						
SPARE NUMBER																	
SPARE NUMBER																	
THREE COMPARTMENT	CUSTOM			2.00	FS VERIFY WITH LOCAL CODE												
SINK WALL SHELF	ST. STL. CUSTOM			2.00 1													
	ST. STL.																
SPLASH MOUNT FAUCET	T&S BRASS         0.7           B-0290         0.7	0.75 14															
SPLASH MOUNT	T&S BRASS	0.50 14															
PRE-RINSE FAUCET GARBAGE DISPOSAL	B-0133-CR-B-SWV IN-SINK-ERATOR			2 00	6 BRANCH CW FROM FAUCET ITEM #24	208	3.20	3 D 16 EXTEND SERVICE TO K.E.C. FURNISHED									
SYSTEM SOILED DISH TABLE	SS-200-7/AS-101 CUSTOM	0.50 14		2.00	<sup>6</sup> THRU SOLENOIDS & VACUUM BREAKER	-00	3.20	3 D 16 EXTEND SERVICE TO K.E.C. FURNISHED CONTROL PANEL.									
W/ SCRAP SINK																	
					1	L20	16.0	1 16									
RECEPTACLE DUPLEX CONVENIENCE								1     48     FURNISH HORIZONTAL RECEPTACLE WHEN MOUNTED ABOVE COUNTERTOP									
RECEPTACLE					1	120	16.0	┷     ↔									

	RALTAR ESIGN ENGINEERING • INTERIOR DESIGN
ES AD AND RENO	
GIBRAI 9102 N. Meridia Indianapolis, IN Homepage www. Email info@Gibro	46260 GibraltarDesign.com altarDesign.com 5777 Fax 317.580.5778
WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITH OF GIBRALTAR DESIGN. T	ISSUED FOR
SPOT SCHI PROJECT	L ES ADDITIONS AND



Wednesday, 3/2/2022 - 4:39 PM - LAST SAVED BY:JO G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-SPOT.C






# PLUMBING NOTES


L. FOODSERVICE SPOT LOCATION SCHEDULES & DRAWINGS ARE FOR REFERENCE AND BIDDING PURPOSES, TO BE USED ONLY AS A GUIDE FOR FOOD SERVICE EQUIPMENT ELECTRICAL, PLUMBING & VENTILATION SPOT LOCATIONS AND ARE NOT APPROVED FOR USE ON THE JOBSITE FOR ROUGH-IN PURPOSES. THE KITCHEN EQUIPMENT CONTRACTOR SHALL BE RESPONSIBLE FOR CREATING HIS/HER OWN ROUGH-IN SCHEDULES & DRAWINGS SHOWING ACCURATE LOCATIONS FOR UTILITIES AND WORK TO BE INSTALLED IN ACCORDANCE WITH ALL FEDERAL, STATE & LOCAL CODES.

- 2. ALL SPOT LOCATIONS SHOWN ON THESE DRAWINGS ARE SPECIFIC TO THE EQUIPMENT SHOWN ON THE FOODSERVICE EQUIPMENT PLAN. REFER TO ARCHITECTURAL & PLUMBING DRAWING SETS FOR ADDITIONAL PLUMBING REQUIREMENTS NOT SHOWN.
- 3. ALL FLOOR AREAS IN THE KITCHEN & SERVING SPACE SHALL BE "TRANSIT LEVEL". DO NOT SLOPE FLOOR TO FLOOR DRAINS OR FLOOR SINKS IN THIS AREA!!!
- 4. MECHANICAL DIVISION TO INSTALL ALL FAUCET ASSEMBLIES, PRE-RINSE SPRAY ASSEMBLIES, HOSE ASSEMBLIES, VACUUM BREAKERS, CHECK VALVES, FLOW CONTROL VALVES, SOLENOID VALVES, WATER PRESSURE REDUCING VALVES, GAS PRESSURE REDUCING VALVES, TEMPERATURE GAUGES, PRESSURE GAUGES, WATER HAMMER SHOCK ABSORBERS & WATER FILTRATION SYSTEMS FURNISHED BY THE KITCHEN EQUIPMENT CONTRACTOR.
- MECHANICAL DIVISION TO FURNISH & INSTALL ALL WATER, GAS & STEAM SUPPLY LINES, DRAIN MANIFOLDS & TAILPIECES, TRAPS, SHUT-OFF VALVES, VENT PIPING, GAS SUPPLY LINE STRAINERS/FILTERS, BACK FLOW PREVENTION DEVICES, FLOOR DRAINS & FLOOR SINKS AS REQUIRED FOR EQUIPMENT INSTALLATION AND ANY CODE REQUIREMENTS. ALL SUPPLY LINES SERVICING EQUIPMENT ADJACENT TO AN EXTERIOR WALL ARE TO BE RAN ALONG INTERIOR FACE OF WALL TO AVOID POTENTIAL FREEZING.
- MECHANICAL DIVISION TO FURNISH & INSTALL STAINLESS STEEL OR CHROME PLATED BRASS ESCUTCHEONS OR FLANGES FOR UTILITY LINES WHICH EXTEND THROUGH BUILDING WALLS AND EQUIPMENT. ALL PENETRATIONS TO BE SEALED WATER-TIGHT AND VERMIN PROOF.
- MECHANICAL DIVISION TO FURNISH & INSTALL TYPE "L" COPPER TUBING DRAIN LINES FROM ALL APPLICABLE EQUIPMENT TO FLOOR SINKS, (INCLUDING WALK-IN COOLER AND FREEZER COILS) AND TO INSULATE ALL DRAIN LINES FROM ICE BINS, REFRIGERATION EQUIPMENT ETC.. MECHANICAL DIVISION TO INSTALL DRAIN LINES SO THEY DO NOT AFFECT UNDERCOUNTER STORAGE AND OTHER OPERATIONAL FUNCTIONS OF THE FIXTURES.
- 8. MECHANICAL DIVISION TO FURNISH & INSTALL CHROME PLATED PIPING ON ALL EXPOSED PIPING ABOVE COUNTER HEIGHT OR IN "DIRECT" LINE OF SIGHT TO THE OWNER/OPERATOR.
- 9. MECHANICAL DIVISION TO FURNISH & INSTALL ALL 12"x12"x8" FLOOR SINKS WITH HALF GRATES. FLOOR SINKS TO BE MOUNTED IN FLOOR SUCH THAT THE TOP OF THE RIM WILL BE FLUSH WITH FINISHED FLOOR ELEVATION UNLESS OTHERWISE DIRECTED BY STATE & LOCAL CODES. FLOOR SINKS FOR DISHMACHINES AND ALL COOKING EQUIPMENT TO HAVE A MINIMUM OF 3" DRAIN CONNECTION.
- 10. MECHANICAL DIVISION TO COOL, HEAT &/OR VENTILATE FOOD SERVICE DRY STORAGE ROOM TO MAINTAIN A TEMPERATURE OF 68 DEGREES TO 72 DEGREES YEAR AROUND.
- 11. MECHANICAL DIVISION TO UTILIZE EXISTING FLOOR DRAINS, FLOOR SINKS, DIRECT PLUMBING DRAINS, GAS CONNECTIONS & WATER CONNECTIONS WHERE POSSIBLE FOR NEW EQUIPMENT AND CAP OFF ANY EXISTING SERVICES MADE OBSOLETE BY THESE DRAWINGS.






Wednesday, 3/2/2022 - 4:40 PM - LAST SAVED BY:JO G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-SPOT.E




# **ELECTRICAL NOTES**

FOODSERVICE SPOT LOCATION SCHEDULES & DRAWINGS ARE FOR REFERENCE AND BIDDING PURPOSES, TO BE USED ONLY AS A GUIDE FOR FOOD SERVICE EQUIPMENT ELECTRICAL, PLUMBING & VENTILATION SPOT LOCATIONS AND ARE NOT APPROVED FOR USE ON THE JOBSITE FOR ROUGH-IN PURPOSES. THE KITCHEN EQUIPMENT CONTRACTOR SHALL BE RESPONSIBLE FOR CREATING HIS/HER OWN ROUGH-IN SCHEDULES & DRAWINGS SHOWING ACCURATE LOCATIONS FOR UTILITIES AND WORK TO BE INSTALLED IN ACCORDANCE WITH ALL FEDERAL, STATE & LOCAL CODES.

- 2. ALL SPOT LOCATIONS SHOWN ON THESE DRAWINGS ARE SPECIFIC TO THE EQUIPMENT SHOWN ON THE FOODSERVICE EQUIPMENT PLAN. REFER TO ARCHITECTURAL & ELECTRICAL DRAWING SETS FOR ADDITIONAL ELECTRICAL REQUIREMENTS NOT SHOWN.
- 3. ELECTRICAL AMPERAGE NOTED IN SCHEDULE INDICATES AMP "DRAW" & NOT CIRCUIT BREAKER SIZE UNLESS OTHERWISE NOTED. ELECTRICAL DIVISION IS RESPONSIBLE FOR PROPER CIRCUIT BREAKER SIZING
- 4. ELECTRICAL DIVISION TO VERIFY ALL FOODSERVICE EQUIPMENT WITH DIRECT ELECTRICAL CONNECTION TO BE IN LINE OF SIGHT OF KITCHEN ELECTRICAL DISTRIBUTION PANEL, AND IF NOT, ELECTRICAL DIVISION TO FURNISH & INSTALL A FUSED QUICK DISCONNECT ADJACENT TO EQUIPMENT.
- 5. ELECTRICAL DIVISION TO INSTALL ALL CONTROL PANELS, STARTERS, SOLENOID VALVES, JUNCTION BOXES & DISCONNECT SWITCHES FURNISHED BY THE KITCHEN EQUIPMENT CONTRACTOR.
- 6. ELECTRICAL DIVISION TO FURNISH & INSTALL ALL WIRING, ELECTRICAL OUTLETS, STARTERS, JUNCTION BOXES, DISCONNECT SWITCHES & CONDUIT REQUIRED FOR EQUIPMENT INSTALLATION IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS & ELECTRICAL CODE REQUIREMENTS. ELECTRICAL RECEPTACLES TO BE FLUSH MOUNTED UNLESS OTHERWISE NOTED.
- ELECTRICAL DIVISION TO FURNISH & INSTALL GROUNDING WIRE TO ALL FOOD SERVICE EQUIPMENT IN ADDITION TO THE NUMBER OF WIRES NOTED IN INDIVIDUAL SERVICES.
- 8. ELECTRICAL DIVISION TO FURNISH & INSTALL GROUND FAULT PROTECTION FOR ANY RECEPTACLE WITHIN THE KITCHEN & SERVING AREAS.
- 9. ELECTRICAL DIVISION TO FURNISH & INSTALL SHUNT TRIP BREAKERS FOR ALL ELECTRICAL SERVICE TO EQUIPMENT UNDER EXHAUST HOODS WHEN FIRE SUPPRESSION SYSTEM IS REQUIRED.
- 10. ELECTRICAL DIVISION TO FURNISH 6'-0" PIGTAIL FLEX CONDUIT AT ALL DIRECT CONNECTION STUB-OUTS AND EXTEND TO FINAL CONNECTION ON EQUIPMENT. ELECTRICAL DIVISION TO PROVIDE CAPS AND CORDS FOR ALL ITEMS WHICH USE CONVENIENCE OUTLETS WHEN NOT SUPPLIED BY THE MANUFACTURER AND SHORTEN ANY CORDS IF NECESSARY.
- 11. ELECTRICAL DIVISION TO UTILIZE EXISTING ELECTRICAL CONNECTIONS WHERE POSSIBLE FOR NEW EQUIPMENT AND CAP OFF ANY EXISTING SERVICES MADE OBSOLETE BY THESE PLANS.






Wednesday, 3/2/2022 - 4:47 PM - LAST SAVED BY:JONATHAN N G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-WALK.DWG


	WALK-IN COOLER/FREEZER OPTIONS/ACCESSORIES SCHEDULE
9-5° RECES	<section-header>         OPTIOONS/ACCESSOORIES SCHEDDULE         HIGHT DIMENSIONS         COLFR       OUTSIDE DIM. = 9'.8" INSIDE DIM. = 9'.0"         HEEZER       OUTSIDE DIM. = 9'.8" INSIDE DIM. = 9'.0"         FREZER       OUTSIDE DIM. = 9'.8" INSIDE DIM. = 9'.0"         COLFR       C. COLFREDORISH         MEDED DALLS       ZE GA. EMBOSSED GALV. STEEL (WHITE BAKED-ON ENAMEL)         LINERYOSED WALLS       ZE GA. EMBOSSED GALV. STEEL (WHITE BAKED-ON ENAMEL)         COST SECTION:       TO MATCH ADJACENT EXTERIOR WALLS         DOOR SECTION:       TO MATCH ADJACENT EXTERIOR WALLS         DING SECTION:       TO MATCH ADJACENT EXTERIOR WALLS         DOOR SECTION:       TO MATCH ADJACENT EXTERIOR WALLS         DOOR SECTION:       TO MATCH ADJACENT INTERIOR W</section-header>
	WALK-IN COOLER/FREEZER ELECTRICAL SCHEDULE
	WALK-IN COOLER (+35° F) ELECTRICAL REQUIREMENTS
	ITEMEQUIPMENT DESCRIPTIONVOLTAGEPHSAMPHPAFFREMARKSE1LIGHTS AND DOOR OPTIONS (COOLER)120120.0DFA
	E2         WALK-IN COOLER EVAPORATOR FANS         120         1         5.0         DFA           E3         WALK-IN COOLER CONDENSING UNIT         208         3         7.7         1.50         PAD
	WALK-IN FREEZER (-10° F) ELECTRICAL REQUIREMENTS           ITEM         EQUIPMENT DESCRIPTION         VOLTAGE         PHS         AMP         HP         AFF         REMARKS
	E1A         LIGHTS AND DOOR OPTIONS (FREEZER)         120         1         20.0         DFA           E7A         WALK-IN FREEZER DRAIN LINE HEAT TAPE         120         1         15.0         90"
	E7BWALK-IN FREEZER EVAPORATOR FANS20815.0DFAE7CWALK-IN FREEZER EVAPORATOR HEATER208114.3PAD
	E8     WALK-IN FREEZER CONDENSING UNIT     208     3     17.1     4.50     PAD
SCALE	WALK-IN COOLER/FREEZER RESPONSIBILITIES BY OTHER TRADES
JALE DI       I         JULE DI       I         JULE DI       I         I       I	COOLER/FREEZER INSULATED FLOOR PANELS. FURNISH AND INSTALL 6 MIL VAPOR BARRIER (JOINTS TO OVERLAP A MINIMUM OF 6") UNDER ENTIRE AREA OF WALK-IN COMPARTMENTS AND TURN UP ON ALL SIDES. FURNISH AND INSTALL 4" THICK CONCRETE TOPPING SLAB (3,000 PSI) WITH POLYPROPELENE HIBER MESH REINFORCEMENT (1.5#/CY).DEPRESSION TO BE CONSTRUCTED AS TO PROVIDE A LEVEL TRANSITION FROM FLOOR FINISH IN KITCHEN AREA TO THE FLOOR FINISH IN WALK-IN COOLER/FREEZER. (VERLEY REQUIRED DEPRESSION THICKNESS WITH WALK-IN MANUFACTURER'S SHOP DRAWING AND ARCHITECTURAL FLOOR FINISH SCHEDULE) FURNISH AND INSTALL ALL SLEEVES THROUGH BUILDING WALLS AND ROOF AS REQUIRED FOR KEC TO RUN REFRIGERATION LINES FROM WALK-IN COOLER/FREEZER TO WALK-IN COOLER/FREEZER COMPRESSORS. SLEEVES TO BE LOCATED AND COORDINATED IN FIELD BY KEC. FRAME ROOF CURB OPENINGS AS REQUIRED. COORDINATE JOIST OR STRUCTURAL MEMBER INSTALLATION TO PROVIDE REQUIRED STRUCTURAL SUPPORT FOR WALK-IN COOLER/FREEZER COMPRESSORS. CUT OPENINGS IN ROOF FOR ACCESS TO CURBS AND PITCH POCKETS. FURNISH AND INSTALL ADEQUATE STRUCTURAL SUPPORT FOR WALK-IN COOLER/FREEZER COMPARTMENTS SET-IN-PLACE AND FLASH (WITH CANT IF REQUIRED) ROOF CURBS AND EQUIPMENT SUPPORT RAIL FURNISHED BY THE WALK-IN COOLER/FREEZER SYSTEM MANUFACTURER. ELECTRICAL DIVISION: FURNISH AND INSTALL ALL CONDUIT AND WIRING NECESSARY BETWEEN EVAPORATOR COILS, CONDENSING UNITS, AND ELECTRICAL DISCONNECTS. FURNISH AND INSTALL ALL CONDUIT AND WIRING NECESSARY BETWEEN EVAPORATOR COILS, CONDENSING UNITS, AND ELECTRICAL DISCONNECTS. FURNISH AND INSTALL ALL CONDUIT AND CONDUIT ABOVE AND DISCONNECTS TO LIGHTS AND ALL HEATED DOOR OPTIONS IN WALK-IN COOLER/FREEZER UNIT. FURNISH AND INSTALL ALL WIRING AND CONDUIT ABOVE AND ON THE OUTSIDE OF THE WALK-IN COOLER/FREEZER COMPARTMENT. ALL PENETRATIONS THRU WALLS AND CEILING ARE TO BE EQUIPPED WITH "SEAL-OFFS" AND SEALED WITH SILCONE AT EACH JUNCTION BOX TO PREVENT MOISTURE FROM COLLECTING IN FIXTURE. <b>MECHANICAL DIVISION:</b> INSURE THAT THERE IS CONSTANT AIRFLOW ABOVE AND AROUND ALL SIDES OF WALK-IN CO
NDENSING UNIT DETAIL NOT TO SCALE B	
IZED STEEL /IBOSSED GALVALUME	WALK-IN COOLER/FREEZER NOTES
FUSED RAIN TIGHT DISCONNECT SWITCH (BY E.D.)	<ol> <li>KEC TO FIELD VERIFY ALL BUILDING CONDITIONS, PIT RECESS, WALK-IN DIMENSIONS AND BUILDING DIMENSIONS TO ENSURE PROPER FIT OF WALK-IN COOLER/FREEZER.</li> <li>KEC TO EXTEND 3/4" DRAIN LINE FROM EVAPORATOR COILS TO FLOOR DRAIN, AS LOCATED ON DRAWING, ON THE EXTERIOR OF THE WALK-IN COOLER/FREEZER COMPARTMENT. DRAIN LINE TO BE SLOPED MINIMUM OF 1/4" PER FOOT. KEC TO COORDINATE DRAIN LINE HEIGHT AS IT EXITS EACH COIL SO THAT IT DOES NOT INTERFERE WITH SHELVING.</li> <li>KEC TO PROVIDE AND INSTALL ALL REQUIRED ELECTRICAL COMPONENTS (FUSED DISCONNECT, TIME CLOCKS, MAGNETIC STARTERS, ETC.) AND FACTORY WIRED (CONDUIT AND CABLE) FOR ALL CONTROLS WITHIN THE REFRIGERATION SYSTEMS, TO A SINGLE POINT OF SERVICE FOR POWER CONNECTION.</li> <li>KEC TO PROVIDE ED WITH A SUFFICIENT NUMBER OF LIGHT FIXTURES TO PROVIDE A MINIMUM OF SEVENTY (70) FOOT CANDLES OF LIGHT INTENSITY MEASURED AT 30" AFF AT ANY POINT IN THE COMPARTMENT. THIS EQUATES TO APPROXIMATELY ONE (1) 100 WATT LIGHT FIXTURE PER FIFTY (50) SQUARE FEET NOT INCLUDING THE LIGHT FIXTURE ABOVE THE DOOR.</li> <li>KEC TO PROVIDE ALL CURBS AND PITCH POCKETS FOR FINAL MOUNTING AND MOUNTING REQUIREMENTS FOR WALK-IN COOLER/FREEZER COMPRESSORS.</li> <li>KEC TO PROVIDE ALL CURBS AND PITCH POCKETS FOR FINAL MOUNTING AND FLASHING BY GD.</li> <li>ALL FINAL CONNECTION LOCATIONS, PENETRATIONS AND ELECTRICAL REQUIREMENTS ARE TO BE VERIFIED PER THE WALK-IN MANUFACTURER'S DRAWINGS PRIOR TO CONSTRUCTION.</li> </ol>
MPRESSOR HOUSING DETAIL NOT TO SCALE C	


PROJECT TIMO ES AC AND RENC					
GIBRAI 9102 N. Meridia Indianapolis, IN Homepage www. Email info@Gibra	.GibraltarDesign.com				
DATE 02/07/22 COORDINATED BY DRAWN BY CHECKED BY	(				
THIS DOCUMENT ARE TH WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITH	S, PLANS, DETAILS, ETC, SHOWN ON E PROPERTY OF GIBRALTAR DESIGN AND E ON THIS SPECIFIC PROJECT. NONE OF L BE USED BY ANY PERSON OR FIRM OUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS				
MARK DATE 03/03/22	ISSUED FOR ADDENDUM #3				
DRAWING					
WALK-IN COOLER AND FREEZER LAYOUT AND DETAILS					
PROJECT TIMOTHY BAL RENOVATION	L ES ADDITIONS AND S				
© GIBRALTAR DESIGN	SHEET				
	K-400				




FULDER ELEMEN 1.DWG

<u> </u>											<u> </u>
	ALLIED AIR REFERENCE (ATI) HOOD SCHEDULE										
HOOD ITEM	HOOD SIZE	HOOD WEIGHT	EXHAUST CFM	EXHAUST COLLAR SIZE	EXHA DUCT VE		EXHAUST S.P.	SUPPLY CFM	SUPPLY AIR DUCT SIZE	SUPPLY AIR DUCT VELOCITY	SUPPLY S.P.
H-30	15'-6" X 5'	1,163	4,265	(2) 13" X 13"	1,800	FPM	1.25"	3,408	(6) 12" DIA.	724	2.15"
VR-53	4" X 16" (2)	60	600	(2) 4" X 16"	4" X 16" 1,440		.75"	N/A	N/A	N/A	N/A
]											
	EXHAUST HOOD CFM CONDENSATE EXHAUST CFM										
EXHA	EXHAUSTED AIR (CFM)				4,265		EXHAUSTED CONDENSATE AIR (CFM)			60	0
HEAT	ED MAKE-UP A	3,	408	MAKE-UP AIR (CFM) -0-			-				
СЕМ ТО	TAL: 4,865 R	EMOVED E	BY HOODS: 4,	865 RET	URNED BY I	MUA: 3	,408	BALAN	ICE REQUIRED	BY HVAC: 1,457	CFM







	PROJI TI ES AI RE CRO SCH	I RCHITECTURE • MO S AC ND S AC ND ENC	AALTAR PESIGN PGINEERING • INTERIOR DESIGN THY BALL DUTION DUATIONS COMMUNITY RPORATION T, INDIANA
	9102 Indian Home Email Phone 21 – DATE 02/ COORI	IBRAI N. Meridio apolis, IN page www info@Gibr 317.580 CT -112 '07/22 DINATED B	.GibraltarDesign.com altarDesign.com .5777 Fax 317.580.5778
	THE CON THIS DOC WERE CR THIS INFO FOR ANY OF GIBRA	CUMENT ARE THE REATED FOR US ORMATION SHALL PURPOSE WITH ALTAR DESIGN. TION AND REFEN IONS DATE	S, PLANS, DETAILS, ETC, SHOWN ON IE PROPERTY OF GIBRALTAR DESIGN AND E ON THIS SPECIFIC PROJECT. NONE OF L BE USED BY ANY PERSON OR FIRM HOUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS ISSUED FOR ADDENDUM #3
Allied Technologies ood Equipment, Inc. 926 SAYRE DRIVE NWOOD, IN 46142 317.887.2020 v.alliedfoodequipment.com	- - -		
Scale: As indicated Nber TBES11022	EXF SYS & S PROJ TIMO REN	HAUST V STEM D CHEDU	L ES ADDITIONS AND





PROJECT TIMO ES AC AND RENC					
GIBRAI 9102 N. Meridic Indianapolis, IN Homepage www. Email info@Gibro Phone 317.580. PROJECT 21-112 DATE 02/07/22 COORDINATED BY DRAWN BY CHECKED BY CHECKED BY COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS THIS INFORMATION SHALL FOR ANY PURPOSE WIT	GibraltarDesign.com altarDesign.com 5777 Fax 317.580.5778				
REVISIONS MARK DATE 03/03/22	ISSUED FOR ADDENDUM #3				
DRAWING EXHAUST VENTILATION SYSTEM DRAWING, DETAILS & SCHEDULE					
PROJECT TIMOTHY BAL RENOVATION	L ES ADDITIONS AND S				
© GIBRALTAR DESIGN	sheet <b>K501</b>				





















PROJECT TIMO ES AC AND RENC	
GIBRAI 9102 N. Meridic Indianapolis, IN Homepage www. Email info@Gibra Phone 317.580. PROJECT 21-112 DATE 02/07/22 COORDINATED BY DRAWN BY	46260 GibraltarDesign.com altarDesign.com 5777 Fax 317.580.5778
THIS DOCUMENT ARE TH WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITH OF GIBRALTAR DESIGN. 1	S, PLANS, DETAILS, ETC, SHOWN ON E PROPERTY OF GIBRALTAR DESIGN AND E ON THIS SPECIFIC PROJECT. NONE OF BE USED BY ANY PERSON OR FIRM OUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS ISSUED FOR ADDENDUM #3
SYSTEM DI & SCHEDU	L ES ADDITIONS AND S
	K502




Wednesday, 3/2/2022 - 5:09 PM - LAST SAVED BY:JONAT G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-ELEV.DWG

<b>GIBRALTAR</b> DESIGN ARCHITECTURE • ENGINEERING • INTERIOR DESIGN					
PROJECT WESTCHESTER INTERMEDIATE SCHOOL - ADDITIONS & RENOVATIONS DUNELAND SCHOOL CORPORATION CHESTERTON, INDIANA					
GIBRALTAR DESIGN 9102 N. Meridian St., Ste. 300 Indianapolis, IN 46260 Homepage www.GibraltarDesign.com Email info@GibraltarDesign.com Phone 317.580.5777 Fax 317.580.5778 PROJECT 21–139 DATE 02/07/2022 COORDINATED BY DRAWN BY JJN CHECKED BY					
RDG         COPYRIGHT NOTICE:         THE CONCEPTS, DESIGNS, PLANS, DETAILS, ETC, SHOWN ON         THIS DOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND         WERE CREATED FOR USE ON THIS SPECIFIC PROJECT. NONE OF         THIS INFORMATION SHALL BE USED BY ANY PERSON OR FIRM         FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT         OF GIBRALTAR DESIGN. THE OWNER MAY RETAIN COPIES FOR         INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS         PROJECT.         REVISIONS         MARK       DATE					
03/03/22 ADDENDUM #3					
DRAWING FOODSERVICE EQUIPMENT DETAILS, ELEVATIONS & SECTIONS					
PROJECT WESTCHESTER IS - ADDITIONS & RENOVATIONS © GIBRALTAR DESIGN SHEET K-600					




Wednesday, 3/2/2022 - 5:09 PM - LAST SAVED BY:JON G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-ELEV.DW

D	ALTAR ESIGN ENGINEERING • INTERIOR DESIGN
INTERN SCHOO ADDITI RENO\	ONS & /ATIONS
9102 N. Meridian Indianapolis, IN Homepage www.G Email info@Gibra	46260 GibraltarDesign.com
WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITHO OF GIBRALTAR DESIGN. TH	PLANS, DETAILS, ETC, SHOWN ON PROPERTY OF GIBRALTAR DESIGN AND ON THIS SPECIFIC PROJECT. NONE OF BE USED BY ANY PERSON OR FIRM JUT THE EXPRESS WRITTEN CONSENT HE OWNER MAY RETAIN COPIES FOR INCE IN CONNECTION ONLY WITH THIS INCE IN CONNECTION ONLY WITH THIS ISSUED FOR ADDENDUM #3
DETAILS, E SECTIONS PROJECT WESTCHESTE	




Wednesday, 3/2/2022 - 5:09 PM - LAST SAVED BY:JONATHAN N G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-ELEV.DWG

ICONSTRUCTION OF CONTROLOGICAL
GIBRALTAR DESIGN         9102 N. Meridian St., Ste. 300         Indianapolis, IN 46260         Homepage www.GibroltarDesign.com         Email info@GibroltarDesign.com         Email info@GibroltarDesign.com         PROJECT         21-139         DATE         02/07/2022         COORDINATED BY         DRAWN BY         JJN         CHECKED BY         RDG         COPYRIGHT NOTICE:         THE CONCEPTS, DESIGNE, PLANS, DETAILS, ETC. SHOWN ON THIS DOCUMENT ARE THE PROPERTY OF GIBRULTAR DESIGN AND
WERE CREATED FOR USE ON THIS SPECIFIC PROJECT. NONE OF THIS INFORMATION SHALL BE USED BY ANY PERSON OR FIRM FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF GIBRALTAR DESIGN. THE OWNER MAY RETAIN COPIES FOR INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS PROJECT.
MARK     DATE     ISSUED FOR       03/03/22     ADDENDUM #3
DRAWING FOODSERVICE EQUIPMENT DETAILS, ELEVATIONS & SECTIONS
PROJECT WESTCHESTER IS - ADDITIONS & RENOVATIONS
© gibraltar design Sheet K-602



Wednesday, 3/2/2022 - 5:10 PM - LAST SAVED BY:JONATHAN NII G:\SHARED DRIVES\RDG PROJECT DATA\RDG PROJECT FOLDER (2021)\2021-026 - GIBRALTAR- TIMOTHY BALL ELEMENTARY\3. DRAWINGS\A. CAD\QF-2021-026-ELEV.DWG

GIBRALTAR DESIGN ARCHITECTURE • ENGINEERING • INTERIOR DESIGN PROJECT WESTCHESTER INTERMEDIATE SCHOOL -ADDITIONS & RENOVATIONS DUNELAND SCHOOL CORPORATION CHESTERTON, INDIANA GIBRALTAR DESIGN 9102 N. Meridian St., Ste. 300 Indianapolis, IN 46260 Homepage www.GibraltarDesign.com Email info@GibraltarDesign.com Phone 317.580.5777 Fax 317.580.5778 PROJECT 21-139 DATE 02/07/2022 COORDINATED BY DRAWN BY JJN CHECKED BY RDG COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, PLANS, DETAILS, ETC, SHOWN ON THIS DOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROJECT. NONE OF THIS INFORMATION SHALL BE USED BY ANY PERSON OR FIRM FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF GIBRALTAR DESIGN. THE OWNER MAY RETAIN COPIES FOR INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS PROJECT. REVISIONS MARK DATE ISSUED FOR 03/03/22 ADDENDUM #3 DRAWING FOODSERVICE EQUIPMENT DETAILS, ELEVATIONS & SECTIONS PROJECT WESTCHESTER IS -ADDITIONS & RENOVATIONS ©gibraltar design SHEET K-603



## SYMBOLS/ABBREVIATIONS

	SYMBOLS/AB
SYMBOL	DESCRIPTION A
ہ ہے سر	EXISTING DUCTWORK
۔ ج خ	DUCTWORK TO BE REMOVED
; <b></b> ;	DUCT TRANSITION
، ا	CAP EXISTING DUCTWORK AS REQUIRED
<b>⊱  <del>  −−</del>?</b>	NEW DUCTWORK TO TIE INTO EXISTING DUCTWORK
	SQUARE TO ROUND TRANSITION
	EXISTING DUCTWORK NEW DUCTWORK
£==3	DUCTWORK TO BE REMOVED
	DUCT TRANSITION CAP EXISTING DUCTWORK AS
ł	REQUIRED
	NEW DUCTWORK TO TIE INTO Existing ductwork
$[\times]$	SUPPLY AIR DUCT DOWN
	RETURN OR EXHAUST DUCT DOWN
	RETURN OR EXHAUST DUCT UP
	VAY W/ HOT WATER REHEAT COIL RETURN OR EXHAUST REGISTER
M	SUPPLY AIR DIFFUSER
	FLEXIBLE DUCTWORK
<b></b>	FLEXIBLE DUCTWORK AUTOMATIC (MOTORIZED) DAMPER
	FIRE - SMOKE DAMPER
$\bigcirc$	SEE SCHEDULES SHEET NOTE
©	DUCT SMOKE DETECTORS
S	PROVIDED BY UNIT MANUFACTURER NON ADJUSTABLE THERMOSTAT
S <sup>CO2</sup>	COMBINATION NON ADJUSTABLE THERMOSTAT/CO2 SENSOR
	DUCT MOUNTED CARBON DIOXIDE SENSOR
Œ	HUMIDISTAT
1	THERMOSTAT - ADJUSTABLE
$\mathbb{T}^{\mathcal{CO2}}$	WALL MOUNTED THERMOSTAT 48' AFF AND SEPARATE CO2 SENSOR - CLG. MTD. OR WALL MTD. (ABOVE 84"AFF)
() <sup>R</sup>	REVERSE ACTING THERMOSTAT
	COMBINED THERMOSTAT/ HUMIDISTAT
Seras	
	HOT WATER SUPPLY PIPING HOT WATER RETURN PIPING
← CHWS →	CHILLED WATER SUPPLY PIPING
	CHILLED WATER RETURN PIPING GAS PIPING
	REFRIGERANT PIPE
<u> </u>	PIPING SLOPED DOWN
~~	PIPING TO BE REMOVED EXISTING PIPING
~o	PIPE TURNED UP
	PIPE TURNED DOWN PIPE EXPANSION
EC	PIPE EXPANSION GUIDE
AN *	PIPE EXPANSION ANCHOR
GM	GAS METER GAS SOLENOID VALVE
凶 1	UNION
⊗ ⊠	CIRCUIT SETTER SHUT-OFF VALVE
	GAS COCK
*	SHUT-OFF VALVE IN RISER
7 F	CHECK VALVE STRAINER
M	PRESSURE REDUCING VALVE
¢ €	2-WAY AUTOMATIC VALVE 3-WAY AUTOMATIC VALVE
× ×	PRESSURE REGULATOR
₿	CONTROL VALVE
	TRIPLE DUTY VALVE FLOW SWITCH
<u></u>	RELIEF VALVE
Ë	GRISWOLD VALVE
á D	MANUAL AIR VENT THERMOMETER
φ	PRESSURE GAUGE

AD-3

nL	
REVIATIO	<u>NS DESCRIPTION</u>
	AUTOMATIC (MOTORIZED) DAMPER
	ABOVE FINISHED FLOOR AIR HANDLING UNIT
	BACKDRAFT DAMPER
BJA	BETWEEN JOIST ABOVE
	BLANK OFF BAROMETRIC RELIEF DAMPER
	COMBUSTION AIR INTAKE
CAT	CONDENSING AIR TEMPERATURE
	CUBIC FEET PER HOUR
CHWS	CHILLED WATER SUPPLY
	CHILLED WATER RETURN
	CIRCUIT SETTER
	CONDENSING UNIT
DN.	DOWN
	DISCONNECT SWITCH DIRECT EXPANSION
	ENTERING AIR TEMPERATURE
EC	ELECTRICAL CONTRACTOR
	ENTERING DRY BULB TEMPERATURE
	ENERGY RECOVERY VENTILATOR EXTERNAL STATIC PRESSURE
	ENTERING WET BULB TEMPERATURE
EWT	ENTERING WATER TEMPERATURE
	EXISTING
	FLEXIBLE CONNECTION
FD	FIRE DAMPER
	FACILITY MANAGEMENT SYSTEM
	NATURAL GAS GENERAL EXHAUST FAN
GPM	GALLONS PER MINUTE
	HOOD
	HORSE POWER HOT WATER SUPPLY
	HOT WATER RETURN
ΗZ	HERTZ
	KITCHEN EXHAUST FAN LIQUID
LAT	LEAVING AIR TEMPERATURE
	LEAVING DRY BULB TEMPERATURE
	LOUVER LEAVING WET BULB TEMPERATURE
	LEAVING WATER TEMPERATURE
M/A	MIXED AIR
	1,000 BTU/HOUR MECHANICAL CONTRACTOR
	MANUAL DAMPER
MOD	MODULATING
	NORMALLY CLOSED
	NECK NORMALLY OPEN
NTS	NOT TO SCALE
	OUTSIDE AIR INTAKE OPPOSED BLADE DAMPER
	PRESSURE REDUCING VALVE
-	PRESSURE SENSOR
	Pounds per square inch Return air
	REVOLUTIONS PER MINUTE
RT	ROOFTOP UNIT
	SUCTION
	SUPPLY AIR SMOKE-FIRE DAMPER
	SENSIBLE HEAT CAPACITY
SL	SILENCER
	TEMPERATURE DIFFERENCE
	TEMPERATURE CONTROL
TEF	TOILET EXHAUST FAN
	THRU JOIGT ABOVE
	TOTAL STATIC PRESSURE
	UNDERCUT DOOR
	UNIT HEATER
	VENT VARIABLE AIR VOLUME
	VARIABLE AIR VOLUME VARIABLE FREQUENCY DRIVE
WC	WATER COLUMN
WPD	WATER PRESSURE DROP

### **GENERAL NOTES**


- A. WORK SHALL COMPLY WITH LOCAL, MUNICIPAL, AND STATE HYAC CODES.
- B. COMMISSIONING: THE OWNER WILL HIRE A COMMISSIONING AGENCY (CXA) TO COMMISSION THE MECHANICAL SYSTEMS FOR THIS PROJECT. THE CXA WILL DEVELOP A COMMISSIONING PLAN THAT WILL OUTLINE THE REQUIREMENTS AND PROCEDURES FOR EACH COMMISSIONED SYSTEM AND WILL BE RESPONSIBLE THAT THE COMMISSIONING MEETS THE REQUIREMENTS OF THE CURRENT ENERGY CODE. THE COMMISSIONING PLAN WILL BE DEVELOPED AFTER CONTRACTS HAVE BEEN AWARDED AND PRIOR TO COMPLETION OF THE SYSTEMS TO BE COMMISSIONED.
- C. THE SCOPE OF WORK SPECIFIED HEREIN AND IN THE SPECIFICATIONS SHALL BE PERFORMED UNDER THE DIRECTION OF A CONSTRUCTION MANAGER. REFER TO THE CONSTRUCTION MANAGER'S INSTRUCTIONS AND DIRECTIONS FOR DETAILS RELATING TO THE EXACT SCOPE OF EACH TRADE. ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS AND CONSTRUCTION MANAGER'S DIRECTIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER FOR CLARIFICATION. THE ARCHITECT/ENGINEER'S DECISION SHALL BE FINAL.
- D. LAYOUT IS DIAGRAMMATIC AND CONTRACTOR SHALL INSTALL DUCTWORK, PIPING AND EQUIPMENT TO MEET ACTUAL FIELD CONDITIONS. REVIEW PROJECT SPECIFICATIONS BEFORE STARTING ANY WORK. SUBMIT SHOP DRAWINGS OF WORK AS PER SPECIFICATIONS.
- E. LAYOUT WORK TO AVOID CONFLICTS BETWEEN DUCTWORK, LIGHTING, CEILINGS, PIPING AND BUILDING STRUCTURE.
- F. COORDINATE EQUIPMENT ELECTRICAL REQUIREMENTS (VOLTAGES, PHASE, LOAD, ETC.) BEFORE ORDERING ANY EQUIPMENT.
- G. SOME CEILING SPACES ARE RETURN AIR PLENUMS AS INDICATED ON PLANS. EXAMINE PLENUM BEFORE CEILING IS INSTALLED (OR REPLACED) AND COORDINATE THE SEALING OF OPENINGS AROUND PIPING, DUCTWORK, CONDUIT, ETC., AND OPENINGS TO OUT-OF-DOORS AND ADJACENT SPACES. COORDINATE THE INSTALLATION OF PARTITIONS/DIVIDERS WITHIN CEILING SPACE AS REQUIRED TO CONFINE RETURN PLENUM TO AREAS INDICATED.
- H. COORDINATE EXACT LOCATION OF CEILING REGISTERS, GRILLES AND DIFFUSERS WITH LIGHTING LAYOUT, SPRINKLER HEADS, AND CEILING GRID. SEE ARCHITECTURAL REFLECTED CEILING PLAN. VERIFY EXACT LOCATION IN FIELD PRIOR TO INSTALLATION. VERIFY CEILING STYLES AND TYPES BEFORE ORDERING REGISTERS, GRILLES AND DIFFUSERS. PROVIDE APPROPRIATE FRAME STYLES AS REQUIRED TO MATCH CEILING STYLE AND TYPES. SET ADJUSTABLE BLADES AS REQUIRED FOR OPTIMUM AIR PATTERN AND TO PREVENT DRAFTS. THE MINIMUM DISTANCE BETWEEN SUPPLY DIFFUSERS/REGISTERS AND SMOKE OR HEAT DETECTORS IS TO BE A MINIMUM OF 3'. COORDINATE WITH FIRE ALARM SYSTEM AS REQUIRED.
- I. ROUTE DUCTWORK AS HIGH AS POSSIBLE TO AVOID CONFLICTS WITH OTHER TRADES. ROUTE DUCTWORK BETWEEN AND THROUGH JOIST SPACES AND BETWEEN LIGHT FIXTURES AS REQUIRED. VERIFY CONDITIONS AND DUCTWORK ROUTING IN FIELD PRIOR TO INSTALLATION.
- J. DUCTWORK, PIPING, EQUIPMENT, ETC. SHALL NOT BE SUPPORTED FROM THE BOTTOM CHORD OF ENGINEERED JOISTS WITHOUT WRITTEN APPROVAL FROM THE STRUCTURAL ENGINEER.
- K. FLEXIBLE DUCTWORK SHALL BE UL LABELED FOR USE IN RETURN AIR PLENUM. ACOUSTICAL FLEXIBLE DUCTWORK AT THE INLET TO AIR DIFFUSERS MAY BE USED. FLEXIBLE CONNECTIONS SHALL BE 5'-0" MAXIMUM LENGTH, AND SHALL BE SUPPORTED WHERE REQUIRED TO PREVENT MOVEMENT.
- L. PROVIDE MANUAL BALANCING DAMPERS AT EACH SUPPLY AIR DUCT AND EACH LOW PRESSURE SUPPLY AIR, RETURN AIR AND EXHAUST DUCTWORK TAKE-OFF INCLUDING TAKEOFFS TO EACH AIR DISTRIBUTION DEVICE. DAMPERS SHALL HAVE LOCKING QUADRANT REGULATORS WITH SPRING LOADED END BEARING. INSTALLATION SHALL BE RATTLE FREE. BE RESPONSIBLE FOR LOCATING BALANCING DEVICES AND COORDINATE LOCATIONS FOR TESTING AND BALANCING.
- M. TRANSFER AIR RETURN GRILLES TO CEILING RETURN PLENUM ARE TO BE PROVIDED WITH A 90 DEGREE MITERED ELBOW ACOUSTICALLY LINED WITH 1/2" THICK DUCT LINER. SEE DETAIL ON PLANS.
- N. RETURN AIR OPENINGS AND TRANSFER AIR OPENINGS IN CEILING PLENUMS ARE TO BE COVERED BY 1/2" X 1/2" SCREEN MESH. PROVIDE ADDITIONAL TRANSFER AIR OPENINGS THROUGH WALLS DIVIDING CEILING RETURN PLENUMS. TRANSFER AIR OPENINGS TO BE SIZED FOR A MAXIMUM VELOCITY OF 500 FPM AT PEAK CONDITIONS. PROVIDE FIRE OR SMOKE/FIRE DAMPERS IN OPENINGS AS NECESSARY.
- O. LOCATE VAV BOXES IN ACCESSIBLE LOCATIONS. ARRANGE CONTROLS OF VAV BOX AS REQUIRED FOR MAXIMUM ACCESSIBILITY. PROVIDE ACCESS DOORS WHEN REQUIRED. MEDIUM PRESSURE DUCTWORK TAKE-OFFS TO VAV BOXES SHALL BE MADE WITH 45 DEGREE TAKE-OFF FITTINGS, CONICAL FITTINGS, AND/OR ENLARGED ENTRANCE LOW-LOSS TAKE-OFF FITTINGS. PROVIDE MINIMUM 2'-Ø' STRAIGHT INLET DUCT TO UPSTREAM OF VAV BOXES. PROVIDE DUCTWORK TRANSITION FROM VAV BOX OUTLET TO DUCT SIZE DOWNSTREAM OF VAV BOX INDICATED ON PLAN.
- P. BAROMETRIC RELIEF DAMPERS TO BE EQUIVALENT TO AMERICAN WARMING MODEL BD-52 LOW LEAKAGE DAMPERS SET AT 0.05" SP.
- Q. VERIFY EXACT THERMOSTAT AND SENSOR LOCATIONS IN FIELD PRIOR TO ROUGH-IN OR INSTALLATION. CONTROL WIRING TO BE ROUTED IN CONDUIT.
- R. PROVIDE AGA APPROVED GAS REGULATOR AT EQUIPMENT REQUIRING LOWER GAS PRESSURE THAN PROVIDED, INCLUDING PIPING BRANCHES SERVING EXISTING EQUIPMENT AND APPLIANCES TO REMAIN. EXTEND GAS REGULATOR VENTS LINE SIZE TO ATMOSPHERE AS REQUIRED. DO NOT COMBINE VENT LINES.
- S. REFRIGERANT PIPING INSTALLATION INCLUDING SIZING IS TO BE AS PER MANUFACTURER'S RECOMMENDATIONS FOR THE ACTUAL FIELD ROUTING AND FOR THE EQUIPMENT PROVIDED. PROVIDE ALL SUCTION LINE TRAPS, SOLENOID VALVES, SIGHT GLASSES AND FILTER/DRIERS AS PER EQUIPMENT MANUFACTURER'S RECOMMENDATIONS.
- T. COORDINATE PHASING OF WORK AND PROVIDE TEMPORARY EQUIPMENT, DUCTWORK AND PIPING AS REQUIRED FOR THE IMPLEMENTATION OF WORK WHILE MAINTAINING SERVICES TO PORTIONS OF BUILDING TO REMAIN OCCUPIED.
- U. SCHEDULE WORK TO AVOID DOUNTIME AND INCONVENIENCE TO OWNER OWNER'S EXISTING FACILITY SHALL REMAIN IN OPERATION AT ALL TIMES. REQUIRED SHUTDOWN OF EXISTING UTILITIES SHALL BE SCHEDULED WITH OWNER'S OPERATING PERSONNEL. NOTIFY OWNER'S REPRESENTATIVE 48 HOURS IN ADVANCE PRIOR TO ANY SHUTDOWN OF EXISTING MECHANICAL SYSTEMS.
- V. VISIT SITE PRIOR TO BIDDING TO FULLY DETERMINE FIELD CONDITIONS AND TO VERIFY EXISTING MECHANICAL SYSTEMS INCLUDING QUANTITIES AND LOCATIONS TO DETERMINE THE FULL EXTENT OF NEW AND DEMOLITION WORK.
- W. COORDINATE NEW INSTALLATIONS WITH EXISTING SYSTEMS. ANY EXISTING CONDUIT, PIPING, DUCTWORK, EQUIPMENT, ETC., SHALL BE REWORKED AS REQUIRED TO AVOID CONFLICTS WITH THE INSTALLATION OF THE NEW MECHANICAL SYSTEMS. NO EXTRAS WILL BE ALLOWED AFTER BIDDING FOR ANY REWORK OF EXISTING FIELD CONDITIONS TO RESOLVE ANY CONFLICTS OR NOT FULLY UNDERSTANDING THE SCOPE OF THE WORK REQUIRED. EXISTING EQUIPMENT, DUCTWORK, PIPING, ETC., SHALL BE REMOVED AS NOTED ON DRAWINGS AND AS REQUIRED TO MEET SCOPE OF NEW WORK.
- X. EXISTING INFORMATION IDENTIFIED ON THE CONTRACT DOCUMENTS IS SCHEMATIC ONLY. BE RESPONSIBLE TO PROPERLY ADDRESS EXISTING CONDITIONS FOR A COMPLETE AND PROPER INSTALLATION OF NEW SYSTEMS. EXISTING EQUIPMENT NOT IDENTIFIED SHALL BE REVIEWED AS TO WHETHER THE EQUIPMENT SHALL REMAIN AND BE RECONNECTED TO THE NEW SERVICES, BE RELOCATED, BE ABANDONED, ETC.
- Y. ANY HIDDEN CONDITIONS IDENTIFIED THROUGH THE COURSE OF CONSTRUCTION SHALL BE IMMEDIATELY REPORTED IN WRITTEN FORM FOR REVIEW AND DIRECTION. OTHERWISE, BE RESPONSIBLE FOR ANY AND REQUIRED CHANGES AND COSTS TO CORRECT SAID HIDDEN CONDITION.
- Z. REMOVE EXISTING EQUIPMENT, PIPING, DUCTWORK, ETC. PRESENTLY SERVING AREAS THAT ARE BEING RENOVATED AND THAT ARE NOT REQUIRED TO STAY IN SERVICE. NO EQUIPMENT, DUCTWORK, PIPING, SUPPORTS, HANGERS, ETC, IS TO BE LEFT ABANDONED. VERIFY QUANTITY, LOCATION AND ELEVATION OF EXISTING TO BE REMOVED IN FIELD. REMOVE EXISTING ABANDONED EQUIPMENT, DUCTWORK AND PIPING IN AREAS THAT ARE TO BE RENOVATED.


- AA. REMOVED DUCTWORK, PIPING AND CONTROLS ARE TO BE TERMINATED PROPERLY BACK TO EXISTING MAINS. PATCH AND SEAL EXISTING DUCTWORK AIRTIGHT. CAP PIPING WATERTIGHT. PROVIDE ADDITIONAL DUCTWORK, PIPING AND CONTROLS AS REQUIRED TO MAINTAIN CONTINUITY OF EXISTING SYSTEMS MODIFIED DUE TO REMOVAL OF PORTION OF SYSTEMS. REPAIR DAMAGED DUCTWORK AND PIPING INSULATION DUE TO NEW
- INSTALLATION WORK. BB.CAPTURE EXISTING REFRIGERANT FROM EXISTING REFRIGERANT PIPING AS REQUIRED AND REUSE OR DISPOSE OF IN A LEGAL MANNER.
- CC. EXISTING EQUIPMENT SHALL REMAIN PROPERTY OF THE OWNER AND OWNER SHALL DETERMINE IF EQUIPMENT IS TO BE STORED ON SITE AT OWNER SELECTED LOCATION OR IF EQUIPMENT IS TO BE ABANDONED OR REMOVED FROM SITE.
- DD.PATCH EXISTING CEILING, FLOOR, WALL AND ROOF OPENINGS AND SURROUNDING FINISHES RESULTING FROM REMOVAL OF EXISTING MATERIALS AND EQUIPMENT SO THAT FINISH WILL MATCH EXISTING IN SURROUNDING AREAS. OPENINGS IN MASONRY WALLS RESULTING FROM REMOVED THERMOSTATS ARE TO BE COVERED WITH A BLANK STAINLESS STEEL COVER PLATE.
- EE. PROVIDE AND INSTALL PVC PIPE PLENUM WRAP, TESTED TO UL 84 AND UL 910, FOR ALL EXISTING PVC PIPING IN NEW OR EXISTING RETURN AIR CEILING PLENUMS.
- FF. PROVIDE FINISHING OF EXISTING CEILING, FLOOR, AND WALL SURFACES AT LOCATIONS AFFECTED BY REMOVAL OF EXISTING MATERIALS AND EQUIPMENT SO THAT NEW FINISH WILL MATCH EXISTING IN SURROUNDING AREAS.
- GG. REMOVE EXISTING CEILINGS AND LIGHT FIXTURES REQUIRED FOR INSTALLATION OF NEW WORK. REINSTALL CEILING AND LIGHT FIXTURES UPON COMPLETION OF WORK. REPLACE DAMAGED CEILING MATERIALS TO MATCH EXISTING.
- HH. PROVIDE CUTTING, CORE DRILLING AND PATCHING OF EXISTING WALL AND ROOF CONSTRUCTIONS REQUIRED FOR THE INSTALLATION OF NEW DUCTWORK, PIPING AND EQUIPMENT. SEAL PENETRATIONS THROUGH WALL AND ROOF STRUCTURE WATERTIGHT AND WITH AN APPROVED FIRE STOPPING MATERIAL, INCLUDING APPROVED FIRE RATED SLEEVE.
- II. PROVIDE STEEL ANGLE SUPPORTS FOR NEW ROOFTOP EQUIPMENT AND SUPPORT RAILS/CURBS. PROVIDE STEEL ANGLE FRAMES AROUND DUCT PENETRATIONS. SECURELY ANCHOR SUPPORTS AND FRAMES TO EXISTING STEEL JOISTS AND BEAM. REWORK EXISTING ROOFING AND INSULATION AND FLASH INTO EXISTING ROOFING TO PROVIDE A WEATHERTIGHT CONDITION AND TO MAINTAIN WARRANTY.
- JJ. PROVIDE STEEL LINTELS FOR NEW OPENINGS THROUGH EXISTING MASONRY WALLS AS REQUIRED. LINTELS TO BE AS FOLLOWS UNLESS NOTED OTHERWISE ON ARCHITECTURAL DRAWINGS: TWO (2) 3-1/2"X3-1/2"X 5/16" ANGLES WITH 5/16" PLATE (1/2" LESS THAN WALL THICKNESS). PROVIDE WAXID WITH 5/16" PLATE FOR OPENINGS ABOVE 48" WIDE.
- KK WORK ON THE ROOF SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE EXISTING ROOFING MANUFACTURER'S RECOMMENDATIONS. ROOF WORK SHALL BE PERFORMED BY CERTIFIED INSTALLERS AS TO MAINTAIN THE EXISTING ROOF WARRANTY. PRIOR TO THE START OF ANY WORK ON THE ROOF, EXISTING ROOF SHALL BE INSPECTED AND CERTIFIED BY THE EXISTING ROOFING MANUFACTURER. ANY DEFICIENCIES WHICH OCCUR BETWEEN THE INITIAL AND FINAL INSPECTIONS SHALL BE CORRECTED AT NO COST TO THE OWNER. CORRECTIVE MEASURES SHALL BE PERFORMED BY CERTIFIED INSTALLERS TO MAINTAIN THE EXISTING ROOF WARRANTY.
- LL. MOUNT NEW THERMOSTATS IN EXISTING SPACES AT LOCATIONS VACATED BY OLD THERMOSTAT WHEN POSSIBLE. REUSE EXISTING CONDUIT IF FOUND TO BE IN GOOD CONDITION.
- MM. PROVIDE AN APPROVED SURFACE MOUNTED RACEWAY AS REQUIRED FOR INSTALLATION OF NEW THERMOSTATS ON EXISTING WALLS TO CONCEAL CONTROL WIRING. SUBMIT SAMPLE OF RACEWAY FOR REVIEW. COORDINATE ROUTING OF RACEWAYS WITH EXISTING BUILDING CONDITIONS AND ADJUST ROUTING TO AVOID CONFLICTS AND TO MINIMIZE THE AMOUNT OF EXPOSED SURFACE MOUNTED RACEWAY.
- NN. REPAIR AND/OR REPLACE DAMAGED PIPE INSULATION THAT OCCURS AS THE RESULT OF THIS CONSTRUCTION.
- 00.MINIMUM SIZE FOR HOT WATER HEATING SUPPLY AND RETURN PIPING TO BE 3/4". PP. DRAIN AND REFILL EXISTING PIPING SYSTEMS AS REQUIRED
- FOR INSTALLATION OF NEW WORK. PROVIDE CHEMICAL TREATMENT, GLYCOL/ANTI-FREEZE MIXTURE FOR WATER PIPING SYSTEM ACCORDING TO OWNER'S REQUIREMENTS AFTER SYSTEM IS FILLED AND VENTED. PROPERLY VENT PIPING SYSTEMS.
- QQ.PROVIDE CONCRETE EQUIPMENT PADS FOR EQUIPMENT INDICATED ON DRAWINGS. COORDINATE LOCATIONS BEFORE INSTALLATION. PADS ARE TO BE DESIGNED WITH REINFORCEMENT TO HANDLE THE WEIGHT OF THE EQUIPMENT BEING SUPPORTED. EXTERIOR CONCRETE PADS TO BE PROVIDED WITH FROST WALLS (MINIMUM OF 48" BELOW GRADE).
- RR PROVIDE WATERTIGHT 4" HIGH CONCRETE CURBS AROUND DUCTWORK AND PIPING FLOOR OPENINGS IN MECHANICAL ROOMS LOCATED ABOVE FINISHED SPACES.
- 55. PROVIDE CONDENSATE PIPING FROM ROOF TOP HVAC UNITS, COOLING COIL DRAIN PANS, CONDENSATE PUMPS, HUMIDIFIERS, FURNACES, ETC. AS REQUIRED TO ROOF, NEAREST DRAIN OR TO WHERE INDICATED ON DRAWINGS. THE PIPING IS TO BE THE SAME SIZE AS THE EQUIPMENT CONNECTION SIZE. PROVIDE TRAPS IN CONDENSATE PIPING PER EQUIPMENT MANUFACTURER'S RECOMMENDATIONS.
- TT. PROVIDE CONDENSATE PUMPS, RECEIVERS, PIPING AND ELECTRICAL CONNECTIONS AS REQUIRED AT EQUIPMENT WHERE EQUIPMENT DRAINS CANNOT BE DRAINED BY GRAVITY DUE TO FIELD CONDITIONS.
- UL PROVIDE APPURTENANCES (I.E. EXPANSION COMPENSATORS, FLEXIBLE CONNECTIONS, EXPANSION LOOPS, JUNCTION BOXES, ETC.) NECESSARY TO CROSS EXPANSION JOINTS IN BUILDING CONSTRUCTION WITH CONDUIT, PIPING, DUCTWORK, ETC. REFER TO ARCHITECTURAL DRAWINGS FOR LOCATION AND QUANTITY OF EXPANSION JOINTS.
- VV. PROVIDE STRUCTURAL SUPPORT FOR FREE STANDING AND WALL MOUNTED PANELS, VFD'S, MOTOR STARTERS, ETC. IN MECHANICAL ROOMS AS REQUIRED.
- WW. ADJUST NEW ROOF-TOP EQUIPMENT LOCATIONS BEING INSTALLED ON EXISTING ROOF LOCATIONS AS REQUIRED TO COORDINATE WITH EXISTING STRUCTURAL CONDITIONS. PROVIDE OUTSIDE AIR-INTAKE EXTENSIONS WITH DUCTWORK SUPPORTS AS REQUIRED TO MAINTAIN MINIMUM 10 FEET CLEARANCE BETWEEN OAI OPENING AND ANY EXHAUST OR VENT LOCATION. EXISTING CEILING SPACES ARE MINIMAL HEIGHT - COORDINATE DUCTWORK INSTALLATION BETWEEN STRUCTURAL JOISTS, CEILING AND LIGHT FIXTURES AS REQUIRED. PROVIDE INCREASE HEIGHT ROOF CURBS AS REQUIRED TO DUCTWORK TRANSITIONS BETWEEN EXISTING STRUCTURAL COMPONENTS.
- XX. PROVIDE VENT PIPING FROM ALL GAS PRESSURE REDUCING STATIONS. PIPING TO BE ROUTED TO THE EXTERIOR OF BUILDING AS REQUIRED. MULTIPLE RELIEFS ARE TO BE PIPED INDIVIDUALLY, NOT GROUPED TOGETHER IN A COMMON HEADER. THE PIPING IS TO BE SAME SIZE AS RELIEF CONNECTION TO EQUIPMENT. TERMINATION LOCATION TO MEET ALL CODE REQUIREMENTS AND BE APPROVED BY ARCHITECT.
- YY. PROVIDE RELIEF VENT PIPING FOR REFRIGERATION EQUIPMENT. PIPING TO BE ROUTED TO THE EXTERIOR OF BUILDING AS REQUIRED. MULTIPLE RELIEFS ARE TO BE PIPED INDIVIDUALLY, NOT GROUPED TOGETHER IN A COMMON HEADER. THE PIPING IS TO BE SAME SIZE AS RELIEF CONNECTION TO EQUIPMENT. TERMINATION LOCATION TO MEET CODE REQUIREMENTS AND BE APPROVED BY ARCHITECT.
- ZZ. PROVIDE A WATERTIGHT SHEET METAL DRIP PAN OVER ELECTRICAL EQUIPMENT INSTALLED UNDER OR NEAR PIPING SYSTEMS. DRIP PAN TO EXTEND MINIMUM 3" OVER FRONT AND SIDES OF ELECTRICAL EQUIPMENT AND BE PITCHED AT A MINIMUM 30 DEGREE ANGLE. SEAL DRIP PAN WATERTIGHT TO WALL.
- AAA.REMOVE EXISTING DOORS AND PORTIONS OF WALLS, CEILINGS, ETC. AS REQUIRED TO INSTALL NEW MATERIAL AND EQUIPMENT IN EXISTING LOCATIONS. REBUILD WALLS, CEILINGS AND REINSTALL EXISTING DOORS AS REQUIRED AFTER INSTALLATION OF NEW MATERIAL AND EQUIPMENT. PATCH AND FINISH TO MATCH EXISTING.
- BBB. PROVIDE ROOF PIPING SUPPORTS FOR PIPING ROUTED ALONG ROOF. SINGLE PIPE SUPPORTS TO BE EQUIVALENT TO PORTABLE PIPE HANGER, INC. TYPE PP-10 ROLLER GUIDE SUPPORT. MULTIPLE PIPE SUPPORTS TO BE EQUIVALENT TO PORTABLE PIPE HANGER, INC. TYPE PPI0 CHANNEL GUIDE SUPPORT. SUPPORTS ARE TO BE INSTALLED AS PER MANUFACTURER'S RECOMMENDATIONS. SUPPORTS TO BE COMPATIBLE WITH AND MAINTAIN THE INTEGRITY (AND EXISTING WARRANTY IF APPLICABLE) OF THE EXISTING OR NEW ROOF SYSTEM.

RCHITECTURE •	
9102 N. Meridia Indianapolis, IN	GibraltarDesign.com altarDesign.com 5777 Fax 317.580.5778 G. JANHU REGISTERED NO. 10302590 ★
DRAWN BY KS CHECKED BY DJ COPYRIGHT NOTICE: THE CONCEPTS, DESIGN: THIS INFORMATION SHAL FOR ANY PURPOSE WIT OF GIBRALTAR DESIGN.	S, PLANS, DETAILS, ETC, SHOWN ON HE PROPERTY OF GIBRALTAR DESIGN AND E USED BY ANY PERSON OR FIRM HOUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS
REVISIONS MARK DATE AD-3 03/03/22	ISSUED FOR ADDENDUM NO. 3
DRAWING MECHANIC SYMBOLS ABBREVIA	
PROJECT TIMOTHY BAI RENOVATION	L ES ADDITIONS AND
© GIBRALTAR DESIGN	sheet <b>M-001</b>


$\bigcirc$	SHEET NOTES
1.	REMOVE EXISTING SUPPLY AIR DIFFUSER AND ASSOCIATED SUPPLY AIR DUCTWORK COMPLETE AS REQUIRED.
2.	REMOVE EXISTING ABOVE CEILING FAN COIL UNIT AND ASSOCIATED DUCTWORK, REFRIGERANT PIPING, CONDENSING UNIT, THERMOSTATS, CONTROLS, ELECTRICAL CONNECTIONS, ETC. COMPLETE AS REQUIRED.
З.	REMOVE EXISTING POWERED TERMINAL UNIT AND ASSOCIATED DUCTWORK, CHILLED WATER PIPING, HOT WATER PIPING, VALVES, THERMOSTATS, CONTROLS, ELECTRICAL CONNECTIONS, ETC. COMPLETE AS REQUIRED.
4.	REMOVE EXISTING CABINET HEATER AND ASSOCIATED HOT WATER PIPING, CONTROLS, THERMOSTATS, ELECTRICAL CONNECTIONS, ETC. COMPLETE AS REQUIRED.
5.	REMOVE EXISTING RETURN AIR GRILLE AND ASSOCIATED RETURN AIR DUCTWORK COMPLETE AS REQUIRED.
6.	REMOVE EXISTING EXHAUST GRILLE AND ASSOCIATED EXHAUST DUCTWORK COMPLETE AS REQUIRED.
٦.	REMOVE EXISTING THERMOSTAT AND ASSOCIATED CONTROL WIRING COMPLETE AS REQUIRED.
8.	REMOVE EXISTING HOT WATER SUPPLY & RETURN PIPING AND ASSOCIATED VALVES, ETC. COMPLETE AS REQUIRED.
9.	REMOVE EXISTING CHILLED WATER SUPPLY & RETURN PIPING AND ASSOCIATED VALVES, ETC. COMPLETE AS REQUIRED.
10.	REMOVE EXISTING TRANSFER AIR GRILLE AND ASSOCIATED DUCTWORK COMPLETE AS REQUIRED.
11.	REMOVE EXISTING CONDENSATE DRAIN PIPING COMPLETE
12.	REMOVE EXISTING ABANDONED FIN TUBE AND ASSOCIATED HOT WATER SUPPLY AND RETURN PIPING, CONTROLS, ETC. COMPLETE AS REQUIRED.

AD-3







REMOVE-EXISTING EXHAUST GRILLE





AD-3

VESTIBULE B-106 -











### UNIT "B" MECHANICAL MEZZANINE DEMOLITION PLAN SCALE: 1/8" = 1'-0"





- AD-3
- ASSOCIATED DUCTWORK, REFRIGERANT PIPING, CONDENSING UNIT, THERMOSTATS, CONTROLS, ELECTRICAL CONNECTIONS, ETC. COMPLETE AS REQUIRED. 4. CONNECTIONS, ETC. COMPLETE AS REQUIRED. 5. REMOVE EXISTING EXHAUST GRILLE AND ASSOCIATED EXHAUST DUCTWORK COMPLETE AS REQUIRED. REMOVE EXISTING TRANSFER AIR GRILLE AND 6. ASSOCIATED DUCTWORK. COMPLETE AS REQUIRED. REMOVE EXISTING THERMOSTAT AND ASSOCIATED CONTROL WIRING COMPLETE AS REQUIRED. 8. 9, REQUIRED. AS REQUIRED. REMOVE EXISTING EXHAUST FAN AND ASSOCIATED 11. CONNECTIONS, ETC COMPLETE AS REQUIRED. REMOVE AND RELOCATE EXISTING TEMPERATURE 12. CONTROL PANELS. DISCONNECT ELECTRICAL 13. CLEAN, LUBRICATE AND CHECK EXISTING UNIT FOR
  - REMOVE EXISTING CABINET HEATER AND ASSOCIATED HOT WATER PIPING, CONTROLS, THERMOSTATS, ELECTRICAL

SHEET NOTES

SUPPLY AIR DUCTWORK COMPLETE AS REQUIRED.

ASSOCIATED DUCTWORK, CHILLED WATER PIPING, HOT WATER PIPING, VALVES, THERMOSTATS, CONTROLS,

REMOVE EXISTING ABOVE CEILING FAN COIL UNIT AND

ELECTRICAL CONNECTIONS, ETC. COMPLETE AS REQUIRED.

REMOVE EXISTING POWERED TERMINAL UNIT AND

REMOVE EXISTING SUPPLY AIR DIFFUSER AND ASSOCIATED

 $\bigcirc$ 

3.

15.

\_ \_\_ \_\_ \_\_ \_\_ \_\_ \_\_ \_\_

AD-3

AD-3

AD-3

REMOVE EXISTING

DIFFUSER

RELIEF TO

 $\mathcal{M}$ 

RELIEF '

REMOVE EX

REMOVE

EXISTING

DIFFUSER

SUPPLY AIR

+----

REMAIN

REMAIN

(10)

SUPPLY AIR

- REMOVE EXISTING HOT WATER SUPPLY & RETURN PIPING

- AND ASSOCIATED VALVES, ETC. COMPLETE AS REQUIRED.

- REMOVE EXISTING CHILLED WATER SUPPLY & RETURN
- PIPING AND ASSOCIATED VALVES, ETC. COMPLETE AS
- 10. REMOVE EXISTING CONDENSATE DRAIN PIPING COMPLETE
- EXHAUST DUCT, EXHAUST GRILLE, CONTROLS, ELECTRICAL
- CONNECTIONS, CONTROLS, ETC. COMPLETE AS REQUIRED.
- PROPER OPERATION AND SUBMIT REPORT FOR ANY UNIT
- DEFICIENCIES. CHANGE FILTERS AND PROVIDE NEW BELTS. 14.


REMOVE EXISTING ABANDONED FIN TUBE AND


CONTROLS, ETC. COMPLETE AS REQUIRED.


REMOVE EXISTING HOT WATER AND CHILL WATER COIL FROM AIR HANDLER AND ASSOCIATED VALVES, ETC. 


ASSOCIATED HOT WATER SUPPLY AND RETURN PIPING,


<image/> <section-header><section-header><section-header><section-header><text><text><text><text><text><text><text><text></text></text></text></text></text></text></text></text></section-header></section-header></section-header></section-header>
Image: constraint of the system of the sy
COPYRIGHT NOTICE:         THE CONCEPTS, DESIGNS, PLANS, DETAILS, ETC, SHOWN ON         THIS DOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND         WERE CREATED FOR USE ON THIS SPECIFIC PROJECT. NONE OF         THIS INFORMATION SHALL BE USED BY ANY PERSON OR FIRM         FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT         OF GIBRALTAR DESIGN. THE OWNER MAY RETAIN COPIES FOR         INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS         PROJECT.         REVISIONS         MARK       DATE         ISSUED FOR         AD-3       03/03/22         ADDENDUM NO.       3
DRAWING UNIT "A" SECOND FLOOR & UNIT "B" MEZZANINE MECHANICAL DEMOLITION PLANS PROJECT TIMOTHY BALL ES ADDITIONS AND RENOVATIONS
© gibraltar design SHEET A,B MD102





















UNIT "B" MECHANICAL MEZZANINE PIPING PLAN SCALE: 1/8" = 1'-0"
















SHEET NOTES


EXTEND CONDENSATE PIPING FROM UNIT THRU WALL. TERMINATE WITH 45 DEGREE ELBOW DOWN TO GRADE. SLEEVE AND SEAL PIPE THROUGH WALL PENETRATION WEATHERTIGHT.








# SHEET NOTES


EXTEND CONDENSATE PIPING FROM UNIT THRU WALL. TERMINATE WITH 45 DEGREE ELBOW DOWN TO GRADE. SLEEVE AND SEAL PIPE THROUGH WALL PENETRATION WEATHERTIGHT.




















$\bigvee$		1											AL EQU												
TAG	MANUFACTURER	MODEL NUMBER	DESCRIPTIO	N	FAN MO MIN. OA	I CFM			<u>200LING</u>	EQUIP/COIL DATA	GAS FIRED HEATI			COOLING				HOT WATER HEAT			<b>E</b> I			UNITS	
					CFM HIGH	Low ESP BHP HP	RPM CFM ESP	BHP HP RPM MBH SH			T STGS (IN) (OUT) EAT	LAT STGS				B LWB EWT LWT		(IN) (OUT) GPT	1 EAT LAT EWT LWT W	PD HP MCA FL				BY	
H-3	TRANE	CSAAØØ8	INTERIOR CENTRAL STATION A HOT WATER HEATING / CHILLED U	AIR HANDLING UNIT	3950 665	- 2.5 6.6 8	3396		•   •				143 113 28,6	78.1 E	52.9 <b>50.</b> 	1 49.4 44 54	15 -	- 54.1 5.4	-10 65 160 140	15 - 16 1		480 3 60	0 × -	FMS	שרו
B-1	~ A tai 10						- 3350 1.1	1.55 6 1542 -						-	•   •			2020 1021 100		- 6 - ·			0 × -	FMS	
	CAMUS	AR-2000 AR-2000	GAS FIRED H.W. CONDENSING BOILER GAS FIRED H.W. CONDENSING BOILER												-   -			2000 1886 189 2000 1886 189			8 - 15 8 - 15		0 × -	FMS	20
B-2 B-3	CAMUS	AR-2000 AR-2000	GAS FIRED H.W. CONDENSING BOILER GAS FIRED H.W. CONDENSING BOILER												-   -			2000 1886 189			8 - 15 8 - 15		0 × -	FMS FMS	20
8-3 RT-1	TRANE	HAEAØ12C3	ROOF MOUNTED GAS FIRED / DX COOL		4585 780		2Ø34 4585 2	2.08 3 1800 131 12	2 <b>-</b>	62 53 5 <sup>2</sup> of	MOD 300 240 56	105 MOD											0 × - 0 × -	FMS	43
RT-1	TRANE	HAEA015C3	ROOF MOUNTED GAS FIRED / DX COOL				2034 4585 2	1.3 2 1430 180 13	3 78			56 MOD								- 10 		480 3 60		FMS	4:
RT-2A	TRANE	HAEA015C3	ROOF MOUNTED GAS FIRED / DX COO				2231 4850 1	1.3 2 1430 180 13			MOD 200 160 26									Al			0 × -	FMS	48
	ENGINEERED AIR		VERTICAL UNIT VENTILATOR - 4 PI		800 380	1/3							29.9 205 60	80	67 56:	3 55.1 44 54	5 -	- 459 46	40 93 160 140	5			0 × -	FMS	
			VERTICAL UNIT VENTILATOR - 4 PI		1200 450	1/2										2 553 44 54			40 90 160 140	5	- 41 -	277 1 60	0 × -	FMS	5
			VERTICAL UNIT VENTILATOR - 4 PI			3/4											-		40 93 160 140	5		277 1 60	0 × -		
			VERTICAL UNIT VENTILATOR - 4 PI			3/4										1 54.4 44 54			40 95 160 140		- 5.5 -		0 × -	FMS	
FC-1	TRANE	FCCBØ8Ø	SUSPENDED COOLING/HEATING F			- 0.3 0.20 0.22										<b>59.5</b> 44 54			60 127 180 160			120 1 60	0 × -	FMS	18
FC-2	TRANE	FCCB12Ø	SUSPENDED COOLING/HEATING F	AN COIL UNIT - 4 PIPE	1230 100	- Ø.3 Ø.2 Ø.2	1659						32.4 25 6.5	80	67 613	3 58.7 44 54	5 -	- 89.2 8.9	60 127 180 160	5 - 6.1	15	120 1 60	ø × -	FMS	2
	TRANE		CEILING MOUNTED FAN COIL UNIT -	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~											$\sim$		$\sim$								
сн-1			HOT WATER WALL SURFACE MOUN	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		m															$\rightarrow$				
СН-2	TRANE	₩ FFCBØ3Ø	HOT WATER CEILING RECESSED MO	OUNTED CABINET HEATER	300 -	0.0	6 1318							-				- 19.9 1	60 121 180 140	5 - 2.8	15	120 1 60	ø × -	FMS	
СН-3	TRANE	FFHBØ4Ø	HOT WATER SEMI-RECESSED WALL M		400 -	0.0	5 1163							-				- 256 1.3	60 119 180 140	5 - 2.8	15	120 1 60	ø × -	FMS	
СН-4	TRANE	FFHB080	HOT WATER SEMI-RECESSED WALL M			0.13								-					60 118 180 140		15	120 1 60	ø × -	FMS	
СН-5	TRANE	FFHBØ4Ø	HOT WATER RECESSED WALL MOU	NTED CABINET HEATER	400 -	0.0	5 1163							-				- 25.6 1.3	60 119 180 140	5 - 2.8	15	120 1 60	ø × -	FMS	
СН-6	TRANE	FFHB080	HOT WATER RECESSED WALL MOU	NTED CABINET HEATER	800 -	Ø.13								-				- 50 2.5	60 118 180 140	5 - 2.9	15	120 1 60	ø × -	FMS	
ref-1		DCRD-095	ROOF MOUNTED TOILET	EXHAUST FAN			- 240 0.5	Ø.Ø4 1/8 1139 -						-						- 1/8 -		120 1 60	ø × -	FMS	
EF-2		DCRD-035	ROOF MOUNTED TOILET	EXHAUST FAN			- 240 05	Ø.Ø4 1/8 1139 -						-						- 1/8 -		120 1 60	ø × -	FMS	
TEF-3		DCRD-060	ROOF MOUNTED TOILET	EXHAUST FAN			- 140 0.4	0.02 1/6 1661 -	-   -					-						- 1/6 -	-   -   -	120 1 60	ø × -	FMS	
EF-4		DCRD-095	ROOF MOUNTED TOILET	EXHAUST FAN			- 240 0.5	<i>0.0</i> 4 1/8 1139 -	-   -					-						- 1/8 -	-   -   -	120 1 60	ø × -	FMS	
EF-5		DCRD-095	ROOF MOUNTED TOILET	EXHAUST FAN			- 240 0.5	<i>0.0</i> 4 1/8 1139 -	•   -					-						- 1/8 -		120 1 60	ø × -	FMS	
EF-6		DCRD-180	ROOF MOUNTED TOILET	EXHAUST FAN			- 2400 0.8	Ø.73 I 1050 -	•   -					-			-   -			- 1 -	-   -   -	120 1 60	ø × -	FMS	
'EF-7		DCRD-120	ROOF MOUNTED TOILET	EXHAUST FAN			- 930 0.6	Ø.19 1/3 1445 -	·   -					-		-   -				- 1/3 -		120 1 60	ø × -	FMS	
TEF-8	TWIN CITY	DCRD-085	ROOF MOUNTED TOILET	EXHAUST FAN			- 190 0.4	<i>0.0</i> 3 1/8 1159 -						-						- 1/8 -		120 1 60	ø × -	FMS	
TEF-9		DCRD-095	ROOF MOUNTED TOILET	EXHAUST FAN			- 490 0.4	Ø.1 1/8 15Ø2 -	• •					-						- 1/8 -		120 1 60	ø × -	FMS	
EF-1Ø		DCRD-085	ROOF MOUNTED TOILET	EXHAUST FAN			- 160 0.4	0.02 1/8 1000 -						-						- 1/8 -		120 1 60	ø × -	FMS	
TEF-11	TWIN CITY	DCRD-095	ROOF MOUNTED TOILET	EXHAUST FAN			- 430 0.6	<i>0.0</i> 3 1/8 1467 -	•   •					-						- 1/8 -		120 1 60	ø × -	FMS	
r <del>EF</del> -12	TWIN CITY	DSI-164	SQUARE INLINE TOLIET	EXHAUST FAN			- 4030 1	1.61 2 1463 -	•   •					-			-   -		-   -   -   -	- 2 -	-   -   -	208 1 60	ø × -	FMS	
GEF-1		T-500	CEILING MOUNTED GENERAL EXHAUS	T FAN w/ INTEGRAL GRILLE			- 225 Ø.3	0.09 1/4 564 -	•   -		-   -   -   -			-			-   -		-   -   -   -	- 1/4 -	-   -   -	120 1 60	ø × -	FMS	
								0.03 1/8 1449 -												- 1/8 -		120 1 60		FMS	$\rightarrow$
3EF-3				~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~				Ø.15 1/2 985 -												- 1/2 -					
C-1/CU-1	MITSUBISHI	TPKA-A12/TRUY-Ø1:	2 WALL MOUNTED AC UNIT / ROOF MO	OUNTED CONDENSING UNIT	32Ø -			12 ·	•   -	95				-			-   -			11	28	208 1 60	Ø × -	FMS	2
:-2/CU-2			BE WALL MOUNTED AC UNIT / ROOF MO		705 -			36	•   •	95				-						25	30	208 1 60	0 × -	FMS	4
UH-1		HV-18			350 -		1 1350		•   •					-					60 100 180 160			120 1 60	0 × -	FMS	
				~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	480 -														60 100 180 160	5 0.02 -					
H-1							- 545 -		•   •					-	-   -										
		DIØ3ØDIFFPA	30' WIDE KITCHEN EXHAUST				- 545 -																		
PREHE	ATING COIL DATA			NOTE 4: PROVIDE WITH:				NOTE 1: PROVIDE WITH:				NOTE 10: Provide u							DE WITH:						
SEE SP		R ADDITIONAL REQ	UIREMENTS	• INTEGRATED ENTHALPY • DISCONNECT SWITCH • FACE/BYPASS DAMPER				•ECM MOTOR WITH POT •MOTORIZED DAMPER •BIRD SCREEN	ENTIOMET	IER SPEED CONTROL	LLER	• DISCON • VIBRAT	ION ISOLATION HA	NGERS				• EC • MO	CONNECT SWITCH M MOTOR WITH POTENTIOM TORIZED DAMPER		NTROLLER				
• CO1	DE WITH: MBUSTION AIR INT			•FILTERS CONDENGATE RUMP (UH			AD-2	• ROOF CURB SEE SPECIFICATIONS FOR	ADDITIO	NAL REQUIREMENTS		NOTE 11:	FICATIONS FOR AD	DITIONA	al Requi	IREMENTS		• INTI SEE SF	BRATION ISOLATION HANGE EGRAL METAL GRILLE PECIFICATIONS FOR ADDIT	IONAL REQUIREM					
• NEU	TRALIZATION BAS		UIREMENTS.	• 10" DEEP FASLEBACK FOR CONNECTIONS (WHERE IN SEE SPECIFICATIONS FOR A	OR UNITS W/ DL	ICTED OUTSIDE AIR	}	NOTE 8: PROVIDE WITH: • DISCONNECT SWITCH				PROVIDE U • DISCON	UITH: INECT SWITCH TION ISOLATION HA	NGERS				NOTE I	$\qquad \qquad $						
	DE WITH:			NOTE 5: PROVIDE WITH:				• DISCONNECT SWITCH • ECM MOTOR WITH POT • MOTORIZED DAMPER • VIBRATION ISOLATION			LLER	• TERMIN	AL STRIPS FOR DE FICATIONS FOR AD	C REAL		REMENTS			DE WITH: INE FAN ECTRICAL RANGE SHUTOFF MOTE ADA SWITCHES	:	<pre>{</pre>				
• DISC • HINC	CONNECT SWITCH GED ACCESS PAI	NELS		•INTEGRAL THERMOSTAT •DISCONNECT SWITCH				SEE SPECIFICATIONS FOR				NOTE 12: PROVIDE U			. <b>I jenin</b> and an and a	ang χι ann interiore		•FAN •MA	N LIMIT NUAL PULL STATION			-3			
ACC • LOU	DUSTICAL TREATH J LEAK ECONOMI	1ENT ZER DAMPERS		• VIBRATION ISOLATION H SEE SPECIFICATIONS FOR A		QUIREMENTS.		NOTE 9: PROVIDE CONDENSING UN •LOW AMBIENT CONTRO	DLS FOR 1	100% COOLING DOWN	N TO -10°∓.	• DISCON • HINGED	NECT SWITCH ACCESS PANELS			TIAL ENTHALPY SE									
	VERED EXHAUST BGY RECOVERY JBLE WALL CONS	TRUCTION	AD-2	NOTE 5: PROVIDE WITH: •INTEGRAL THERMOSTAT				• EQUIPMENT SUPPORT PROVIDE AC INDOOR UNI • WALL MOUNTED WIRED	Rails Twith:			ACOUS	ION ISOLATION RC TICAL TREATMENT AK ECONOMIZER			HCORE DECK DS-	52								
SEE SP	RIABLE SPEED C	MPRESSOR RADDHIONAL REQ	UIREMENTS.	• DISCONNECT SWITCH SEE SPECIFICATIONS FOR A	DDITIONAL RE	QUIREMENTS.		• CONDENSATE PUMP • WALL MOUNTING HARD SEE SPECIFICATIONS FOR	WARE			• POWER • HUMIDIS	ED EXHAUST FAN		AD-	-2									
													E WALL CONSTRUC		$\gamma$	1									
												SEE SPECI	BLE SPEED COMPR HCANONS FOR AD	DIHONA	L REQUI	REMENTS.									
								$\sim$	~~~~		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~			~~~~	~~~~		~~~~					~~~~~	~~~~~		$\overline{\sim}$
												-								-			-	-	
								}  -			BUPPLY AIR		RETURN AIR			EXHAUGT A				lu lu	EAT WHEEL DI	ISCHARGE			
								AD-2	TAG	SUMMER CFM DB	WINTER WB DB WB		DB WB DE	ter B WB		SUMMER CFM DB WB		NTER DB WB		DB WB	CFM DB	MER	WINTER DB WB		RE
									RT-2A		65.0 F 53.2 52.1 F		75 63 F 72			2,818 86.4 TØ:			2,818 92 74 F			.7 66.5 F		<b>F</b> -	
								\$ [	RT-2B	4,850 77.6 6	65.0 F 53.2 52.7 F	2,670	75 63 F 71	2 53	=	2,818 86.4 70.3	5 F 1	6.1 15.9 F	2,818 92 74 F	-100 -11 F	2,670 79.7	.1 66.5 F	47.2 38.2	F -	
																									-

PROJE TI ES AN RE CRO	CHITECTURE •	<image/> <section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header>
9102 Indian Home Email Phone 21– DATE 02/ COORI SM DRAWN KS	N. Meridic apolis, IN page www. info@Gibro 317.580. CT -112 (07/21 DINATED BY	GibraltarDesign.com altarDesign.com 5777 Fax 317.580.5778 G. JAWHU REGISTERED NO. 10302590
THE CON THIS DOC WERE CR THIS INFI FOR ANY OF GIBR/ INFORMAT PROJECT.	CUMENT ARE TH REATED FOR USE DOMATION SHALL PURPOSE WITH ALTAR DESIGN. T TON AND REFER	S, PLANS, DETAILS, ETC, SHOWN ON E PROPERTY OF GIBRALTAR DESIGN AND E ON THIS SPECIFIC PROJECT. NONE OF L BE USED BY ANY PERSON OR FIRM OUT THE EXPRESS WRITTEN CONSENT THE OWNER MAY RETAIN COPIES FOR RENCE IN CONNECTION ONLY WITH THIS ISSUED FOR
		ADDENDUM NO. 2 ADDENDUM NO. 3
DRAW ME		AL SCHEDULES
REN	OTHY BAL OVATION	
(C) GIBRAL	TAR DESIGN	SHEET <b>M-501</b>

TAG	FIXTURE/EQUIPMENT	FIXTURE/EQUIPMENT	FIXTURE/EQUIPMENT	ACCEPTABLE	FIXTURE VALVE/FAUCET	FIXTURE VALVE/FAUCET	ACCEPTABLE	ACCESSORIES/REMARKS	
NO.	TYPE	DESCRIPTION	MANUFACTURER AND MODEL NO.	MANUF.	TYPE	TYPE	MANUF.	(SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION)	HP KW FLA AMPS MOCP VOLT PH
WC-1	WATER CLOSET	VITREOUS CHINA, WALL MOUNTED	AMERICAN STANDARD #2257.103	NOTE #1	BATTERY SENSOR FLUSH VALVE	SLOAN 'G2 OPTIMA' *8116-1.6	NOTE *3	BEMIS #2155-C SEAT	
WC-2	WATER CLOSET	VITREOUS CHINA, WALL MOUNTED, ADA	AMERICAN STANDARD \$2257.103	NOTE #	BATTERY SENSOR FLUSH VALVE	SLOAN 'G2 OPTIMA' #8111-1,6	NOTE *3	BEMIS #2155-C SEAT	
UR-1	URINAL	BATTERY SENSOR FLUGH VALVE	SLOAN 'G2 OPTIMA' *8111-1,6	NOTE #	BATTERY SENSOR FLUSH VALVE	SLOAN 'G2 OPTIMA' *8111-1,6	NOTE *3	-	
L-1	LAVATORY	VITREOUS CHINA, WALL MOUNTED, 20"XI8", ADA	AMERICAN STANDARD #0355.012	NOTE #	ELECTRONIC BATTERY SENSOR, 4' CENTERS	SLOAN *EBF-187	NOTE #Ø	PROVIDED WITH THERMOSTATIC MIXING VALVE. MCGUIRE "PW-2150-WC 1-1/2" PROWRAP, MCQUIRE "H2167CCLK SUPPLIES	
WC-1				NOTE *2	-	-	-	-	12Ø 1
S-1	SINK	1-COMPARTMENT STAINLESS STEEL SINK, 22"x19-1/2"x4-1/2"	ELKAY "LRADQ-221945	NOTE *3	2 HANDLE, HIGH GOOSENECK	ELKAY *LKD2448BH	NOTE #Ø	ELKAY #35 STRAINER, ELKAY #LK-53 DRAIN ASSEMBLY, MCGUIRE #H2167CCLK SUPPLIES	
S-2	SINK AD-3	2-COMPARTMENT STAINLESS STEEL SINK, 37-1/4'x17'x5-1/2', ADA	ELKAY "DRKAD311755R4	NOTE *3	2 HANDLE, HIGH GOOSENECK	CHICAGO FAUCET CO. "50-317XKABCP	NOTE #Ø	MCGUIRE "B-8912-CSDF P-TRAP, MCGUIRE "H2167CCLK SUPPLIES	
S-3	SINK	2-COMPARTMENT STAINLESS STEEL SINK, 33'X19'X6'	ELKAY "LRADQ-3319	NOTE #	Ø.5 GPM-SINGLE LEVER HANDLE, 4' CENTERS	CHICAGO FAUCET #2200-ABCP-E2605JKCP	NOTE #Ø	MCGUIRE "PW-2150-WC 1-1/2" PROWRAP, MCQUIRE "H2167CCLK SUPPLIES	
<del>9</del> -4	SINK	1-COMPARTMENT STAINLESS STEEL SINK, 22"x19-1/2"x6-1/2"	ELKAY "LRADQ-2219	NOTE *3	2 HANDLE, HIGH GOOSENECK	CHICAGO FAUCET CO. "50-317XKABCP	NOTE *4	MCGUIRE "B-8912-CSDF P-TRAP, MCGUIRE "H2167CCLK SUPPLIES, JOSAM "61030 SOLIDS INTERCEPTOR	
MB-1	MOP BASIN	MOLDED STONE, 30'x30'x6'H	FIAT #98-3030	NOTE *4	WALL MOUNTED SERVICE FAUCET	CHICAGO FAUCET CO. #897	NOTE #Ø	W/ 3/4" HOSE THREAD, VACUUM BREAKER, WALL BRACE	
PB-1	PLUMBERS BOX	FOR CLOTHES WASHER	GUY GRAY "B200TS	-	-	-	-	-	
FD-1	FLOOR DRAIN	CAST IRON BODY, ADJUSTABLE 6"X6" NICKEL BRONZE TOP	WADE #100-G6	NOTE #5	-	-	-	VANDALPROOF SCREWS, PLUGGED TRAP PRIMER	
FS-1	FLOOR SINK	CAST IRON, 8-1/8' DEEP, ACID RESISTING, 12'X12' TOP		NOTE #5				ALUMINUM DOME STRAINER, SECURED HINGED GRATE, SLOPED RIM	
SC-1	SILLCOCK	NON-FREEZE, VACUUM BREAKER, REMOVABLE KEY	WADE *8600	NOTE *6	-	-	-	-	
RD-1	ROOF DRAIN	CAST IRON BODY, GRAVEL STOP, LARGE SUMP	MIFAB *R1200-EU	NOTE #5	-	-	-	-	
FRD-1	OVERFLOW ROOF DRAIN	CAST IRON BODY, GRAVEL STOP, LARGE SUMP	MIFAB *R1200-W	NOTE #5	-	-	-	-	
TW-1	TEMPERED WATER VALVE	TEMPERED WATER VALVE	BRADLEY *559-4000A TMV	NOTE #1	-	-	-	-	
тwн-1	TANKLESS WATER HEATER	193 MBH, 5.6 GPM @ 70 DEGREE RISE (GAS FIRED)	NAVIEN *NPE-240A2	-	-	-	-	ISOLATION KIT, TEMP. RELIEF VALVE, DRAIN VALVE AND CONDENSATE PIPED TO FLOOR DRAIN	2 - 120 1
WH-2	TANKLESS WATER HEATER	199 MBH, 56 GPM @ 70 DEGREE RISE (GAS FIRED)	NAVIEN *NPE-240A2	-	-	-	-	ISOLATION KIT, TEMP. RELIEF VALVE, DRAIN VALVE AND CONDENSATE PIPED TO FLOOR DRAIN	2 - 120 1
WH-3	TANKLESS WATER HEATER	193 MBH, 5.6 GPM @ 70 DEGREE RISE (GAS FIRED)	NAVIEN *NPE-240A2	-	-	-	-	ISOLATION KIT, TEMP. RELIEF VALVE, DRAIN VALVE AND CONDENSATE PIPED TO FLOOR DRAIN	2 - 120 1
DBP-1	DOMESTIC BOOSTER PUMP	180 GPM @ 65 PSI DISCHARGE W/ SUCTION @ 25 PSI	METROPOLITAN #MS-MTIII-5D-PHI-65	NOTE #1	-	-	-	W/ 120 GAL. HYDROPNEUMATIC TANK, 4" SUCTION/ 4" DISCHARGE, (105 GPM @ 92' TDH EA. PUMP) 138' MIN. SHUT-OFF HEAD	(2) 5 480 3
CP-1	RECIRCULATING PUMP	19 GPM @23' HEAD, ALL BRONZE CONSTRUCTION	B4G * PL-55	NOTE *8	-	-	-	W/ STRAP ON AQUASTAT	2/5 4.7 - 120 1

NOTE #10: ZURN, DELTA, T43 BRASS, CHICAGO FAUCET CO.

NOTE #11: AMT, B4G

NOTE #4: MUSTEE, SWAN NOTE #5: ZURN, JOSAM, J.R. SMITH, MIFAB

NOTE #6: JOSAM, ZURN, J.R. SMITH, WOODFORD

NOTE #1: LEONARD, POWERS, LAWLER


NOTE #3: JUST

## **GENERAL NOTES**


- A. WORK SHALL COMPLY WITH LOCAL, MUNICIPAL, AND STATE PLUMBING CODES.
- B. THE SCOPE OF WORK SPECIFIED HEREIN AND IN THE SPECIFICATIONS SHALL BE COORDINATED WITH THE CONSTRUCTION MANAGER - REFER TO THE SCOPE OF WORK FOR EACH TRADE, ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS AND CONSTRUCTION MANAGERS SCOPE SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER FOR CLARIFICATION. THE ARCHITECT/ENGINEER'S DECISION SHALL BE FINAL.
- C. LAYOUT IS DIAGRAMMATIC. INSTALL PIPING AND EQUIPMENT TO MEET ACTUAL FIELD CONDITIONS. REVIEW PROJECT SPECIFICATIONS BEFORE STARTING ANY WORK. SUBMIT SHOP DRAWINGS OF WORK AS PER SPECIFICATIONS.
- D. COORDINATE PHASING OF WORK AND PROVIDE TEMPORARY PIPING AND SERVICES AS REQUIRED FOR THE IMPLEMENTATION OF WORK.
- E. LAYOUT WORK TO AVOID CONFLICTS BETWEEN DUCTWORK, LIGHTING, CEILINGS, PIPING AND BUILDING STRUCTURE.
- F. SCHEDULE WORK TO AVOID DOWNTIME AND INCONVENIENCE TO OWNER.
- G. TRADE COORDINATION
- H. COORDINATE EQUIPMENT ELECTRICAL REQUIREMENTS (VOLTAGES, PHASE, LOAD, ETC.) BEFORE ORDERING ANY EQUIPMENT.
- COORDINATE VENT THROUGH ROOF LOCATIONS WITH OUTDOOR AIR INTAKE LOCATIONS TO MAINTAIN A MINIMUM SEPARATION OF TEN FEET.

$\langle \rangle$	PLUMBING KITCH			<b>ILW</b>		SCHEDU
CONN. NO.	CONNECT TO	COLD WATER	HOT WATER	WASTE	FLOOR DRAINS	REMARKS
2	COOLER COIL	-	-	-	FD-1	-
٦	FREEZER COIL	-	-	-	FD-1	-
14	ISLAND WORK TABLE	-	-	-	FS-1	-
15	HAND SINK	1/2 <b>•</b>	V2"	-	11/2"	-
18	PREP SINK	1/2 °	1/2"	-	FS-1	-
19	GARBAGE DISPOSAL	1/2 <b>•</b>	-	-	2"	-
24	ICE MAKER	V <sub>2</sub> •	-	-	FD-1	WATTS #LF9D
35	COMBI OVERN/STEAMER	(2)1/2"	V2"	-	FS-1	WATTS #9D-BBFP
37	TILT SKILLET	V <sub>2</sub> •	1/2"	-	FT	WATTS #9D-BBFP
38	FLOOR TROUGH	-	-	-	4"	-
45	THREE COMPARTMENT SINK	-	-	-	FS-1	-
47	SPLASH MOUNT FAUCET	3/4 '	3/4"	-	-	-
48	PRE RINGE FAUCET	1/2 °	1/2"	-	-	-
49	GARBAGE DISPOSAL	1/2 °	-	-	2"	-
51	DISH MACHINE	1/2 °	1/2"	-	FS-1	-
52	DIGH MACHINE BLOW DRYER	-	-	-	FS-1	-
63	MOP SINK	3/4 '	3/4"	-	4'	-
٦Ø	DROP-IN HOT/COLD UNIT	-	-	-	FD-1	-
73	DROP-IN COLD WELL	-	-	-	FD-1	-
80	DROP-IN HOT/COLD UNIT	-	-	-	FD-1	-
83	DROP-IN COLD WELL	-	-	-	FD-1	-
୨୭	DROP-IN HOT/COLD UNIT	-	-	-	FD-1	-
92	DROP-IN COLD WELL	-	-	-	FD-1	-
			1			


WASTE LINES, INDIRECT PIPING, ETC. FOR FIXTURES AND KITCHEN EQUIPMENT ITEMS. PROVIDE AND INSTALL ALL VALVES, STOPS, TRAPS, AND PRESSURE REGULATORS NECESSARY TO CONNECT LINES. FOR FURTHER INFORMATION AND DESCRIPTION OF KITCHEN EQUIPMENT BEING SUPPLIED REFER TO ARCHITECTURAL DRAWINGS, KITCHEN EQUIPMENT DRAWINGS, AND ENLARGED KITCHEN AREA DRAWINGS.





D ARCHITECTURE • F PROJECT TIMOT ES AD AND	PORATION
9102 N. Meridia Indianapolis, IN Homepage www.1 Email info@Gibra Phone 317.580.5 PROJECT 21—112 DATE 02/07/21 COORDINATED BY SM DRAWN BY JM CHECKED BY DJ COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS THIS INFORMATION SHALL FOR ANY PURPOSE WITHO OF GIBRALTAR DESIGN. TH	46260 GibraltarDesign.com 5777 Fax 317.580.5778 5777 Fax 317.580.5778 G. JAW G. JAW BE GISTERED NO. 10302590 STATE OF WDIANA STATE OF WDIANA FROPERTY OF GIBRALTAR DESIGN AND ON THIS SPECIFIC PROJECT. NONE OF BE USED BY ANY PERSON OR FIRM DUT THE EXPRESS WRITTEN CONSENT HE OWNER MAY RETAIN COPIES FOR
REVISIONS MARK DATE	ENCE IN CONNECTION ONLY WITH THIS ISSUED FOR ADDENDUM NO. 3
NOTES, SYI ABBREVIAT	L ES ADDITIONS AND





<image/> <section-header><section-header><section-header><section-header><section-header><section-header><section-header></section-header></section-header></section-header></section-header></section-header></section-header></section-header>
9102 N. Meridian St., Ste. 300 Indianapolis, IN 46260
Email info@GibraltarDesign.com Phone 317.580.5777 Fax 317.580.5778
PROJECT 21-112 DATE 02/07/21 COORDINATED BY SM DRAWN BY AG CHECKED BY DJ
DJ COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, PLANS, DETAILS, ETC, SHOWN ON THIS DOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND WERE CREATED FOR USE ON THIS SPECIFIC PROJECT. NONE OF THIS INFORMATION SHALL BE USED BY ANY PERSON OR FIRM FOR ANY PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF GIBRALTAR DESIGN. THE OWNER MAY RETAIN COPIES FOR INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS PROJECT.
REVISIONSMARKDATEISSUED FORAD-102/17/22ADDENDUM NO. 1AD-303/03/22ADDENDUM NO. 3Image: Colspan="2">Image: Colspan="2" Image: C
DRAWING
ELECTRICAL SITE PLAN PROJECT TIMOTHY BALL ES ADDITIONS AND
© GIBRALTAR DESIGN SHEET E-002











## **GENERAL NOTES**

- CIRCUIT ALL NORMAL LIGHTING FIXTURES TO PANEL HP-11 UNLESS OTHERWISE NOTED.
- EMERGENCY SENSING LEADS SHALL BE CONNECTED TO CONSTANT HOT FEEDS FROM NORMAL LIGHTING IN ROOM. THIS FEED SHALL BE TAKEN AHEAD OF ANY EMERGENCY SHUTDOWNS, RELAYS, CONTACTORS OR SWITCHES.
- REFER TO ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATION OF ALL CEILING MOUNTED LIGHT FIXTURES.
- 4. ROUTE CONDUIT AS TIGHT TO THE EXPOSED CEILINGS AND STRUCTURE AS POSSIBLE TO MAXIMIZE CEILING SPACE.
- 5. VERIFY TEACHING SURFACE WITH OWNER'S REPRESENTATIVE IN FIELD PRIOR TO INSTALLATION AND ADJUST SWITCHING TO PROPERLY ILLUMINATE TEACHING SURFACE. CAREFULLY COORDINATE FINAL SWITCHING WITH FINAL FURNITURE PLANS AND TEACHING WALL LOCATIONS.
- 6. CIRCUIT TAGS WITH AN 'X' PREFIX SHOWN WITH A SWITCH LEG SHALL BE A SWITCHED EMERGENCY FIXTURE CONNECTED TO EXISTING EMERGENCY PANEL IXHI. THE FIXTURE SHALL BE PROVIDED WITH A UL924 RATED BYPASS DEVICE TO ALLOW THE FIXTURE TO BE CONTROLLED ALONG WITH THE NORMAL FIXTURES IN THE ROOM. UPON LOSS OF POWER, THE FIXTURE SHALL BE IMMEDIATELY POWERED TO 100% REGARDLESS OF SWITCH POSITION.
- FIXTURES WITH A 'NL' TAG SHALL BE CONNECTED TO THE NIGHT LIGHT CIRCUIT INDICATED IN EXISTING EMERGENCY PANEL IXHI.
- 8. EXIT SIGNS SHALL BE CONNECTED TO CIRCUIT INDICATED IN EXISTING EMERGENCY PANEL 1XHI.
- 9. TYPE PB EMERGENCY FIXTURES IN GYM TO BE PROVIDED WITH EMERGENCY POWER BY TWO (2) MYERS LV-5-X 1100VA LIGHTING INVERTERS AND UL924 BYPASSES.


### SHEET NOTES


 $\bigcirc$ 

- PROVIDE A FULL ACUITY N-LIGHT STAND ALONE SYSTEM TO CONTROL THE GYMNASIUM AND STAGE LIGHTING. PROVIDE OCCUPANCY SENSORS, SWITCHES, ACCESSORIES, DEVICES, CABLING, ETC. FOR A COMPLETE AND PROPER INSTALLATION. LOW YOLTAGE CABLING SHALL BE ROUTED IN CONDUIT IN EXPOSED CEILINGS.
- VERIFY EXACT LOCATION OF FIXTURE WITH ARCHITECT AND PROVIDE CUSTOM WIRE GUARD PROTECTION.
- . TWO (2) GYMNASIUM INVERTERS, PROVIDE TWO (2) MINIMUM 1100VA MYERS LV-5-R-X SERIES INVERTERS OR APPROVED EQUAL. INVERTER SHALL BE LOCATED FOR EASY ACCESS AND PROPER COOLING IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- 4. CONNECT EMERGENCY INTERIOR LIGHTING FIXTURES TO CIRCUIT INDICATED IN PANEL IXHI VIA GYMNASIUM EMERGENCY INVERTERS. MEASURE AND BALANCE LOADS ACROSS INVERTERS PER MANUFACTURER'S INSTRUCTIONS. PROVIDE UL924 BYPASSES DEVICES TO ALLOW THE FIXTURE TO BE CONTROLLED ALONG WITH THE NORMAL LIGHTING IN THE ROOM. UPON LOSS OF POWER, FIXTURE SHALL BE IMMEDIATELY POWERED TO 100% FOR A MINIMUM OF 90 MINUTES, REGARDLESS OF SWITCH POSITION. VERIFY CONDITIONS AND REQUIREMENTS IN FIELD AND WITH LIGHTING CONTROLS MANUFACTURER, COMPLETE AS REQUIRED.

# EXTERIOR LIGHTING NOTES

- NEW EXTERIOR LIGHTING SHALL BE CONNECTED TO EXISTING EXTERIOR LIGHTING 277V, 20A CIRCUITS (FROM EXISTING PANEL 145) YIA NEW TIME CLOCK CONTROL SYSTEM AND INVERTERS AS SPECIFIED.
- CIRCUIT NUMBERS SHOWN ARE NOT ACTUAL, BUT ARE SHOWN TO INDICATE CIRCUITING REQUIREMENTS. VERIFY ACTUAL CIRCUIT ASSIGNMENTS IN FIELD.
- 3. IF EXISTING EXTERIOR LIGHTING CIRCUITRY DOES NOT HAVE SUFFICIENT CAPACITY FOR NEW LIGHTING FIXTURES, NEW 2777, 20A CIRCUITS (FROM EXISTING PANEL 1H5) SHALL BE PROVIDED WITH NEW CIRCUITRY FROM NEW PANEL HP-11, COMPLETE AS REQUIRED.
- 4. EXTERIOR LIGHTING CIRCUITS \*2 AND \*3 SHALL BE CONNECTED TO EXISTING CIRCUITRY (FROM EXISTING PANEL 1H5) VIA NEW TIME CLOCK, PHOTOCELL AND CONTACTORS.
- 5. EXTERIOR LIGHTING CIRCUIT XIT SHALL BE CONNECTED TO NEW 20/AIP CIRCUITRY FROM EXISTING EMERGENCY PANEL IXHI VIA NEW TIME CLOCK, PHOTOCELL, CONTACTORS AND EXTERIOR LIGHTING INVERTER #1.
- CONTRACTOR SHALL MODIFY AND REVISE EXISTING EXTERIOR LIGHTING CIRCUITRY (FROM EXISTING PANEL 1H5) AS REQUIRED TO ACCOMPLISH NEW SWITCHING: AND EMERGENCY CONTROL AS SPECIFIED. INVERTER CIRCUITS SHALL BE PROVIDED WITH INDEPENDENT RACEWAYS AND SHALL NOT SHARE RACEWAYS AND BOXES WITH NORMAL CIRCUTRY, PROVIDE NEW 204/IP CIRCUITS FROM EXISTING EMERGENCY PANEL WHERE EXISTING CAPACITY IS NOT SUFFICENT FOR NEW LOADS.






## **GENERAL NOTES**

- CIRCUIT ALL DEVICES WITH A 'H' PREFIX TO EXISTING PANEL HP-8.
- 2. CIRCUIT ALL DEVICES WITH A 'B' PREFIX TO EXISTING PANEL BCP-1.
- CIRCUIT ALL DEVICES WITH A 'L' PREFIX TO EXISTING PANEL ILI.
- CIRCUIT ALL DEVICES WITH A 'E' PREFIX TO NEW PANEL EM-TECHI.
- 5. CIRCUIT ALL DEVICES TO EXISTING PANEL INDICATED ON CIRCUIT PREFIX UNLESS OTHERWISE NOTED. CIRCUIT NUMBERS ARE ARBITRARY AND ARE ONLY SHOWN TO INDICATE CIRCUITING REQUIREMENTS. NEW CIRCUIT BREAKERS SHALL MATCH THE MAKE, MODEL AND WITHSTAND RATING OF THE EXISTING PANELBOARD. VERIFY EXACT CONDITIONS AND REQUIREMENTS IN FIELD.
- PROVIDE ALL LABOR AND MATERIAL TO PROVIDE THE NECESSARY ROUGH-INS, RACEWAYS AND ELECTRICAL SERVICES FOR ALL OF THE ACCESS CONTROL, SOUND SYSTEMS, TECHNOLOGY SYSTEMS AND EQUIPMENT. SEE TECHNOLOGY DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF DEVICES/EQUIPMENT, MOUNTING HEIGHTS AND ELECTRICAL REQUIREMENTS. COORDINATE AND VERIFY EXACT LOCATIONS OF ALL OF THESE ROUGH-INS AND REQUIREMENTS WITH TECH DYNE, ARCHITECT, OWNER, CONSTRUCTION MANAGER AND DIVISION 27 CONTRACTOR PRIOR TO ROUGHING-IN.
- ALL EXISTING TO REMAIN RECEPTACLES LABELED AS 'EX' SHALL BE REPLACED WITH NEW WIRING DEVICE, FACE PLATE AND COVER PLATE MATCHING NEW DEVICES, COMPLETE AS REQUIRED.
- 8. CUT AND PATCH EXISTING WALLS AS REQUIRED TO INSTALL NEW DEVICES. REPAIR SURFACES TO MATCH EXISTING OR NEW FINISH

### SHEET NOTES


- REFER TO MECHANICAL EQUIPMENT CONNECTION SCHEDULE FOR ADDITIONAL CIRCUITING AND WIRING INFORMATION.
- VERIFY EXACT POWER REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN.
- B. PROVIDE WIRING TO INTERFACE EXISTING ELEVATOR CONTROLLER AND SHUNT TRIP TO NEW FIRE ALARM SYSTEM AND DETECTORS, COMPLETE AS REQUIRED. SEE DETAIL AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.

D ARCHITECTURE • E PROJECT TIMOT ES ADI AND	PORATION
GIBRAL 9102 N. Meridian Indianapolis, IN 4 Homepage www.0 Email info@Gibral Phone 317.580.5 PROJECT 21–112 DATE 02/07/21 COORDINATED BY SM DRAWN BY AG CHECKED BY DJ COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, THIS INFORMATION SHALL FOR ANY PURPOSE WITHO OF GIBRALTAR DESIGN. TH	46260 GibraltarDesign.com
MARK       DATE         AD-3       03/03/22         AD-3       03/03/22         AD-3	OR POWER



SCALE: 1/8" = 1'-Ø"

UNIT "A" ELECTRICAL SECOND FLOOR POWER PLAN



### **GENERAL NOTES**


- CIRCUIT ALL DEVICES WITH A 'H' PREFIX TO EXISTING PANEL HP-9.
- 2. CIRCUIT ALL DEVICES WITH A 'B' PREFIX TO EXISTING PANEL BCP-2.
- 3. CIRCUIT ALL DEVICES WITH A 'L' PREFIX TO EXISTING
- 4. CIRCUIT ALL DEVICES WITH A 'E' PREFIX TO NEW PANEL EM-TECH2.

PANEL 2L1.


- 5. CIRCUIT ALL DEVICES TO EXISTING PANEL INDICATED ON CIRCUIT PREFIX UNLESS OTHERWISE NOTED. CIRCUIT NUMBERS ARE ARBITRARY AND ARE ONLY SHOWN TO INDICATE CIRCUITING REQUIREMENTS. NEW CIRCUIT BREAKERS SHALL MATCH THE MAKE, MODEL AND WITHSTAND RATING OF THE EXISTING PANELBOARD. VERIFY EXACT CONDITIONS AND REQUIREMENTS IN FIELD.
- 6. PROVIDE ALL LABOR AND MATERIAL TO PROVIDE THE NECESSARY ROUGH-INS, RACEWAYS AND ELECTRICAL SERVICES FOR ALL OF THE ACCESS CONTROL, SOUND SYSTEMS, TECHNOLOGY SYSTEMS AND EQUIPMENT. SEE TECHNOLOGY DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF DEVICES/EQUIPMENT, MOUNTING HEIGHTS AND ELECTRICAL REQUIREMENTS. COORDINATE AND VERIFY EXACT LOCATIONS OF ALL OF THESE ROUGH-INS AND REQUIREMENTS WITH TECH DYNE, ARCHITECT, OWNER, CONSTRUCTION MANAGER AND DIVISION 27 CONTRACTOR PRIOR TO ROUGHING-IN.
- ALL EXISTING TO REMAIN RECEPTACLES LABELED AS 'EX' SHALL BE REPLACED WITH NEW WIRING DEVICE, FACE PLATE AND COVER PLATE MATCHING NEW DEVICES, COMPLETE AS REQUIRED.
- 8. CUT AND PATCH EXISTING WALLS AS REQUIRED TO INSTALL NEW DEVICES. REPAIR SURFACES TO MATCH EXISTING OR NEW FINISH

# SHEET NOTES


- REFER TO MECHANICAL EQUIPMENT CONNECTION SCHEDULE FOR ADDITIONAL CIRCUITING AND WIRING INFORMATION.
- VERIFY EXACT POWER REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN.







D ARCHITECTURE • E PROJECT TIMOT ES ADI AND	PORATION
GIBRAL 9102 N. Meridian Indianapolis, IN 4 Homepage www.0 Email info@Gibra Phone 317.580.5 PROJECT 21–112 DATE 02/07/21 COORDINATED BY SM DRAWN BY AG CHECKED BY DJ COPYRIGHT NOTICE: THE CONCEPTS, DESIGNS, THIS INFORMATION SHALL FOR ANY PURPOSE WITHO OF GIBRALTAR DESIGN. TH INFORMATION AND REFERE PROJECT. REVISIONS	46260 GibraltarDesign.com ItarDesign.com 5777 Fax 317.580.5778
UNIT "B" ME ELECTRICA PROJECT	L POWER PLANS



## **GENERAL NOTES**


- CIRCUIT ALL DEVICES TO PANEL INDICATED BY PANEL DIVISION LINES UNLESS OTHERWISE NOTED.
- 2. CIRCUIT ALL DEVICES WITH AN 'E' PREFIX TO PANEL EM-TECH3 UNLESS OTHERWISE NOTED.
- 3. CIRCUIT ALL DEVICES WITH AN 'H' PREFIX TO PANEL HP-11 UNLESS OTHERWISE NOTED.
- PROVIDE ALL LABOR AND MATERIAL TO PROVIDE THE NECESSARY ROUGH-INS, RACEWAYS AND ELECTRICAL SERVICES FOR ALL OF THE ACCESS CONTROL, SOUND SYSTEMS, TECHNOLOGY SYSTEMS AND EQUIPMENT. SEE TECHNOLOGY DRAWINGS AND SPECIFICATIONS FOR LOCATIONS OF DEVICES/EQUIPMENT, MOUNTING HEIGHTS AND ELECTRICAL REQUIREMENTS. COORDINATE AND VERIFY EXACT LOCATIONS OF ALL OF THESE ROUGH-INS AND REQUIREMENTS WITH TECH DYNE, ARCHITECT, OWNER, CONSTRUCTION MANAGER AND DIVISION 27 CONTRACTOR PRIOR TO ROUGHING-IN.


# SHEET NOTES

LOW VOLTAGE TO BE SEPARATED.


- REFER TO MECHANICAL EQUIPMENT CONNECTION SCHEDULE FOR ADDITIONAL CIRCUITING AND WIRING INFORMATION.
- VERIFY EXACT POWER REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN. . PROVIDE FLEXIBLE RETRACTING CABLE CONNECTION FROM FRONT OF BLEACHER TO JUNCTION BOXES IN WALL. PROVIDE MINIMUM 2" CONDUIT CONNECTION FOR LOW

VOLTAGE BOXES. PROVIDE 3/4°C. FOR POWER. POWER AND






PROPERLY TERMINATE, CAP AND SPIKE WITH 18" METAL SPIKE W/ 1.5" DIAMETER FOR FUTURE EXTENSION.



	INTERIC	OR LIGHTING LUMINA		CHED		
SYMBOL	DESCRIPTION	MANUFACTURER SERIES DR CATALOG NUMBER	VOLTAGE/ BALLAST	LAMPS/CRUSS SECTION		REMARKS
		LITHONIA *2BLT4-40L-ADP-EZI-LP840 COLUMBIA *LCAT24 SERIES METALUX *24CZ2 SERIES	120/277 VOLT Ø-107 DIM	LED 4000K MAX 32W MIN 4000LM	RECESSED LAY-IN	-
	2' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #2BLT4-48L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 38W MIN 4800LM	RECESSED LAY-IN	-
	2' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #2BLT4-60L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 48W MIN 6000LM	RECESSED LAY-IN	-
	2' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #2BLT4-60L-ADP-EZI-LP850 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 5000K MAX 48W MIN 6000LM	RECESSED LAY-IN	-
	2' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #2BLT4-72L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 61W MIN 7200LM	RECESSED LAY-IN	-
	FIXTURE	LITHONIA #2BLT2-40L-ADP-EZI-LP840 COLUMBIA #LCAT22 SERIES METALUX #22CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 32W MIN 4000LM	RECESSED LAY-IN	-
	FIXTURE	LITHONIA #2BLT2-48L-ADP-EZI-LP840 COLUMBIA #LCAT22 SERIES METALUX #22CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 48W MIN 4800LM	RECESSED LAY-IN	-
o	INVERTED LENS AND TRIPLE	LITHONIA #2GTL4-88L-RW-A19INY-MYOLT-EZI- LP840-ABC COLUMBIA #LJT24 SERIES METALUX #GR LED SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 65W MIN 8800 LM	RECESSED LAY-IN	-INVERTED LENS AND TRIPLE GASKETING
0	I' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #BLT4-40L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-107 DIM	LED 4000K MAX 33W MIN 4000LM	RECESSED	- AD-2
0	I' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #BLT4-48L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-107 DIM	LED 4000K MAX 40W MIN 4800LM	RECESSED	- AD-2
	I' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #BLT4-60L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT 0-107 DIM	LED 4000K MAX 50W <b>YH 6000L</b> X	RECESSED	- AD-2 AD-2
0	I' X 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #BLT4-30L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT Ø-10V DIM	LED 4000K MAX 16W MIN 3000LM	RECESSED GYPSUM	-PROVIDE WITH DRYWALL GRID ADAPTER (*DGA14)
0	I' × 4' LED DIRECT/INDIRECT FIXTURE	LITHONIA #BLT4-40L-ADP-EZI-LP840 COLUMBIA #LCAT24 SERIES METALUX #24CZ2 SERIES	120/277 VOLT 0-107 DIM	LED 4000K MAX 33W MIN 4000LM	RECESSED GYPSUM	-PROVIDE WITH DRYWALL GRID ADAPTER (*DGA14)
~~~~		LITHONIA #LDNG-40-10-LOG-AR-LGG-MVOLT -EZI0-XX		LED	RECESSED	
0		PRESCOLITE "LTR SERIES PORTFOLIO "LDGB SERIES	0-107 DIM	4000K MAX 11W MIN 1000LM	LAY-IN/ GY <b>psum</b>	
0	SEMI-SPECULAR ALZAK REFLECTOR, IRIDESCENT FREE	LITHONIA *LDNG-40-15-LOG-AR-LSS-MVOLT -EZI0-XX PRESCOLITE *LTR SERIES PORTFOLIO *LDGB SERIES	120/277 VOLT 0-107 DIM	LED 4000K MAX 18W MIN 1500LM	RECESSED LAY-IN/ GYPSUM	-VERIFY TRIM FINISH WITH ARCHITECT
⊨		LITHONIA *CLX-L48-7000LM-SEF-FDL-MVOLT -GZI0-40K-80CRI-XX-XX METALUX *SNLED SERIES COLUMBIA *MPS SERIES	120/277 VOLT Ø-107 DIM	LED 4000K MAX 49W MIN 7000LM	'Y' CHAIN Suspend	-COORD LOCATIONS WITH DUCTWORK & PIPING
0	CABLE	LITHONIA #IBG-24L-SEF-AFL-GND-MVOLT-GZIØ- 40K-80CRI-WGX-XX-XX COLUMBIA #PEL4 SERIES METALUX *OHB SERIES	120/277 VOLT 0-107 DIM	LED 4000K MAX 192W 24,000LM	CABLE MTD 6' ABOVE BOTTOM OF STRUCTURE	-PROVIDE WIREGUARD AND SAFETY CABLE
0	SUSPENDED LED CYLINDER PENDANT	VISA *CPI542-L40-H-MVOLT-XX-XX OR APPROVED EQUAL	120/277 VOLT 0-10V DIM	LED 4000K MAX 16W MIN 1700LM	SUSPENDED VERIFY W/ ARCHITECT	-VERIFY FINISH WITH ARCHITECT
	PAR30 DIMMABLE HEAD, TWO	CON-TECH *CTL5030-B-FA-30-BD30 PROVIDE WITH NTEK-X-B TRACK JUNO *TEK SERIES QR-APRROVED FOUL		0NE (1) LED 15W EQUIV PAR 30 PER	36' STEM MOUNTED TO UNISTRUT	-PROVIDE ALL MOUNTING ACCESSORIES -VERIFY FINISH WITH ARCHITECT
<ul><li>⊗ </li></ul>		DUAL-LITE "SE-S-R-X LITHONIA "LE-S-X-I-R-X SURE-LITES *CX SERIES	RERINVOLI	MAX 3W	WALL	-YEBRY EINGHAUITH ARCHITECT -PROVIDE WITH ARROWS AS REQUIRED
•		DUAL LITE SE DR LITHONIA "LE-S-X-2-R-X SURE-LITES "CX SERIES AD-2	1207211 VOLT	MAX 3W	WALL	-VERIFY FINISH WITH ARCHITECT -PROVIDE WITH ARROWS AS REQUIRED
	FIXTURE ON EMERGENCY CIRCUIT WITH 90 MINUTE, 1400 LUMEN OUTPUT BATTERY UNIT OR INVERTER	BODINE FACTORY INSTALLED DRIVER OR MYERS LV SERIES INVERTER	12Ø/277 VOLT	-	IN FIXTURE/ REMOTE	-PROVIDE TEST SWITCH AND CHARGING INDICATOR
	CONSTANT HOT, UNSWITCHED NIGHT LIGHT FIXTURE					

<image/> <section-header><section-header><section-header><text><text><text><text><text><text><text><text></text></text></text></text></text></text></text></text></section-header></section-header></section-header>
GIBRALTAR DESIGN         9102 N. Meridian St., Ste. 300         Indianapolis, IN 46260         Homepage www.GibraltarDesign.com         Email info@GibraltarDesign.com         Phone 317.580.5777 Fax 317.580.5778         PROJECT         21-112         DATE         02/07/21         COORDINATED BY         SM         DRAWN BY         AG         CHECKED BY         DJ         COPYRIGHT NOTICE:         THE SOCUMENT ARE THE PROPERTY OF GIBRALTAR DESIGN AND         WERE CREATED FOR USE ON THIS SPECIFIC PROLOCT. NONE OF         FOR ANY DEPROSE WITHOUT THE EXPRESS WRITEN CONSENT         MARK       DATE         INFORMATION AND REFERENCE IN CONNECTION ONLY WITH THIS         PROJECT.       ISSUED FOR         AD-1       02/17/22         ADDENDUM NO. 1       AD-2         AD-3       03/03/22         ADDENDUM NO. 3       Image: Comparison of the co
Image: Shear and the second secon




						FCL			F/		MEN			CTION SC		ייים	F		
			Ι						╺╴┖╾╲				1				• <b>6</b>		
	TAG	DESCRIPTION			LOAD	1		MOCP	VOLT	PHASE	PANEL	CKT. NO.	FUSED Switch	FEEDER		START	ER BY:	LOCATION	REMARKS
ŀ	444.0		WATTS	ΗP	MCA	FLA	AMPS						C/B	CABLE	C	MC.	EC.		
ŀ	AH-3		13677	-	16	14	-	-	480	3	EX. 2H2	13-15-17	25A/3P	4 #10 \$ 1 #10 GRD.	3/4'	×	-	•	-
⊦	АН-3	AIR HANDLING UNIT	9145	6	-	-	-	-	480	3	EX. 2H2	14-16-18	20A/3P	4 #12 \$ 1 #12 GRD.	3/4'	×	-	•	-
	B-1	BOILER	960	-	-	8	-	15	12Ø		EX. IL2	61	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	•	-
	B-2	BOILER	960	-	-	8	-	15	12Ø	1	EX. IL2	21	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	B-3	BOILER	960	-	-	8	-	15	12Ø	1	EX. IL2	23	154/19	2 #12 \$ 1 #12 GRD.	<sup>3</sup> ⁄4"				
	RT-I	ROOFTOP UNIT	64688	-	78	-	-	125	480	3	MDP3	ONE-LINE	125A/3P	4 #1/0 \$ 1 #6 GRD.	2"	×	-	-	-
	RT-2A	ROOFTOP UNIT	67262	-	81	-	-	125	480	3	MDP3	ONE-LINE	125A/3P	4 #1/Ø \$ 1 *6 GRD.	2"	×	-	-	-
	RT-2B	ROOFTOP UNIT	67262	-	81	-	-	125	480	3	MDP3	ONE-LINE	125A/3P	4 #1/Ø \$ 1 *6 GRD.	2"	×	-	-	-
	VUV-1		72Ø	-	-	-	3	-	277		VARIES	VARIES	2ØA/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
-	VUV-2	UNIT VENTILATOR	1136	-	-	-	4	-	277	1	VARIES	VARIES	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
╞	VUV-3	UNIT VENTILATOR	1524	-	-	-	6	-	277	1	VARIES	VARIES	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	VUY-4	UNIT VENTILATOR	1524	-	-	-	6	-	277	1	VARIES	VARIES	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	FC-1	FAN COIL UNIT	466	-	4	-	-	15	12Ø	1	VARIES	VARIES	154/19	2 #12 \$ 1 #12 GRD.	<sup>3</sup> ⁄4"	×	-	-	-
	FC-2	FAN COIL UNIT	728	<u> </u>	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	, , ,			120			VARIES		2 #12 4 1 #12 GRD.	3/4'	$\stackrel{\times}{\frown}$	~~~~	<u> </u>	
ζ	FC-3		583	-	3	-	-	15	208		BCP-2	61-63	15A/2P	3 #12 \$ 1 #12 GRD.	<sup>3</sup> 4'	×	-	-	-
Į	CH-1	CABINET HEATER	330	-	3			15	120		VARIES	VARIES	20A/1P	2 #12 & 1 #12 GRD.	3/4	×		<u> </u>	
-	CH-2		336	-	3	-	-	15	12Ø	1	VARIES	VARIES	2ØA/1P	2 #12 \$ 1 #12 GRD.	<sup>3</sup> ⁄4"	×	-	-	-
-	CH-3		336	-	3	-	-	15	12Ø	1	VARIES	VARIES	2ØA/1P	2 #12 \$ 1 #12 GRD.	<sup>3</sup> ⁄4"	×	-	-	-
	CH-4	CABINET HEATER	346	-	3	-	-	15	12Ø	1	VARIES	VARIES	2ØA/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	CH-5	CABINET HEATER	336	-	3	-	-	15	12Ø	1	VARIES	VARIES	2ØA/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	СН-6	CABINET HEATER	348	-	3	-	-	15	12Ø	1	VARIES	VARIES	20A/1P	2 #12 & 1 #12 GRD.	3/4"	×	-	-	-
	TEF-1	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	NEW 1L12	44	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	ŤEF-2	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	NEW 1L12	46	15A/1P	2 #12 & 1 #12 GRD.	3/4"	×	-	-	-
	TEF-3	ROOF TOILET EXHAUST FAN	528	1/6	-	-	-	-	12Ø	1	NEW 1L12	48	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	TEF-4	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	NEW ILI3	22	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	TEF-5	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	NEW ILI3	24	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	TEF-6	ROOF TOILET EXHAUST FAN	1920	1	-	-	-	-	12Ø	1	EX. ILT	13	30A/1P	2 #10 \$ 1 #10 GRD.	3/4"	×	-	-	-
	TEF-7	ROOF TOILET EXHAUST FAN	864	1/3	-	-	-	-	12Ø	1	EX. ILT	15	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	TEF-8	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	EX. ILT	Г	15A/1P	2 #12 & 1 #12 GRD.	3/4"	×	-	-	-
	TEF-9	INLINE TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	EX. IL6	39	15A/1P	2 #12 & 1 #12 GRD.	3/4"	×	-	-	-
	TEF-1Ø	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	EX. IL4	37	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	TEF-11	ROOF TOILET EXHAUST FAN	528	1/8	-	-	-	-	12Ø	1	EX. IL4	41	15A/1P	2 #12 \$ 1 #12 GRD.	3⁄4"	×	-	-	-
	TEF-12	CEILING TOILET EXHAUST FAN	2825	2	-	-	-	-	2Ø8	1	EX. 2L1	26-28	25A/2P	3 #10 \$ 1 #10 GRD.	3/4"	×	-	-	-
_	GEF-1	CEILING GENERAL EXHAUST FAN	696	1/4	-	-	-	-	12Ø	1	NEW ILI3	26	15A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
	GEF-2	ROOF GENERAL EXHAUST FAN	528	1/8	<u>·</u>		, 	, 	120		EX. IL4	39	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	$\stackrel{\times}{\frown}$	~~~~	<u> </u>	·
Z	GEF-3	CEILING GENERAL EXHAUST FAN	1176	1/2	-	-	-	-	12Ø	1	EX. BCP-1		20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	-
Ī	AC-1/CU-1	AC/CONDENSING UNIT	2288					28	208		VARIES	VARIES	3ØA/2P	3 #10 \$ 1 #10 GRD.	34	×			
ł	4C-2/CU-2	AC/CONDENSING UNIT	52 <i>00</i>	-	25	-	-	3Ø	2Ø8	1	EM-TECH	1@-12	3ØA/2P	3 #10 \$ 1 #10 GRD.	3/4"	×	-	-	-
-	UH-1	UNIT HEATER	199	1/100	-	-	-	-	12Ø	1	VARIES	VARIES	20A/IP	2 #12 & 1 #12 GRD.	3⁄4"	×	-	-	-
	UH-2	UNIT HEATER	199	1/50	-		- ~~~		120				204/11P	2 #12 \$ 1 #12 GRD.	<sup>3</sup> /4'	$\overset{\times}{\frown}$		- ~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
ζ	H-1	EXHAUST HOOD	372		-	-	3	-	12Ø	1	EX. ILI	48	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	×	-	-	WALL SWITCH
$\langle  $	H-2		372	$\overline{}$	-		3		120		EX. ILI	27			<sup>3</sup> ⁄4'	$\sim$	-		
	TWH-1	TANKLESS WATER HEATER	24Ø	-	-	-	2	-	12Ø	1	EX. 1L2	25	20A/IP	2 #12 \$ 1 #12 GRD.	3/4"	-	-	-	-
	TWH-2	TANKLESS WATER HEATER	24Ø	-	-	-	2	-	12Ø	1	EX. IL2	25	20A/IP	2 #12 \$ 1 #12 GRD.	3⁄4 '	-	-	-	-
	TWH-3	TANKLESS WATER HEATER	24Ø	-	-	-	2	-	12Ø	1	EX. IL2	27	20A/IP	2 #12 \$ 1 #12 GRD.	3⁄4'	-	-	-	- 
	DBP-1	DOMESTIC BOOSTER PUMP	6318	(2)5	-	-	-	-	480	3	EX. 1H4	VARIES	15A/3P	4 #12 \$ 1 #12 GRD.	3⁄4'	-	-	-	PROVIDE TWO (2) CONNECTIONS
	RCP-1	RECIRCULATING PUMP	564	2/5	-	-	5	-	12Ø	1	EX. 1L2	27	20A/1P	2 #12 \$ 1 #12 GRD.	3/4"	-	-	-	-
L																			

					P	UMP	EQU	UIPME		CONNEC		N 3	<b>SCH</b>	EDULE	
tag:	DESCRIPTION	LOAD	Н₽	MOCP	VOLT	PHASE	PANEL	CKT. NO.	FUSED Switch	FEEDER		START	ED BY:	LOCATION	REMARKS
		WATTS							C/B	CABLE	с	MC.	EC.		
BP-1	BOILER PUMP	3990	3		48Ø	3	EX. IH6	1-3-5	15A/3P	4 #12 \$ 1 #12 GRD.	3/4"	-	-	•	ACROSS THE LINE STARTER
BP-2	BOILER PUMP	3990	3	-	480	3	EX. IH6	7-9-11	15A/3P	4 #12 \$ 1 #12 GRD.	3/4"	-	-	-	ACROSS THE LINE STARTER
BP-3	BOILER PUMP	3990	3	-	480	3	EX. 1H6	13-15-17	15A/3P	4 #12 \$ 1 #12 GRD.	3⁄4"	-	-	-	ACROSS THE LINE STARTER
CP-1	CHILLER PUMP	9145	1 1/2	-	480	3	EX. 1H6	19-21-23	20A/3P	4 #12 \$ 1 #12 GRD.	3⁄4"	-	-	-	ACROSS THE LINE STARTER
HWP-1	HOT WATER PUMP	17460	15	-	480	3	EX. 1H4	32-34-36	25A/3P	4 #10 \$ 1 #10 GRD.	3⁄4"	-	-	-	VARIABLE FREQUENCY DRIVE
H₩P-2	HOT WATER PUMP	17460	15	-	480	3	EX. 1H4	38-40-42	25A/3P	4 #10 \$ 1 #10 GRD.	3⁄4"	-	-	-	VARIABLE FREQUENCY DRIVE
CWP-1	CHILLED WATER PUMP	22447	2Ø	-	480	3	EX. 1H6	2-4-6	35A/3P	4 #8 \$ 1 #10 GRD.	3⁄4"	-	-	-	VARIABLE FREQUENCY DRIVE
CWP-2	CHILLED WATER PUMP	22447	2Ø	-	480	3	EX. IH6	8-10-12	35A/3P	4 *8 \$ 1 *10 GRD.	3⁄4"	-	-	-	VARIABLE FREQUENCY DRIVE

### DIMD FOURDMENT CONNECTION SCHEDULE

RENOV	
9102 N. Meridia Indianapolis, IN Homepage www. Email info@Gibro Phone 317.580.3 PROJECT 21-112	46260 GibraltarDesign.com 5777 Fax 317.580.5778
DATE 02/07/21 COORDINATED BY SM DRAWN BY AG	ISIII 10302590 ITE
THIS DOCUMENT ARE THI WERE CREATED FOR USE THIS INFORMATION SHALL FOR ANY PURPOSE WITH OF GIBRALTAR DESIGN. T	, PLANS, DETAILS, ETC, SHOWN ON E PROPERTY OF GIBRALTAR DESIGN AND ON THIS SPECIFIC PROJECT. NONE OF BE USED BY ANY PERSON OR FIRM OUT THE EXPRESS WRITTEN CONSENT HE OWNER MAY RETAIN COPIES FOR ENCE IN CONNECTION ONLY WITH THIS
REVISIONS MARK DATE AD-3 03/03/22	ISSUED FOR ADDENDUM NO. 3
DRAWING ELECTRICA	L SCHEDULES
RENOVATION	
© GIBRALTAR DESIGN	SHEET E-601



		EX	ΡΑ	NE	EL 1L1								EX	(. F	PA	NE	Ľ	BC	CP-	-1	
TOTAL KW: 59,2	ENCLO	OSURE: NEMA-1	PHA	ASE:	3¢	VOLT.	AGE:	120 / 208	TOTAL KW: 34,1		ENCL	OSURE:	NEMA	4-1	PHA	θE: 3	Þ			VOLTAGE:	120 / 208
MOUNTING: SURFACE	BUSSI	NG: COPPER	FAU	LT CU	RRENT RATING: EX	ISTING		MLO(AMPS): 200	MOUNTING: SURFACE		BUSS	ING: CC	PPER		FAUL		RENT	RATIN	NG: EX	ISTING AIC	MLO(AMPS):
FEEDER: 4 *3/0 4 1 *6					N: CUST. A-120				FEEDER: 4 *3/0 4 1 *6	GRD.								T. A-12			
	C/B	LOAD			LOAD		C/B				2/B		LOAD	1				LOAD		C/B	
LOAD DESCRIPTION	TRIP POLE		C+ CC1	T. NO.			POLE	LOAD DESCRIPTION	LOAD DESCRIPTION		POLE	Aø	Bø		CCT.	NOL	 		C¢		
A121 - REC/CH-5	20 1	536		2		20	1	EXISTING SPARE	Aleia - QUAD/TY	20	1	900		•••	1		300			20 1	A124 - DESK/TV
A126 - BOTTLE FILLERS	20 1	1152	3	4	1136	20	1	A116/119/120/122-REC/CH-5	Aløia - Receps	20	1		600		3	4				20 1	EXISTING SPAR
A124 - RECEPS	20 1		000 5	-	1000		1	Al23 - RECEPS		20	1				5	6				20 1	EXISTING SPAR
A128-RECEPS+EXTBLDG		600	7 <u>7</u>		800	20	1	A108 - RECEPS	AI23-RECEPS ABY CTR	20	1	800			7	-	100			20 1	A124 - RECEPS
A129 - RECEPS	20 1	1000	9		1752	20		AIO9/110-REC/BOT. FILL.	A123 - DESK/TY	20		000	300		9	10		600		20 1	Alø3 - RECEPS
AI30 - RECEPS	20 1		00 11	-	800	20	1	Allo - RECEPS		20			500			12			600	20 1	Alø3 - RECEPS
Al36 - RECEPS	20 1	600		14		20	1			20	1						00	)	000	20 1	A103 - DESK/T
AI36 - RECEPS	20 1	400		16	800	20		A146/147/148/150 - REC	AIOS-RECEPS ABY CTR				400			16		400	-	20 1	AI28 - RECEPS
A138/139/140/141 - REC			00 17		400			A149 - RECEPS	AIDS - DESK/TY				400	300				400	300		AI28 - RECEPS
	20 1	200			400	20				20		600		500		18	00	!	500	20 1	
AI36 - RECEPS	20 1		21	2Ø 22	1200	20		EXISTING SPARE	AIØT - RECEPS A	20		600	1.00			20 6		600		20 1	Alø4 - RECEPS
A144 - RANGE	40	3328				20		A142 - RECEPS	AIOT - RECEPS B	20			600			22		600	-	20 1	AIØ4 - RECEPS
	2		328 23		800	20		A142 - ABV. CTR. REC		2Ø		<b> </b>		300					300	20 1	AIØ4 - DESK/T
					3328	40	-	A151 - RANGE		20		<b> </b>			25			1==		20 1	EXISTING SPARE
		372		)8	3328		2		A109 - DESK/TV	20			300		27			400		20 1	AI29 - RECEPS
EXISTING SPARE					1000			AI51 - FRIDGE A	Aløg - RECEPS	2Ø		<b> </b>		800	29			'	300	20 1	AI29 - DESK/TV
A144 - MICROWAVE		1600			1600	20		AI51 - MICROWAVE	EXISTING SPARE	20		1	-			32 9				20 1	AI30 - DESK/TV
A144 - ABY. CTR.	20 1	600		34	1200	20	1		EXISTING SPARE	20	1	<b>I</b>			33			400		20 1	A130 - RECEPS
EXISTING SPARE	20 1			36	1000		1	AI51 - FRIDGE B	AIIT-RECEPS ABY CTR	20	1		400		35			!		20 1	EXISTING SPAR
EXISTING SPARE	20 1		37		1200	2Ø	1	A151 - VENDING MACH.	AIIT - DESK/TY	2Ø	1	900				38 6		I		20 1	A105 - RECEPS
EXISTING SPARE	2Ø 1			40	1000	20	1	A11@/112/113/114/15@-REC	Existing spare	20	1				39			600		20 1	A105 - RECEPS
EXISTING SPARE	20 1		41		400	2Ø	1	Allo/115 - RECEPS	EXISTING SPARE	2Ø	1				41	<u>≁</u> 2	$\frown$	$\sim$	-300/	28	
Existing spare	20 1				400	2Ø	1	A151 - TV	A149 - LAMINATOR	2Ø	1	1200				44		I		20 1	GEF-3
A132/144 - RECEPS	20 1	600	45	-				AVA-RESERS	A149 - DIE CUT MACHINE		1		1200		45		$\sim$	$\sim$		non	
A122 BOTTLE FILLERS	20 1			48	372	2Ø	1	H-1	A149 - BINDING MACHINE		1			200				!		20 1	EXISTING SPAR
A125 EXT. DOOR OPER.	20 1	1200							A149 - TABLE QUAD	2Ø	1	400			49			!		20 1	EXISTING SPAR
A125 INT. DOOR OPER.	20 1	1200		52	600	2Ø	1	A106 - RECEPS	A149 - PRINTER	2Ø			1200		51			I		20 1	EXISTING SPARE
A143 - KILN	60		992 53		872	2Ø	1	A100/102 - REC/CH-5			2			1200				!		20 1	EXISTING SPAR
	2	4992		56		2Ø	1	A125 INT. DOOR OPER.	EXISTING SPARE	2Ø	1				55					20 1	EXISTING SPAR
EXISTING SPACE				58	1200	2Ø	1	A125 EXT. DOOR OPER.	AI44 - DESK/TV	2Ø	1		300		57			300		20 1	A136 - DESK/TV
EXISTING SPACE			59	60	200	2Ø	1	A125 EXT. BLDG. REC	A145 - QUAD/TV	2Ø	1			300	59	60		I		20 1	EXISTING SPAR
	-	10328 8652 12	Ø72		8528 12816 6844				A145 - RECEPS	2Ø	1	800			61			I		20 1	EXISTING SPARE
				-			Д	AD-3	AI42 - DESK/TY	2Ø	1		300		63	64		!		20 1	EXISTING SPARE
		-						21,468	EXISTING SPARE	2Ø	1				65			!		20 1	EXISTING SPARE
NOTE: REFER TO GENER								18,916	EXISTING SPARE	2Ø	1				67			!		20 1	EXISTING SPARE
FOR ADDITIONAL INFORM	1ATION					Ť	IOTAL:	59,240	A147 - PRINTER	2Ø	1		1200		69			I		20 1	EXISTING SPARE
									A147 - POSTER PRINTER		1			1200				'		20 1	EXISTING SPARE
									EXISTING SPARE	2Ø	1				73			I		20 1	EXISTING SPARE
r									EXISTING SPARE	20	1				75			!		20 1	EXISTING SPARE
		EV							EXISTING SPACE						דד			'		20 1	EXISTING SPAR
		EX	۲A	NE	EL 2L1				EXISTING SPACE						79			I		20 1	EXISTING SPARE
									EXISTING SPACE	<b>I</b>		<b>I</b>			81			!		┨────┤────	EXISTING SPACE
TOTAL KW: 16.1		OSURE: NEMA-1		49E:		VOLT.		120 / 208	EXISTING SPACE	[		<b> </b>			83			!		┨─────	EXISTING SPACE
MOUNTING: SURFACE		NG: COPPER				ISTING	AIC	MLO(AMPS): 100				5600	8800	6100		Ŀ	476   3	3900	42 <i>00</i>		
FEEDER: 4 *2 4 1 *8 G			LOC	CATIO	N: CUST. A-319																= 11,076
	C/B	LOAD			LOAD		C/B	] 7				n –									= 12,700
LOAD DESCRIPTION	TRIP POLE		C\$ CC1			TRIP	POLE		NOTE: REFER TO GENER FOR ADDITIONAL INFORM			1									= 10,300 = 34,076
A317 - BOTTLE FILLERS	20 1	1152	1		536	20	1	A321 - REC/CH-1	FOR ADDITIONAL INFOR			1								IUIAL	- J7,010
A317/319/320-REC/CH-1	20 1	936	3		600	20	1	A321 - RECEPS													
A322 - RECEPS	20 1		00 5		1200	20		A311 - PRINTER													
A325 - TV/RECEPS	2Ø 1	1200	T		1200		2														
A326 - RECEPS	20 1	400	9		800	2Ø	1	A307 - RECEPS						/ =				D/		9	
EXISTING LOAD	20 1		11		800	2Ø	1	A313 - RECEPS					C/	(. F	<b>-</b> A			D	~ <b>~</b> ~	· <b>∠</b>	
EXISTING LOAD	20 1		13		800	2Ø	1	A314 - RECEPS												·	
EXISTING LOAD	2Ø 1		15	16		20	1	EXISTING LOAD	TOTAL KW: 21,0		ENCL	OSURE:	: NEM4		-	3E: 3				VOLTAGE:	120 / 208
EXISTING LOAD	2Ø 1		17		1200	20	1	A309/310/311/312/316-REC	MOUNTING: SURFACE		BUSS	ING: CC	OPPER		FAUL		RENT	RATIN	NG: EX	ISTING AIC	MLO(AMPS): 2
EXISTING LOAD	2Ø 1			2Ø		2Ø	1	EXISTING LOAD	FEEDER: 4 *3/0 \$ 1 *6	GRD.	- 2'C.				LOC	4TION	CUST	t. A-31	19		
EXISTING LOAD	2Ø 1		21	22	800	2Ø	1	A300/301/302 - RECEPS			C/B		LOAD							C/B	
EXISTING LOAD	20 1			24		2Ø	1	ROOF RECEPS	LOAD DESCRIPTION	TRIP	POLE	Дф			CCT.	NO.				TRIP POL	E LOAD DESC
EXISTING LOAD	20 1		25	26		25		TEF-12	EXISTING SPARE	20	1				1	2				20 1	EXISTING SPAR
EXISTING LOAD	20 1		27	28	1413		2	<u>                                     </u>	EXISTING SPARE	2Ø	1				3					2Ø 1	EXISTING SPAR
EXISTING LOAD	2Ø 1			30		2Ø	1	EXISTING SPARE	A314-RECEPS ABY CTR	-	-			400					400	2Ø 1	A329 - RECEPS
	- '	2352 1336 14		_	3949 3613 3400			-	A314 - DESK/TY	20		300				8 9	300			20 1	4329 - DESK/TV
1				L		4	Д	6,301	EXISTING SPARE	20	1				9					20 1	EXISTING SPAR
								4,949	A304 - RECEPS A	20	1	1	İ	600					1	20 1	EXISTING SPAR
								.,			· ·										
NOTE: REFER TO GENER	AL NOTE 'B'	]						4,800				300									
NOTE: REFER TO GENER FOR ADDITIONAL INFORM						Ŧ	C		A304 - DESK/TV A304 - RECEPS B	2Ø 2Ø	1	300	600		13 15	14				20 1 20 1 20 1	EXISTING SPARE

- RECEPS	TOTAL KW: 21.0 MOUNTING: SURFACE FEEDER: 4 *3/0 & 1 *6 LOAD DESCRIPTION EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR A314 - DESK/TY	1RIP 20 20	BUSSI	NG: CC	NEMA PPER	A-1								120 / 208
12/316-REC D - RECEPS	MOUNTING: SURFACE FEEDER: 4 *3/0 & 1 *6 LOAD DESCRIPTION EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR	1RIP 20 20	BUSSI - 2°C. C/B	NG: CC	PPER		FAUL							
D - RECEPS	FEEDER: 4 *3/0 & 1 *6 LOAD DESCRIPTION EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR	1RIP 20 20	- 2°C. C/B									SINCE		MLO(AMPS): 200
- RECEPS	LOAD DESCRIPTION EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR	1RIP 20 20	C/B	Дф	LOAD		LOC			T. A-31			7.0	
RE	EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR	TRIP 20 20		Дф						LOAD	-	6	2/B	
RE	EXISTING SPARE EXISTING SPARE A314-RECEPS ABY CTR	2Ø 2Ø	1		Bø	C¢	CCT.	. NO.	Дф	Bø	C¢		POLE	LOAD DESCRIPTION
RE	A314-RECEPS ABY CTR						1	2	•••			20		
RE		20	1				3	4				2Ø	1	EXISTING SPARE
	A314 - DESK/TV	2Ø	1			400	5	6			400	2Ø	1	A329 - RECEPS ABY CTR
		2Ø	1	300			T	8	300			2Ø	1	A329 - DE6K/T∨
	EXISTING SPARE	2Ø	1				9	10				2Ø	1	EXISTING SPARE
	A304 - RECEPS A	2Ø	1			600	11	12				2Ø	1	EXISTING SPARE
	A3Ø4 - DESK/T∨	2Ø	1	300			13	14				2Ø	1	EXISTING SPARE
	A304 - RECEPS B	2Ø	1		600		15	16				2Ø	1	EXISTING SPARE
	A313-QUAD/ABY CTR	2Ø	1			800	17	18			400	2Ø	1	A328 - RECEPS ABY CTR
	A313 - DESK/T∨	2Ø	1	300			19	2Ø	300			2Ø	1	A328 - DE6K/T∨
	EXISTING SPARE	20	1				21	22		400		2Ø	1	A327 - RECEPS ABY CTR
	EXISTING SPARE	2Ø	1				23	24				2Ø	1	EXISTING SPARE
	A307-RECEPS ABY CTR	2Ø	1	400			25	26				2Ø	1	EXISTING SPARE
	A3Ø7 - DESK/T∨	2Ø	1		300		27	28				2Ø	1	EXISTING SPARE
	EXISTING SPARE	2Ø	1				29	3Ø			900	2Ø	1	A327 - DESK/T∨
	A306 - RECEPS A	2Ø	1	600			31	32				2Ø	1	EXISTING SPARE
	A306 - DESK/TV	2Ø	1		300		33	34				2Ø	1	EXISTING SPARE
	A306 - RECEPS B	2Ø	1			600	35	36				2Ø	1	EXISTING SPARE
	A305 - RECEPS A	2Ø	1	600			37	38				2Ø	1	EXISTING SPARE
	A305 - DE6K/TV	2Ø	1		300		39	40				2Ø	1	EXISTING SPARE
	A305 - RECEPS B	2Ø	1			600	41	42				2Ø	1	EXISTING SPARE
	A303 - RECEPS A	2Ø	1	600			43	44				2Ø	1	EXISTING SPARE
	A3Ø3 - DE6K/T∨	2Ø	1		300		45	46		300		2Ø	1	A322 - DE <del>SK</del> /TV
	A3Ø3 - RECEPS B	2Ø	1			600	47	48				2Ø	1	EXISTING SPARE
	A321 - QUAD/ABY CTR	2Ø	1	800			49	50				2Ø	1	EXISTING SPARE
	EXISTING SPARE	2Ø	1				51	52				2Ø	1	EXISTING SPARE
	A330 - REC/TV	2Ø	1			1200	53	54				2Ø	1	EXISTING SPARE
	EXISTING SPARE	2Ø	1				55	56				2Ø	1	EXISTING SPARE
	A321 - DE6K/T∨	2Ø	1		300		57	58						EXISTING SPACE
		20			$\sim$	$\sim$	100	60						EXISTING SPACE
<b>&gt;</b>	FC-3	15		292			61	62						EXISTING SPACE
$\mathcal{A}$			2		292		63	64						EXISTING SPACE
		$\overline{\ }$	$\overline{\mathbf{\nabla}}$	$\sim$	$\overline{}$		65	66						EXISTING SPACE
AD-3	EXISTING SPACE						67	68						EXISTING SPACE
	EXISTING SPACE						69	٦Ø						EXISTING SPACE
	EXISTING SPACE						71	72						EXISTING SPACE
	NOTE: REFER TO GENER FOR ADDITIONAL INFORM			·	5392	4800	J		1800	1300	1700	 	B= C=	7,792 6,692 6,500 20,984

200 3CRIPTION TV ARE ARE PS ABV. CTR PS A PS ABV. CTR TV PS ABV. CTR TV PS ABV. CTR TV PS ABV. CTR ARE S ABV. CTR ARE ARE ARE ARE ARE ARE ARE AR	<image/> <section-header><section-header><section-header><section-header><section-header><text><text><text><text><text><text><text></text></text></text></text></text></text></text></section-header></section-header></section-header></section-header></section-header>
200         36CRIPTION         ARE         ACE         ACE         ACE	GIBRALT'AR DESIGN         9102 N. Meridian St., Ste. 300         Indianopolis, IN 46260         Homepage www.GibraltarDesign.com         Project         21-112         DATE         02/07/21         COOPVRIGHT NOTICE:         THE CONCEPTS, DESIGNS, DETAILS, ETC, SHOWN ON         DRAWN BY         AG         CHECKED BY         DJ         COPYRIGHT NOTICE:         THE CONCEPTS, DESIGNS, DETAILS, ETC, SHOWN ON         THE DOTE CONSTRUCTION ON STATE OF TO SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, THE OWNER MAY RETAIN COPIES FOR TOP SUBALTAR DESIGN, T
	A Constant of the second

### **GENERAL ROUGH-IN NOTES: GENERAL NOTES:** 1) NOTHING SET FORTH IN THESE DRAWINGS SHALL RELEASE ANY CONTRACTOR FROM HIS CONTRACTOR SHALL USE THESE DRAWINGS IN CONJUNCTION WITH THE SPECIFICATIONS TO DETERMINE THE FULL SCOPE, INTENT AND REQUIREMENTS OF THE PROJECT. SPECIFICATIONS AND RESPONSIBILITY TO PROVIDE APPROPRIATE QUANTITIES, FIELD MEASUREMENTS, DIMENSIONAL STABILITY, INSTALLATION, ANCHORAGE, AND COORDINATION WITH OTHER TRADES: OR RELEASE HIM DRAWINGS ARE INTENDED TO BE COMPLEMENTARY, NOT MUTUALLY EXCLUSIVE. WORK SHOWN ON FROM HIS RESPONSIBILITY TO IDENTIFY AND RESOLVE DEVIATIONS FROM THE REQUIREMENTS OF THE DRAWINGS BUT NOT LISTED IN THE SPECIFICATIONS. AND WORK DESCRIBED IN THE THE CONTRACT DOCUMENTS, OR FREE HIM OF HIS RESPONSIBILITY TO ALERT DESIGNER TO ERRORS SPECIFICATIONS BUT NOT SHOWN ON THE DRAWINGS SHALL BE INTERPRETED AS THOUGH WORK WERE FULLY DESCRIBED IN BOTH PLACES. THE HIGHER QUANTITY, HIGHER QUALITY, MORE LABOR OR OMISSIONS. INTENSIVE AND OVERALL MORE STRINGENT AND MORE COSTLY REQUIREMENT SHALL APPLY. 2) CONTRACTOR SHALL UTILIZE THESE DRAWINGS IN CONJUNCTION WITH THE SPECIFICATIONS TO DETERMINE THE FULL SCOPE, INTENT AND REQUIREMENTS OF THE PROJECT. SPECIFICATIONS AND COLORS OF CABLING USED FOR ALL COMMUNICATIONS TECHNOLOGY WORK SHALL BE REVIEWED AND APPROVED PRIOR TO PROCUREMENT AND INSTALLATION. DRAWINGS ARE INTENDED TO BE COMPLEMENTARY, NOT MUTUALLY EXCLUSIVE. WORK SHOWN ON THE DRAWINGS BUT NOT LISTED IN THE SPECIFICATIONS AND WORK DESCRIBED IN THE ALL LADDER RACK AND OTHER COMMUNICATION TECHNOLOGY CABLING PATHWAYS DEPICTED ON SPECIFICATIONS BUT NOT SHOWN ON THE DRAWINGS SHALL BE INTERPRETED AS THOUGH WORK WERE FULLY DESCRIBED IN BOTH PLACES. THE HIGHER QUANTITY, HIGHER QUALITY, MORE LABOR THE ENLARGED FLOOR PLANS AND OTHERWISE NECESSARY FOR PROFESSIONAL WIRE INTENSIVE AND OVERALL MORE STRINGENT AND MORE COSTLY REQUIREMENT SHALL APPLY UNLESS MANAGEMENT WITHIN THE MAIN EQUIPMENT ROOM (ER) AND ALL TELECOMMUNICATION ROOMS (TR) OTHERWISE CLARIFIED IN WRITING PRIOR TO BID. SHALL BE PROVIDED BY THE COMMUNICATIONS TECHNOLOGY CONTRACTOR. SEE DIVISION 27 SPECIFICATIONS AND DRAWINGS FOR REQUIREMENTS. 3) EACH CONTRACTOR SHALL VERIFY IN THE FIELD ALL EXISTING APPLICABLE CONDITIONS AND DIMENSIONS SHOWN ON THE DRAWINGS AND AS PERTINENT TO THE INTENT OF THESE DRAWINGS. THE DIVISION 27 CONTRACTOR SHALL THOROUGHLY REVIEW THE SPECIFIED ROUGH-IN TO ENSURE ANY DISCREPANCY DISCOVERED SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGNER PRIOR THAT SUPPLIED ROUGH-IN WILL SUPPORT THE CABLING AND DEVICES BEING SUPPLIED. DIVISION 27 TO THE COMMENCEMENT OF ANY WORK AFFECTED BY, OR RELATED TO, SUCH DISCREPANCY. EACH CONTRACTOR SHALL THOROUGHLY COORDINATE WITH THE DIVISION 26 ROUGH-IN PROVIDER PRIOR CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH, OR CAUSED BY HIS TO ROUGH-IN MATERIAL ACQUISITION AND INSTALLATION. FAILURE TO COMPLY WITH THIS REQUIREMENT. 4) EACH CONTRACTOR SHALL REVIEW ALL PORTIONS OF HIS WORK, BEFORE STARTING THE WORK, TO VERIFY THAT THE WORK WILL NOT PROHIBIT COMPLETION OF THE PROJECT AS INTENDED IN THESE **GENERAL PATHWAYS NOTES:** CONSTRUCTION DOCUMENTS. ALL QUESTIONS SHALL BE REFERRED TO THE DESIGNER FOR RESOLUTION. ROUGH-IN/PATHWAYS SHALL BE CLOSELY REVIEWED AND COORDINATED PRIOR TO INSTALLATION. IT IS THE RESPONSIBILITY OF THE ROUGH-IN PROVIDER TO THROUGHLY REVIEW AND UNDERSTAND THE EACH CONTRACTOR SHALL BE RESPONSIBLE FOR JOB CLEANLINESS. PROJECT AREAS SHALL BE REQUIREMENTS OF THE SYSTEMS THAT WILL USE THE PATHWAYS. THIS INCLUDES, BUT IS NOT THOROUGHLY CLEANED AND TRASH DISPOSED OF AT THE END OF EACH WORK DAY. OWNER'S LIMITED TO, PROPER SIZING OF BOXES, AND PROVIDING THE CORRECT QUANTITY AND SIZES OF FACILITIES SHALL NOT BE USED FOR WASTE DISPOSAL. CONVEYANCES. THE COST FOR REMOVING AN INSUFFICIENT PATHWAY SYSTEM AND INSTALLING AN APPROPRIATELY SIZED AND TYPED PATHWAY SYSTEM IS THE RESPONSIBILITY OF THE 6) PROVIDE DUST PROTECTION WHEN WORKING IN EXISTING FACILITIES, SEAL OFF ALL WORK AREAS CONTRACTOR. FROM REMAINDER OF THE EXISTING FACILITY TO RETAIN ALL CONSTRUCTION DIRT AND DUST. SEAL PATHWAYS SHALL BE COMPLIANT WITH THE CONTRACT DOCUMENTS. EXISTING DOORS WITH TAPE AND PROVIDE DUST-PROOF BARRIERS AS REQUIRED. WHERE CONDUIT IS SHOWN AND/OR SPECIFIED, PROVIDE PULL BOXES SHOWN ON THE DRAWINGS 7) ALL WORK SHALL BE SEQUENCED TO PROVIDE FOR THE OWNER'S CONTINUED USE OF THE EXISTING PLUS ADDITIONAL PULL BOXES AS FOLLOWS: FACILITY WHEN REQUIRED. OWNER'S ACCESS, EGRESS AND SAFETY SHALL BE MAINTAINED BY EACH CONTRACTOR. THE SEQUENCE OF WORK SHALL BE AS DETERMINED BY THE CONSTRUCTION A) EVERY 180 DEGREES OF CONDUIT BEND; MANAGER. REFER TO THE PROJECT MANUAL FOR FURTHER REQUIREMENTS. B) EVERY 100 FEET OF CONDUIT PATH. 8) EACH CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL SURFACES AND FINISHES IN INSTALLED PULL BOXES AND JUNCTION BOXES BE IN ACCESSIBLE LOCATIONS. THE INTERIOR OR EXTERIOR OF THE FACILITY. DAMAGED SURFACES OR FINISHES RESULTING FROM THE PERFORMANCE OF THE WORK OR NEGLIGENCE SHALL BE REPAIRED AT NO COST TO THE OWNER ROUGH-IN REQUIREMENTS INDICATED ON PLANS, ELEVATIONS AND DETAILS TAKE PRECEDENCE BY THE RESPONSIBLE CONTRACTOR. FINISHES AND SURFACES SHALL BE MADE TO MATCH THE OVER VALUES GIVEN ON THE LEGEND, BUT ONLY TO THE EXTENT THAT THOSE SPECIFIC ITEMS ARE EXISTING FINISHES OR SURFACES TO THE SATISFACTION OF THE OWNER AND ARCHITECT/ MODIFIED. CONSTRUCTION MANAGER. PROVIDE PATHWAYS FOR COMMUNICATIONS AND SECURITY SYTEMS CABLING. REFER TO SECTIONS 9) "TECHNOLOGY" CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TELEPHONE, DATA. "PATHWAYS FOR COMMUNICATIONS" AND "PATHWAYS FOR SAFETY AND SECURITY". CENTRAL SOUND, SECURITY CCTV AND ALARM SYSTEM SERVICES IN ALL EXISTING AREAS FOR DURATION OF PROJECT FOR MULTI-PHASED PROJECTS. CONTRACTOR SHALL COLLABORATE WITH 6) PROVIDE COVER PLATES FOR DEVICE, JUNCTION AND PULL BOXES. COORDINATE MATERIAL AND OWNER'S TECHNOLOGY PERSONNEL AS NECESSARY AND PROVIDE TEMPORARY WIRING, CROSS-FINISH OF BLANK PLATES TO MATCH SURROUNDING PLATES. CONNECTS, TERMINATION DEVICES, AND LABOR TO MAINTAIN OPERATION ACCEPTABLE TO THE OWNER. CONTRACTOR SHALL REFER TO THE FRONT END DOCUMENTS OF THE SPECIFICATIONS FOR WHERE CONDUITS ARE SPECIFIED "TAAC" (TO ABOVE ACCESSIBLE CEILING) THIS SHALL MEAN THAT ADDITIONAL INFORMATION RELATED TO PHASING. ALL PHASING QUESTIONS SHALL BE ADDRESSED CONDUITS SHALL BE STUBBED INTO AN ACCESSIBLE CEILING CAVITY WITHIN THE SAME ROOM AS THE PRIOR TO THE CONTRACTOR'S BID SUBMISSION. DEVICE THE CONDUIT SERVES. SEE ALSO "DEFINITIONS." 10) EACH CONTRACTOR SHALL FIELD VERIFY ALL EXISTING APPLICABLE CONDITIONS AND DIMENSIONS WHERE DEVICE CONDUITS ARE SPECIFIED "TAHC" (TO ABOVE ACCESSIBLE HALLWAY/CORRIDOR SHOWN ON THE DRAWINGS. AS PERTAINS TO THE INTENT OF THESE DRAWINGS, CONTRACTOR CEILING) THIS SHALL MEAN THAT CONDUITS SHALL BE RUN CONTINUOUS AND STUBBED OUT INTO AN SHALL BRING TO THE ATTENTION OF THE ARCHITECT AND DESIGNER ANY DISCREPANCIES ACCESSIBLE CEILING CAVITY WITHIN THE NEAREST CORRIDOR FEATURING AN ACCESSIBLE CEILING DISCOVERED PRIOR TO THE COMMENCEMENT OF ANY WORK AFFECTED BY OR RELATED TO SUCH CAVITY. SEE ALSO "DEFINITIONS." DISCREPANCY. EACH CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH OR CAUSED BY THAT CONTRACTOR'S FAILURE TO COMPLY WITH THIS REQUIREMENT. 9) CONDUIT INSTALLER SHALL INSTALL PULL STRINGS IN CONDUITS IMMEDIATELY AFTER INSTALLATION. THIS INCLUDES CONDUITS TARGETED FOR IMMEDIATE AND FUTURE USE. 10) WHERE A MOUNTING HEIGHT MEASUREMENT IS APPLIED TO A ROUGH-IN. THE MEASUREMENT SHALL BE REFERENCED TO THE CENTER OF THE ROUGH-IN DEVICE, EXCEPT WHERE OTHERWISE DETAILED, GENERAL CABLING NOTES: 11) ROUGH-IN BOXES SHALL BE INSTALLED FLUSH IN WALLS AND CEILINGS 1) ALL PROVIDED CABLE SHALL BE RATED FOR THE ENVIRONMENT INSTALLED. 12) PATHWAYS SHALL BE INSTALLED CONCEALED MANNER. EXPOSED CONDUIT SHALL NOT BE 2) ALL INSTALLED CABLING SHALL BE CONTINUOUS AND WITHOUT SPLICES, EXCEPT WHERE PERMITTED IN FINISHED AREAS. OTHERWISE NOTED. 13) SURFACE MOUNT BACK BOXES AND MATCHING RACEWAY SHALL BE USED FOR COMMUNICATION 3) "ABOVE ACCESSIBLE CEILING" SHALL BE INTERPRETED TO GENERALLY MEAN THE ACCESSIBLE TECHNOLOGY DEVICES THAT ARE NOT INSTALLED WITHIN A WALL OR CEILING CAVITY ABOVE SUSPENDED CEILING AND BENEATH THE DECK/FLOOR ABOVE. CONDUITS STUBB ABOVE ACCESSIBLE CEILING SHALL TE 13) PROVIDE CODE-COMPLIANT FIRE-STOPPING FOR PATHWAYS THROUGH FIRE-RATED WALLS, FLOORS CAN VIEW AND ACCESS WITHOUT STRA AND CEILINGS. VERTICAL LIFT DEVICE, 14) ALL CONDUIT PROVIDED FOR COMMUNICATION TECHNOLOGY USE SHALL BE PROVIDED WITH NYLON 4) COLOR CODING OF CABLING SHALL BE END-BUSHINGS. BUSHINGS SHALL BE INSTALLED AT EACH END OF THE CONDUIT; AT EACH PULL/ INSTALLATION. JUNCTION/DEVICE BOX; ON CONDUIT STUBS; AT EACH LOCATION WHERE PULLING CABLE THROUGH THE CONDUIT MAY CAUSE THE CABLE TO RUB AGAINST THE END OF A CONDUIT OR ITS END FITTING. 5) ALL CABLE IN EXPOSED CEILINGS SHAI 15) DEVICES DESIGNATED WITH THE "CH" SUBSCRIPT (COUNTER HEIGHT) SHALL BE CLOSELY COORDINATED IN THE FIELD WITH ARCHITECT, CASEWORK AND FURNITURE VENDORS PRIOR TO ROUGH-IN. SLEEVE AND FIRE-STOPPING NO 16) DEVICES TO BE INSTALLED AT CASEWORK LOCATIONS SHALL BE CLOSELY COORDINATED WITH THE 1) ALL PENETRATIONS THROUGH BUILDI CASEWORK TO ENSURE FUNCTIONAL CONNECTIVITY. COORDINATE WITH THE ARCHITECT AND THE CABLING SHALL BE SLEEVED. EQUIPMENT AND CASEWORK DRAWINGS. 2) ALL SLEEVES THROUGH WALLS OR FL 17) ROUGH-IN SHALL BE CLOSELY COORDINATED TO COMPLEMENT THE INTENDED FURNITURE PLAN AND ONE OF THE APPROVED METHODS FO TO ENSURE THE SAFE AND EFFICIENT CONNECTIVITY OF EQUIPMENT. 3) APPROVED MANUFACTURERS FOR UL 18) MANY COMMUNICATIONS DEVICES ARE INTENDED TO HAVE ADJACENT POWER OR INTEGRAL UNIQUE FIRESTOP PRODUCTS, AND WI RECEPTACLES (MULTI-SERVICE) TO SERVE THE SAME EQUIPMENT. CLOSE PROXIMITY OF SEPARTE DEVICES IS CRITICAL FOR USABILITY AND AESTHETICS. COORDINATE THE LOCATION OF SEPARATE 4) ALL SLEEVES THROUGH FLOORS SHALI DEVICES SO THAT THEY ARE LOCATED ADJACENT AND AT THE SAME ELEVATION. THE FLOOR RATING. 19) TELECOMMUNICATION DEVICE MOUNTING HEIGHT SHALL BE CONSISTENT WITH THE ELECTRICAL 5) ALL UN-USED SLEEVES THROUGH WAL OUTLET MOUNTING HEIGHTS FOR THE FACILITY (NEW OR EXISTING) UNLESS OTHERWISE INDICATED FIRESTOPPED TO A RATING EQUAL TO ON DRAWINGS. CONTRACTOR SHALL SEEK THE DIRECTION OF THE DESIGNER/ARCHITECT/ENGINEER/ CONSULTANT SHOULD DISCREPANCIES BE FOUND WITHIN THE DRAWINGS, SPECIFICATIONS AND ACTUAL FIELD CONDITIONS. 6) ALL SLEEVES THROUGH WALLS HOLDI TO OR HIGHER THAN THE WALL RATING 20) CONDUITS STUBBED INTO THE CEILING CAVITY SHALL BE MARKED WITH AN INDELIBLE MARKER INDICATING THE CONDUIT'S INTENDED USE. MARK CONDUIT SO AS TO BE READABLE FROM BELOW. ALL PENETRATIONS SHALL BE PART OF LABEL WITHIN 6 INCHES OF THE CONDUIT BUSHING. BELOW OF EXAMPLES OF LABELS TO BE USED. PENETRATIONS SHALL EITHER BE AN A "CAMERA," "ICOM," "DOOR," "SPKR," "MIC," "CLOCK," "VOL," "PANEL," "WAP," "DATA," "PHONE," "COM," ASSEMBLY OR FIRESTOPPED WITH REMOVABLE PUTTY OR FIRESTOP BAGS. "RF," "VP," "INPUT," ETC. 21) WHERE SPECIFICATIONS AND/OR DRAWINGS INDICATE THE USE OF SURFACE RACEWAY AND BOXES IN LIEU OF RECESSED ROUGH-IN, THE BOX SIZE AND USABLE RACEWAY CABLE AREA SHALL SUBSTANTIALLY MATCH THAT OF THE DEFAULT STANDARD ROUGH-IN. IN SOME CIRCUMSTANCES THIS MAY REQUIRE THE CONTRACTOR TO PROCURE MATERIALS ONLY AVAILABLE BY SPECIAL ORDER FROM THE MANUFACTURERS. 22) LADDER RACK AND OTHER COMMUNICATION TECHNOLOGY CABLING PATHWAYS DEPICTED ON THE ENLARGED FLOOR PLANS SHALL BE PROVIDED AS INDICATED. ADDITIONAL PRODUCTS NECESSARY FOR PROFESSIONAL WIRE MANAGEMENT WITHIN THE MAIN EQUIPMENT ROOM <ER> AND ALL TELECOMMUNICATION ROOMS <TR> SHALL BE ALSO BE PROVIDED AS NECESSARY. 23) ELEVATOR TELEPHONE CONNECTIONS, SHALL BE CLOSELY COORDINATED WITH THE ELEVATOR PROVIDER. PROVIDE CONDUIT FROM THE ELEVATOR CONTROL PANEL TO THE CORRIDOR CEILING SPACE, UNLESS OTHERWISE INDICATED ON THE DRAWINGS. 24) COORDINATE THE TELEPHONE CONNECTION REQUIREMENTS FOR THE FIRE ALARM CONTROL PANEL (FACP) WITH THE FIRE ALARM INSTALLER. PROVIDE CONDUIT FROM THE FACP TO ACCESSIBLE CORRIDOR CEILING SPACE, UNLESS OTHERWISE INDICATED ON THE DRAWINGS. 25) COORDINATE DATA CABLING AND TERMINATION REQUIREMENTS FOR HVAC BUILDING AUTOMATION SYSTEM (BAS), WITH THE BAS PROVIDER. 26) PROVIDE A MINIMUM OF TWO (2) 2-INCH DIAMETER THROUGH-THE-WALL CONDUIT SLEEVES FOR USE AS COMMUNICATION AND SECURITY CABLE PATHWAYS INTO EACH SPACE CONTAINING COMMUNICATION AND SECURITY DEVICES. ROUTE CONDUITS FROM ABOVE ACCESSIBLE CEILING TO THE NEAREST HALLWAY/CORRIDOR FEATURING AND ACCESSIBLE CEILING CAVITY.

$\square$	AUDIO-VISUAL SYSTEMS
X LI	VOICE AND DATA OUTLET WITH LOCAL INPUT
$\mathbf{\nabla}_{\mathbf{x}}^{\mathbf{L}}$	X = QUANTITY OF (4) PAIR VOICE/DATA CABLES (MIN. 1 VOICE AND 1 DATA CABL
	WITHOUT SUBSCRIPT) LI = FUTURE LOCAL INPUT CABLING TO A VIDEO PROJECTOR, TELEVISION, ETC.
	DATA OUTLET WITH LOCAL INPUT           X = QUANTITY OF (4) PAIR DATA CABLES (MIN. 2 DATA CABLE WITHOUT
	SUBSCRIPT)
Y	LI = FUTURE LOCAL INPUT CABLING TO A VIDEO PROJECTOR, TELEVISION, ETC.
$\mathcal{A}_{\mathbf{v}}$	
	QUANTITY OF TWO - (4) PAIR DATA CABLES - THIS OUTLET WILL ALSO ACCEPT CABLING FROM LOCAL INPUT LOCATIONS
	Y = MODEL
Y	VIDEO PROJECTOR WALL MOUNTED
	QUANTITY OF TWO - (4) PAIR DATA CABLES - THIS OUTLET WILL ALSO ACCEPT
VF	Y = MODEL
	FLAT PANEL DISPLAY CEILING MOUNTED - NETWORK
<sup>Y</sup> ⟨ ¬¬¬ <sup>FP</sup>	QUANTITY OF TWO - (4) PAIR DATA CABLES - THIS OUTLET WILL ALSO ACCEPT LOCAL INPUT CABLES
	Y = MODEL
<b>m</b> Y	FLAT PANEL DISPLAY WALL MOUNTED - NETWORK
FP ·	QUANTITY OF TWO - (4) PAIR DATA CABLES - THIS OUTLET WILL ALSO ACCEPT
┝┥╒┓	LOCAL INPUT CABLES Y= MODEL / HEIGHT = 60" (UNLESS OTHERWISE NOTES)
AV X	AUDIO VIDEO (A/V) OUTLET X = SYSTEM
	Y = MODEL
	SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS
MC	MICROPHONE INPUT – WALL MOUNT
мс	SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS
	MICROPHONE INPUT – CEILING MOUNT
X	X = SYSTEM
(MC)	SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS
	SYSEM SPEAKER – RECCESSED CEILING MOUNTED
<b>~</b> ×	X = SYSTEM
$\langle S \rangle_{Y}^{\gamma}$	Y= MODEL
-	
×	SYSTEM SPEAKER – WALL MOUNTED X = SYSTEM
s	Y = MODEL
	SYSTEM SPEAKER – PENDANT MOUNTED
Ϋ́×	X = SYSTEM
𝔄 <sup>∧</sup>	Y = MODEL
	SYSTEM SPEAKER – CEILING MOUNTED
	X = SYSTEM
$\langle s \rangle_{Y}^{\wedge}$	Y = MODEL
X	
	X = SYSTEM
	Y = TYPE
	Y = TYPE SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS
	SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS
	SEE SYTEM DETAILS FOR CONNECTIVITY REQUIREMENTS INTERACTIVE WHITE BOARD

AD-3

	DISTRIBUTED SYSTEMS
$\langle S \rangle_{Y}^{V}$	SPEAKER – SUSPENDED CEILING MOU CABLE AS REQUIRED BY SYSTEM V = INTREGAL VOLUME CONTROL Y = MODEL
€ Y	SPEAKER – SOLID CEILING MOUNT CABLE AS REQUIRED BY SYSTEM V = INTREGAL VOLUME CONTROL Y = MODEL
⊢s <sup>γ</sup>	SPEAKER, WALL TYPE CABLE AS REQUIRED BY SYSTEM Y = MODEL
S <sub>Y</sub>	SPEAKER, PENDANT CABLE AS REQUIRED BY SYSTEM Y = MODEL
₽	SPEAKER, VOLUME CONTROL CABLE AS REQUIRED BY SYSTEM P = PRIORITY OVERRIDE OPTION
нн	SPEAKER, HORN TYPE CABLE AS REQUIRED BY SYSTEM Y = MODEL
VIS	VIDEO INTERCOM CALL STATION QUANTITY ONE - (4) PAIR DATA CABLE ACCESS CONTROL SYSTEMS CABLE TO DOOR CONTROLER
VIM	VIDEO INTERCOM MASTER STATIC QUANTITY ONE - (4) PAIR DATA CABLE ACCESS CONTROL SYSTEMS CABLE TO DOOR CONTROLER
Ю	CLOCK – BATTERY TYPE WALL CLOCK; 12" DIAMETER, UNLESS OTHERWISE NOTE WG = PROVIDE WITH ACCESSORY WIRE GUARD
HOO	CLOCK – BATTERY TYPE WALL CLOCK; 12" DIAMETER, UNLESS OTHERWISE NOTE WG = PROVIDE WITH ACCESSORY WIRE GUARD DOUBLE SIDED
(LED) <sub>Y</sub>	LED CLOCK – CEILING MOUNTED QUANTITY OF ONE - (4) PAIR DATA CABLE PER CLOCK Y = MODEL
(LED) Y LED	LED CLOCK QUANTITY OF ONE - (4) PAIR DATA CABLE PER CLOCK Y = MODEL DOUBLE SIDED
	LED CLOCK – WALL MOUNTED QUANTITY OF ONE - (4) PAIR DATA CABLE PER CLOCK Y = MODEL

[	
	SECURITY/LIFE SAFETY
	VIDEO SURVEILLANCE CAMERA OUTLET WALL MOUNTED
∑ <sup>CAM</sup>	QUAINTY OF ONE - (4) PAIR DATA CABLE (UNLESS OTHERWISE NOTED) Y = CAMERA TYPE
Y	VIDEO SURVEILLANCE CAMERA OUTLET CEILING MOUNTED
	QUAINTY OF ONE - (4) PAIR DATA CABLE (UNLESS OTHERWISE NOTED) Y = CAMERA TYPE
Y	VIDEO SURVEILLANCE CAMERA OUTLET EXTERIOR WALL
	QUAINTY OF ONE - (4) PAIR DATA CABLE (UNLESS OTHERWISE NOTED) Y = CAMERA TYPE
	SECURE DOOR
X SD	DENOTES A DOOR WITH CONNECTIVITY FOR STATUS SENSOR(S) AND LOCKING AND UN-LOCKING CAPABILITIES.
	X – WHERE UTILIZED WILL BE DEFINED ON SYSTEM DIAGRAM
	DOOR STATUS SENSOR
DS	DOOR STATUS SENSOR ALLOWS DOOR MONITORING WITH OR WITHOUT LOCKING PROVISIONS CABLE AS REQUIRED BY SYSTEM
	DOOR RELEASE
	DOOR RELEASE SWITCH ALLOWS MANUAL ACTUATION OF AN ELEC. DOOR LOCK. CABLE AS REQUIRED BY SYSTEM
	KEYPAD
KP	KEYPAD UTILIZED TO ACTUATE ACCESS TO A SECURE DOOR. CABLE AS REQUIRED BY SYSTEM
	PROXIMITY CARD READER
	QUANTITY ONE – (4) PAIR DATA CABLE
CR	Y = MODEL
	MAY BE A COMBINATION KEYPAD AND READER; SEE SPECIFICATION.
	PANIC (DURESS) SWITCH
PS 上	SWITCH UTILIZED TO MANUALLY ACTUATE ALARM AND/OR ACCESS CONTROL SYSTEM.
	ELECTRONIC HOLD OPEN
EHO	CABLE AS REQUIRED BY SYSTEM
	ELECTRIC DOOR LOCK/STRIKE
	REQUIRES 120V POWER
	SECURITY MONITOR
SM L	ONE DATA CABLE, PLUS OTHER SPECIAL A/V CABLES AS REQUIRED BY SYSTEM
	X = TYPE

- BBED		
ERSON	CAM	QUAINTY OF ONE - (4
		Y = CAMERA TYPE
NT AND	N/	VIDEO SURVE
	Y	QUAINTY OF ONE - (4
		Y = CAMERA TYPE
	v	VIDEO SURV
		QUAINTY OF ONE - (4
		Y = CAMERA TYPE
ATIONS		
LIZING	l _×	DENOTES A DOOR W
	SD	AND UN-LOC
STEMS,		X – WHERE UTILIZED
o i Eino,		
		DOOR STATUS SENS
THAN	DS	
		CABLE AS REQUIRED
		DOOR RELEASE SWI
EQUAL		
		CABLE AS REQUIRED
	KP	KEYPAD UTILIZED TO
		CABLE AS REQUIRED
	CR	QUANTITY ONE - (4)
		Y = MODEL
		MAY BE A COMBINAT
	PS	SWITCH UTILIZED TO SYSTEM.
	EHO	CABLE AS REQUIRED

ERMINATE IN A LOCATION IN WHICH A NORMAL HEIGHT P RAIN WHILE STANDING UPRIGHT ON A LADDER OR OTHER
E COORDINATED AND APPROVED PRIOR TO PROCUREME
ALL BE IN CONDUIT.
TES:
ING STRUCTURE (WALL AND/OR FLOORS) FOR COMMUNIC
LOORS HOLDING A FIRE RATING SHALL BE INSTALLED UTI DR A UL LISTED ASSEMBLY.
LISTED SLEEVES SHALL BE SPECIFIED TECHNOLOGY SY MREMOLD.
LL BE FIRESTOPPED TO A RATING EQUAL TO OR HIGHER
LLS OR FLOORS HOLDING A FIRE RATING SHALL BE O OR HIGHER THAN THE WALL OR FLOOR RATING.
NING A FIRE RATING SHALL BE FIRESTOPPED TO A RATING NG.
OF THE RE-USABLE PATHWAY SYSTEM; FIRESTOPPED ASSEMBLY WITH FIRESTOP MATERIALS BUILT INTO THE

$\langle S \rangle_{Y}^{V}$	CABLE V = INT Y = MO
€ Y	CABLE V = INT Y = MO
⊢s	CABLE Y = MC
J S <sub>Y</sub>	CABLE Y = MO
HV	CABLE P = PR
ЧĦ	CABLE Y = MO
VIS	QUANT ACCES
VIM	QUANT ACCES
Ю	WALL WG = F
HOO	WALL WG = F DOUBL
$\left< ED \right>_{Y}$	QUAN <sup>-</sup> Y = MC
	QUAN <sup>-</sup> Y = MC DOUBI
	QUAN <sup>-</sup> Y = MC

¥ <sup>×</sup>	х = С В = В
$\underbrace{\mathbf{Y}}^{w} \underbrace{\mathbf{V}}^{w}$	QUAI
$\underline{\Psi}^{\times}_{\mathbf{V}}$	X = C B = B
× × V F	X = C F = F
$\nabla^{\mathbf{x}} \nabla^{\mathbf{y}}$	X = C Y = (I
₩AP Υ	QUAI
WAP	QUAI
$\chi^{POS}$	X = C SEE
×	X = C
$\sum_{BAS}^{BAS}$	QUAI
FACP	QUAI
	QUAI
EMER EMER	QUAI
$\frac{1}{2} \qquad SP$	QUAI
Y	000

### SPEAKER – SUSPENDED CEILING MOUNTED AS REQUIRED BY SYSTEM REGAL VOLUME CONTROL SPEAKER – SOLID CEILING MOUNTED AS REQUIRED BY SYSTEM REGAL VOLUME CONTROL DEL SPEAKER, WALL TYPE AS REQUIRED BY SYSTEM SPEAKER, PENDANT AS REQUIRED BY SYSTEM

SPEAKER, VOLUME CONTROL
AS REQUIRED BY SYSTEM IORITY OVERRIDE OPTION
SPEAKER, HORN TYPE
AS REQUIRED BY SYSTEM

VIDEO INTERCOM CALL STATION	
TY ONE - (4) PAIR DATA CABLE	
S CONTROL SYSTEMS CABLE TO DOOR CONTROLER	

VIDEO INTERCOM MASTER STATION	
TITY ONE - (4) PAIR DATA CABLE	
SS CONTROL SYSTEMS CABLE TO DOOR CONTROLER	
CLOCK – BATTERY TYPE	

CLOCK; 12" DIAMETER, UNLESS OTHERWISE NOTED PROVIDE WITH ACCESSORY WIRE GUARD BLE SIDED LED CLOCK – CEILING MOUNTED

	TELECOMMUNICATIONS
<b>—</b> X	VOICE OUTLET; STANDARD
	X = QUANTITY OF - (4) PAIR VOICE CABLES CABLE WITHOUT SUBSCRIPT)
<b>,</b> ×	B = BLANK COVER, NO CONNECTORS OR CABLE
W	VOICE OUTLET; WALL MOUNTED TELEPHONE
	QUANTITY OF ONE - (4) PAIR VOICE CABLES CABLE WITHOUT SUBSCRIPT)

VOICE AND DATA OUTLET; STANDARD
UANTITY OF (4) PAIR VOICE/DATA CABLES (MIN. 1 VOICE AND 1 DATA CAB WITHOUT SUBSCRIPT)
ANK COVER, NO CONNECTORS OR CABLE
VOICE AND DATA OUTLET IN OFFICE FURNITURE
UANTITY OF (4) PAIR VOICE/DATA CABLES (MIN. 1 VOICE AND 1 DATA CAB WITHOUT SUBSCRIPT)
JRNITURE MOUNTED
DATA OUTLET; STANDARD
UANTITY OF (4) PAIR DATA CABLES (MIN. 1 DATA CABLE WITHOUT SUBSCRIPT)

(B) BLANK COVER: (CH) COUNTER HEIGHT WIRELESS LAN ACCESS POINT OUTLET WALL MOUNTED ANTITY OF TWO - (4) PAIR DATA CAT6A CABLES

WIRELESS LAN ACCESS POINT OUTLET CEILING MOUNTED
TITY OF TWO - (4) PAIR DATA CAT6A CABLES

POINT OF SALE DATA OUTLET
UANTITY OF (4) PAIR VOICE/DATA CABLES (MIN. 1 DATA CABLE WITHOUT SUBSCRIPT)
SYSTEM DIAGRAM FOR ADDITIONAL CABLING REQUIREMENTS
ABOVE CEILING OUTLET
UANTITY OF (4) PAIR DATA CABLES (MIN. 1 DATA CABLE WITHOUT SUBSCRIPT)
BUILDING AUTOMATION SYSTEMS OUTLET

ANTITY OF TWO - (4) PAIR DATA CABLES		
ORDIATE OUTLET LOCATION WITH BUIDLING CONTROLS CONTRACTOR		
FIRE ALARM CONTROL PANEL		
ANTITY OF TWO - (4) PAIR DATA CABLES		

RDINATE OUTLET LOCATION WITH FIRE ALARM CONTRACTOR		
ELEVATOR CONTROL OUTLET		
ITITY OF TWO - (4) PAIR DATA CABLES		
RDINATE OUTLET LOCATION WITH ELEVATOR CONTRACTOR		
EMERGENCY TELEPHONE OUTLET		
ITITY OF ONE - (4) PAIR VOICE CABLES (UNLESS OTHERWISE NOTED)		
RDINATE OUTLET LOCATION WITH SECURITY SYSTEM CONTRACTOR		
SECURITY ALARM PANEL OUTLET		

ITITY OF TWO - (4) PAIR DATA CABLES
RDINATE OUTLET LOCATION WITH SECURITY SYSTEMS CONTRACTOR

### SCOPE OF WORK


- "T" SERIES DRAWINGS BEING ISSUED FOR SCOPE AND COORDINATION. THE SOUND AND SECURITY SYSTEMS TO PART OF A LATER BID PACKAGE.
- THE ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL OUTLET / JUNCTION BOXES, CONDUITS AND RACEWAY FOR ALL LOW VOLTAGE SYSTEMS. THIS WORK IS DEPICTED ON THE "E" AND "T" SERIES DRAWINGS. FOR COORDINATION PURPOSES, OCCASSIONALLY AN ITEM OF WORK MAY BE SHOWN ON THE E SERIES
- DRAWINGS AND THE T SERIES DRAWINGS. IN ADDITION, THE SAME WORK MAY BE INCLUDED ON MULTIPLE T SERIES DETAIL SHEETS FOR SIMILAR REASONS. REQUEST A CLARIFICATION FOR ANY ITEMS THAT APPEAR UNCLEAR AS TO QUANTITY OR CONTRACT RESPONSIBILITY. EXAMPLE: ELECRICAL DEVICES ARE SHOWN ON T SERIES DETAIL SHEETS FOR COORDINATION AND SPACING PURPOSES; THE ELECTRICAL OUTLETS AND POWER EQUIPMENT IS THE RESPONSIBILITY OF DIVISION 26. LIKEWISE, SOME TELECOMMUNICATIONS CONDUITS APPEAR ON E SERIES SHEETS FOR SPACE COORDINATION; TELECOMMUNICATIONS PATHWAY AND SPACES ARE COVERED UNDER DIVISION 27.
- REFER TO DIVISION 26 AND DIVISION 27 SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- NO LOW VOLTAGE CABLING SHALL RUN EXPOSED IN AREAS OF THE BUILDING THAT DO NOT HAVE CEILINGS (I.E. GYMNASIUMS, LOCKER ROOMS, ETC.)- ALL CONDUITS RUN TO NEAREST ACCESSIBLE CEILING SPACE.

### LEGEND NOTES

- (1) BASE SYMBOLS ARE UTILIZED TO REFERENCE THE FLOORPLAN LOCATION AND PROPER ROUGH-IN REQUIREMENTS. WHERE SUBSCRIPTS ARE USED WITH THESE SYMBOLS, THEY MODIFY THE REQUIREMENTS. ROUGH-IN REQUIREMENTS CAN BE FOUND ON THE "T-7XX" SERIES DRAWINGS. PRIOR TO INSTALLATION OF ROUGH-IN, VERIFY ROUGH-IN SIZE REQUIREMENTS WITH DEVICE SUPPLIER; (3) INCREASE SIZE OF BOX, AS REQUIRED TO ACCOMMODATE THE QUANTITY AND SIZE OF CONDUITS ENTERING BOX.
- (4) ALL 1-GANG AND 2-GANG ROUGH-IN BOXES, RECESS/FLUSH MOUNTED, SHALL BE ASSEMBLED FROM 4" SQUARE BOXES AND SEPARATE TRIM RINGS. DEPTH OF COMPOSITE ASSEMBLY SHALL AS INDICATED, MINIMUM
- (5) IN APPLICATIONS WHERE THE DRAWINGS AND/OR SPECIFICATIONS REQUIRE THE USE OF SURFACE RACEWAY AND BOXES IN LIEU OF CONCEALED ROUGH-IN, CONTRACTOR SHALL MATCH THE SIZE OF THE BOX LISTED ON THE LEGEND; SHALL MATCH THE QUANTITY OF USABLE RACEWAYS; AND SHALL MATCH THE USABLE RACEWAY CABLE AREA SUBSTANTIALLY. TO QUANTITY AND SIZES OF RACEWAYS LISTED ON THE LEGEND. CONTRACTOR IS ADVISED THAT THIS MAY REQUIRE PROCUREMENT OF MATERIALS ONLY
- AVAILABLE BY SPECIAL ORDER FROM THE MANUFACTURERS. WHERE FIELD CONDITIONS INVOLVE INACCESSIBLE AREAS THE ROUGH-IN SHALL BE MODIFIED TO ALLOW THE PATHWAY TO BE ACCESSIBLE AND REUSABLE.
- COLOR CODING OF CABLING SHALL BE COORDINATED AND APPROVED PRIOR TO PROCUREMENT AND INSTALLATION. (8) SYMBOLS AND SUBSCRIPTS MAY DISTINGUISH BETWEEN VOICE (V) AND DATA (D) INTENDED USES. MATERIALS AND INSTALLATION FOR VOICE AND DATA USES SHALL BE IDENTICAL UNLESS SPECIFICALLY
- NOTED. (1D. 1V IS THE SAME AS 2 CABLES). SYMBOLS PLACED ON EXTERIOR WALLS WITH A "WP" SUBSCRIPT SHALL BE INSTALLED WITH WEATHERPROOF HOUSINGS AND THE ROUGH-IN SEALED FROM MOISTURE INGRESS.
- (10) WHERE A TELECOMMUNICATIONS OUTLET LOCATION IS ADJACENT TO AN ELECTRICAL OUTLET, THE MOUNTING HEIGHT WILL BE THE SAME FOR EACH. WHERE MULTIPLE TELECOMMUNICATIONS ARE ADJACENT (SUCH AS TELECOMMUNICATIONS AND SOUND DEVICES, FACEPLATES SHALL BE COORDINATED TO THE SAME TYPE AND COLOR AND MOUNTED AT THE SAME HEIGHT.

PATHWAY AND SPACES DEVICES				
	TELECOMMUNICATION WALL LINING (BACKBOARD) 8' TALL, 4' WIDTH ¾" AC PLYWOOD; CUT TO FIT SPACE AS SHOWN PAINTED WITH FIRE RETARDANT WHITE PAINT			
Ħ	LADDER RACK SIZE AS INDICATED 8' MOUNTING HEIGHT WHEN HORIZONTAL, UON			
	4" DIAMETER UNLESS OTHERWISE NOTED; PROVIDE FIRE STOPPING; ROUTE FROM ROOM TO ACCESSIBLE CEILING			
	NOTE: PROVIDE WATERFALL DEVICE WHEN CABLE DROP IS GREATER THAN 6"  SLEEVE THROUGH WALL  2" DIAMETER UNLESS OTHERWISE NOTED: PROVIDE FIRE STOPPING:			
	2 DIAMETER UNLESS OTHERWISE NOTED, PROVIDE FIRE STOPPING, ROUTE FROM ACCESSIBLE CEILING TO ACCESSIBLE CEILING NOTE; NOT ALL SLEEVES WILL BE SHOWN, ONLY ADDITIVE INSTANCES REQUIRED TO ACHIEVE DESIGN GOALS FIRE RATED SLEEVE THROUGH FLOOR			
$\bigcirc$	4" DIAMETER UNLESS OTHERWISE NOTED; PROVIDE FIRE STOPPING; ROUTE FROM ROOM TO ACCESSIBLE CEILING NOTE: PROVIDE WATERFALL DEVICE WHEN CABLE DROP IS GREATER THAN 6"			
۲	POKE-THRU – FIRE RATED DEVICE SEE ELECTRICAL DRAWINGS FOR POKE-THRU SIZE AND TYPE ADJACENT SYMBOL DENOTES CABLING REQUIREMENTS MODIFIED TO FIT BOX			
۲	FLOOR BOX – FLUSH TO FINISHED FLOOR         SEE ELECTRICAL DRAWINGS FOR FLOORBOX SIZE AND TYPE         ADJACENT SYMBOL DENOTES CABLING REQUIREMENTS MODIFIED TO FIT BOX			
	FURNITURE WHIP - WALL			
O	FURNITURE WHIP FROM FIRE RATED POKE THROUGH DEVICE         X = [WHERE X REPRESENTS A-C] POKE-THRU SIZE AND TYPE         1 1/4" WHIP FITTING MINIMUM			
РР	TELEPOWER POLE           ADJACENT SYMBOL DENOTES CABLING REQUIREMENTS MODIFIED TO FIT BOX			
J P	JUNCTION/PULL BOX – WALL MOUNTED SIZE AS NOTED OR CALCULATED BY QUANTITY AND SIZE OF CONDUITS NOTE; ALL BOXES SHALL BE MOUNTED SO AS TO ALLOW RE-ENTRY IN A SAFE MANNER			
U P	JUNCTION/PULL BOX – FLOOR MOUNTED SIZE AS NOTED OR CALCULATED BY QUANTITY AND SIZE OF CONDUITS NOTE; ALL BOXES SHALL BE MOUNTED SO AS TO ALLOW RE-ENTRY IN A SAFE			
0 P	MANNER JUNCTION/PULL BOX – CEILING MOUNTED SIZE AS NOTED OR CALCULATED BY QUANTITY AND SIZE OF CONDUITS NOTE; ALL BOXES SHALL BE MOUNTED SO AS TO ALLOW RE-ENTRY IN A SAFE MANNER			





SCALE: 3/32 = 1'-0"

3 EXISTING DATA CABINET TO BE REMOVED. REMOVE FIBER CABLING ASSOCIATED WITH DATA CABINET BACK TO THE SOURCE. 4 EXISTING CLOCK TO BE REMOVED. SECURELY STORE IN A LOCATION DESIGNATED BY OWNER. EXISTING INTERCOM SPEAKER TO BE REMOVED. EXISTING MAIN INTERCOM CABINET, TO REMAIN IN SERVICE UNTIL AREA IS DEMO'D. WHEN AREA IS READY TO BE DEMO'D REMOVE INTERCOM CABINET AND FOR ANY INTERCOM SPEAKERS THAT NEED TO REMAIN IN SERVICE IN OTHER AREAS WAITING FOR DEMO PULL THE EXISTING SPEAKERS BACK TO THE NEAREST NEW TELECOM ROOM. EXISTING AUDIO/VIDEO SYSTEMS AND DEVICES

(ALL DEMOLITION NOTES MAY NOT BE USED ON THIS SHEET.)

SURFACE RACEWAY REMOVE SURFACE RACEWAY.

2 EXISTING WIRELESS ACCESS POINT(S) TO BE REMOVED.

LOCATION DESIGNATED BY OWNER.

EXISTING TELECOMMUNICATION OUTLET(S) TO BE REMOVED.

REMOVE CABLE BACK TO THE SOURCE. IF OUTLET(S) ARE IN

REMOVE CABLE BACK TO THE SOURCE. SECURELY STORE IN A


DEMOLITION NOTES:

- (PROJECTOR, TELEVISION, INTERACTIVE BOARD), AND RELATED MOUNTS AND CABLING, ETC. TO BE REMOVED, SECURELY STORE IN A LOCATION DESIGNATED BY OWNER. NOTE - MOST OF THE CLASSROOM PROJECTORS ARE SITTING ON PORTABLE CARTS.
- EXISTING SECURITY DEVICES (CAMERAS, CARD READER, CONTROLLER, DOOR INTERCOM ETC.) AND RELATED MOUNTS TO BE REMOVED. REMOVE CABLE BACK TO THE SOURCE.
- 9 EXISTING SECURITY CAMERA(S) TO REMAIN. CEILING MOUNTED UNITS SHALL BE DISCONNECTED FROM CEILING TILE AND TEMPORARILY SUPPORTED TO STRUCTURE ABOVE
- CEILING. 10 EXISTING INTERCOM SPEAKER(S) TO REMAIN. DISCONNECT FROM CEILING TILE AND PROVIDE TEMPORARY ABOVE CEILING
- SUPPORT. (TYPICAL) 11 EXISTING WIRELESS ACCESS POINT TO REMAIN DISCONNECT


- GENERAL DEMOLITION NOTES:
- THE CONTRACT DOCUMENTS DO NOT PROPOSE TO SHOW ALL 1 SYSTEMS, MATERIALS, OR EQUIPMENT EXISTING ON THE PROJECT THAT WILL REQUIRE DEMOLITION. DEMOLITION DRAWINGS ARE BASED ON PARTIAL FIELD OBSERVATION. REPORT DISCREPANCIES TO THE CONSULTANT BEFORE DISTURBING EXISTING INSTALLATION.
- REMOVE ALL ABANDONED CABLING AS DEFINED BY THE NEC. ALL REMOVED TECHNOLOGY AND / OR SECURITY DEVICE TO BE INVENTORIED AND TURNED OVER TO THE OWNER. PROTECT
- IDENTIFY ITEMS TO BE SALVAGED WITH THE OWNER. PROVIDE 4 NON-DESTRUCTIVE REMOVAL OF SYSTEMS, MATERIALS, AND EQUIPMENT FOR REUSE OR SALVAGE AS INDICATED.
- REMOVE ALL COMMUNICATIONS DEBRIS FROM SITE AND 5
- LEGALLY DISPOSE OF IT.
- 6 COORDINATE ALL LOW VOLTAGE DEMO ACTIVITY WITH CONSTRUCTION MANAGER, REVIEW DEMO PHASING PLANS. CONTRACTOR UNDERSTANDS THAT ADJACENT AREAS NEED TO REMAIN IN OPERATION AND THAT SERVICES TO THESE
- AREAS NEED TO BE MAINTAINED. CONTRACTOR SHALL NOTIFY THE OWNER AND CONSULTANT NO LESS THAN THREE DAYS IN ADVANCE BEFORE COMMENCING ANY DEMOLITION TO INSURE THAT NO
- ADJACENT OCCUPIED AREAS WILL BE DISRUPTED. 9 FIRE STOP ANY SLEEVES WHERE CABLES HAVE BEEN REMOVED.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING 10 TELEPHONE, DATA, CENTRAL SOUND, SECURITY CCTV AND ALARM SYSTEM SERVICES IN ALL EXISTING AREAS FOR DURATION OF PROJECT FOR MULTI-PHASED PROJECTS. CONTRACTOR SHALL COLLABORATE WITH OWNER'S TECHNOLOGY PERSONNEL AS NECESSARY AND PROVIDE TEMPORARY WIRING, CROSS-CONNECTS, TERMINATION DEVICES, AND LABOR TO MAINTAIN OPERATION ACCEPTABLE TO THE OWNER. CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR ADDITIONAL INFORMATION RELATED TO

PHASING.

3 AND STORE AS DIRECTED BY THE OWNER.







N-TV

DE

I**|**−TV

\_\_\_\_

ШЧ





\_\_\_\_\_

A.

"HH


 $(\cdot)$ 

D

CLASSROOM

<sup>WAP</sup> 민구

GLASS ROOM




### ) PLAN NOTES:

(ALL NOTES MAY NOT BE USED ON THIS SHEET.)

- 1 NEW TELECOMMUNICATION OUTLET(S) TO BE INSTALLED IN SURFACE RACEWAY WHERE REQUIRED.
- (2) EXISTING CARD READER, TO BE RE-INSTALLED IN NEW DOOR FRAME.
- 3 EXISTING SECURITY CAMERA(S), TO BE RE-INSTALLED IN NEW CEILING.
- (4) AUDIO AND DATA CABLE TO TRAVEL WITH BLEACHERS.
- PROVIDE CONDUIT FOR SPEAKER CABLE. ROUTE FROM SPEAKER TO SOUND CABINET. 6 EXISTING INCOMING WAN FIBER.

TO TR - A-111







UNIT "A" TELECOMMUNICATIONS SECOND FLOOR PLAN SCALE: 3/32 = 1'-0"

### PLAN NOTES:

(ALL NOTES MAY NOT BE USED ON THIS SHEET.)

- NEW TELECOMMUNICATION OUTLET(S) TO BE INSTALLED IN SURFACE RACEWAY WHERE REQUIRED. (1)
- 2 EXISTING CARD READER, TO BE RE-INSTALLED IN NEW DOOR FRAME.
- 3 EXISTING SECURITY CAMERA(S), TO BE RE-INSTALLED IN NEW CEILING.
- (4) AUDIO AND DATA CABLE TO TRAVEL WITH BLEACHERS.
- PROVIDE CONDUIT FOR SPEAKER CABLE. ROUTE FROM SPEAKER TO SOUND CABINET. (5)
- (6) EXISTING INCOMING WAN FIBER.





ш D:\DROPBOX\CROWN\_POINT\_ COMMUNITY\_SCHOOI - MAC ELEMENTRY SCHOOLS\TIMOTHY BALL ELEMENTARY\DRAWINGS\T-DRAWINGS\TBALL T103 TELECOMMUNICATIONS FIRST FLOOR PLAN.DWG

$\bigcirc$	PLAN NOTES:
	(ALL NOTES MAY NOT BE USED ON THIS SHEET.)
1)	NEW TELECOMMUNICATION OUTLET(S) TO BE INSTALL SURFACE RACEWAY WHERE REQUIRED.
2)	EXISTING CARD READER, TO BE RE-INSTALLED IN NEW


(4) AUDIO AND DATA CABLE TO TRAVEL WITH BLEACHERS.

(6) EXISTING INCOMING WAN FIBER.


5 PROVIDE CONDUIT FOR SPEAKER CABLE. ROUTE FROM SPEAKER TO SOUND CABINET.


- 3 EXISTING SECURITY CAMERA(S), TO BE RE-INSTALLED IN NEW CEILING.


- LED IN EW DOOR



C D:\DROPBOX\CROWN\_POINT\_ COMMUNITY\_SCHOOLS\T - MAC ELEMENTRY SCHOOLS\TIMOTHY BALL ELEMENTARY\DRAWINGS\T-DRAWINGS\TBALL T104 UNI TELECOMMUNICATIONS FIRST FLOOR PLAN.DWG










- PLAN NOTES:
- (ALL NOTES MAY NOT BE USED ON THIS SHEET.)
- 1 NEW TELECOMMUNICATION OUTLET(S) TO BE INSTALLED IN SURFACE RACEWAY WHERE REQUIRED.
- 2 EXISTING CARD READER, TO BE RE-INSTALLED IN NEW DOOR FRAME.
- 3 EXISTING SECURITY CAMERA(S), TO BE RE-INSTALLED IN NEW CEILING.
- (4) AUDIO AND DATA CABLE TO TRAVEL WITH BLEACHERS.
- PROVIDE CONDUIT FOR SPEAKER CABLE. ROUTE FROM SPEAKER TO SOUND CABINET. (5)
- 6 EXISTING INCOMING WAN FIBER.

SCALE: 1/8 = 1'-0"








UNIT "D" TELECOMMUNICATIONS FIRST FLOOR PLAN SCALE: 1/8 = 1'-0"

### PLAN NOTES:


- (ALL NOTES MAY NOT BE USED ON THIS SHEET.)
- 1 NEW TELECOMMUNICATION OUTLET(S) TO BE INSTALLED IN SURFACE RACEWAY WHERE REQUIRED.
- 2 EXISTING CARD READER, TO BE RE-INSTALLED IN NEW DOOR FRAME.
- (3) EXISTING SECURITY CAMERA(S), TO BE RE-INSTALLED IN NEW CEILING.
- (4) AUDIO AND DATA CABLE TO TRAVEL WITH BLEACHERS.
- 5 PROVIDE CONDUIT FOR SPEAKER CABLE. ROUTE FROM SPEAKER TO SOUND CABINET.
- 6 EXISTING INCOMING WAN FIBER.



\DROPBOX\CROWN\_POINT\_ OMMUNITY\_SCHOOLS\T-BALL - MAC ELEMENTRY CHOOLS\TIMOTHY BALL ELEMENTARY\DRAWINGS\TB30X CONSULTANT-REVIT.DWG

271513				
PANEL SERVICE OUTLET				
NTS				
WHERE DEVICE IS LOCATED IN A SPECIAL MOUNTING				
ARRANGEMENT SUCH A A FLOORBOX OR TELEPOWER POLE, UTILIZE INTEGRAL	REFERENCE TERMINATION AND COLOR CODING CHART FOR CABLE AND JACK COLORS			
FACEPLATE IN LIEU OF STANDARD SINGLE GANG				
FACEPLATE.				
Ø				
©	©			
	6 6 6			
	Ϋ́́Ϋ́́			
(1) DOUBLE GANG SS FACEPLATE (DEC (2) 4 PORT DECORA STYLE MODULE FF (2) 1 PORT BLANKS				
(6) RJ45 UTP JACK INSERTS; 4 PR UTP	CABLES TO ER/TR			
	SYMBOL SUBSCRIPTS MAY INDICATE A QUANTITY(AS			
	SHOWN OR A #D INDICATING DATA AND #V INDICATING VOICE. THE ADDITION OF TH			
	D AND V CABLES WOULD INDICATE THE TOTAL 4 PAIR			
271513	CABLES TO THE OUTLET.			

REFERENCE TERMINATION AND COLOR CODING CHART FOR CABLE AND JACK COLORS
FACP ELEV BAS
(1) DUAL PORT SURFACE JACK (MOUNTED AS DIRECTED) (1) RJ45 8P 8C MOD JACK; (1) 4 PAIR CABLE TO ER/TR
COORDINATE FINAL TERMINATION WITH EQUIPMENT VENDOR
271513



3 DOUBLE GANG FP 4 NTS

2 DOUBLE GANG FP 2 NTS 1 DOUBLE GANG FP 1 NTS



D:\DROPBOX\CROWN\_POINT COMMUNITY\_SCHOOLS\T-BALL - MAC ELEMENTRY SCHOOLS\TIMOTHY BALL ELEMENTARY\DRAWINGS\TB30X4; - CONSULTANT-REVIT.DWG

