

ADDENDUM NO. 1

April 1, 2024

**TRI-CREEK SCHOOL CORPORATION - HOLTZ ROAD
IMPROVEMENTS
Lowell, IN 46356**

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications, and the Drawings dated March 19, 2024 by Torrenga Engineering. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 1-1 and attached Addendum No. 1 from Torrenga Engineering dated March 28, 2024 and consisting of 1 page and 15 drawings.

A. SPECIFICATION SECTION 0 32 00 - SCHEDULES AND REPORTS

1. Replace:

Guideline Schedule with that attached revised Guideline Schedule

Activity Name	Original Duration	Start	Finish	2024																															
				April				May				June				July				August				September				October				November			
				01	08	15	22	29	06	13	20	27	03	10	17	24	01	08	15	22	29	05	12	19	26	02	09	16	23	30	07	14	21	28	04
Tri-Creek Holtz Road Improvements	92	Apr-09-2024	Aug-16-2024	Tri-Creek Holtz Road Improvements																															
Project Administration	87	Apr-09-2024	Aug-09-2024	Project Administration																															
Bid Opening	0	Apr-09-2024	Apr-09-2024	Bid Opening																															
Recommend/Award	0	Apr-11-2024	Apr-11-2024	Recommend/Award																															
Notice to Proceed	0	Apr-15-2024	Apr-15-2024	Notice to Proceed																															
Procure Submittals	25	Apr-15-2024	May-17-2024	Procure Submittals																															
Start Construction	0	May-09-2024*	May-09-2024	Start Construction																															
Substantial Completion	0	Aug-01-2024*	Aug-01-2024	Substantial Completion																															
Punchlist	7	Aug-01-2024	Aug-09-2024	Punchlist																															
Final Completion	0	Aug-09-2024*	Aug-09-2024	Final Completion																															
Site Work	70	May-09-2024	Aug-16-2024	Site Work																															
Mobilize	5	May-09-2024	May-15-2024	Mobilize																															
Erosion Control	5	May-16-2024	May-22-2024	Erosion Control																															
Utilities	10	May-23-2024	Jun-06-2024	Utilities																															
Strip & Store Topsoil	5	Jun-07-2024	Jun-13-2024	Strip & Store Topsoil																															
Excavate and Stockpile Subsoil	5	Jun-14-2024	Jun-20-2024	Excavate and Stockpile Subsoil																															
Grade and Rough Contour Site	10	Jun-21-2024	Jul-05-2024	Grade and Rough Contour Site																															
Concrete Curbs and Walks	10	Jul-08-2024	Jul-19-2024	Concrete Curbs and Walks																															
Asphalt Paving	5	Jul-22-2024	Jul-26-2024	Asphalt Paving																															
Striping/Painting	5	Jul-29-2024	Aug-02-2024	Striping/Painting																															
Landscaping	5	Aug-05-2024	Aug-09-2024	Landscaping																															
Site Equipment	5	Aug-12-2024	Aug-16-2024	Site Equipment																															
<div><div></div> Actual Work</div> <div><div></div> Remaining Work</div> <div><div></div> Critical Remaining Work</div> <div><div></div> Milestone</div> <div><div></div> Summary</div>		222100.09 Tri-Creek Holtz Road Improvements																				<div>SKILLMAN</div>													
		Guideline Schedule (ADD 1) Apr-09-2024																																	
		1 of 1																																	

Torrenga Engineering, Inc.

REGISTERED PROFESSIONAL ENGINEERS

907 Ridge Road
Munster, IN 46321
Phone 219.836.8918
www.torrenga.com
March 28, 2024
Page 1

PROJECT: <u>Addendum One</u>	1. Addendum One Holtz Road Improvements Lowell, Indiana Torrenga Project No.: 2023-5056
CONTRACT NO.:	2023-5056
SPEC SECTION:	
SHEET NO.:	C-2.1, C-2.2, C-2.2, & C-4.0

1. Sheet C-2.1 IMPROVEMENT PLAN

- 1" Pavement Resurfacing is revised to 1.5" Pavement Resurfacing

2. Sheet C-2.2 IMPROVEMENT PLAN

- 1" Pavement Resurfacing is revised to 1.5" Pavement Resurfacing

3. Sheet C-2.3 IMPROVEMENT PLAN

- 1" Pavement Resurfacing is revised to 1.5" Pavement Resurfacing


4. Sheet C-4.0 DETAILS & SPECIFICATIONS

- Milling Detail and Typical Pavement Resurfacing are added.

interoffice memorandum

FINAL ENGINEERING PLANS
HOLTZ ROAD IMPROVEMENTS, LOWELL, INDIANA

INDEX
PAGE DESCRIPTION
COVER TITLE PAGE
C-1.0 TOPOGRAPHY & EXISTING CONDITIONS
C-1.1 DEMOLITION PLAN
C-2.0 OVERALL PLAN & TYPICAL CROSS SECTIONS (1"=60')
C-2.1 TO C-2.3 IMPROVEMENT PLAN (1" = 20')
C-3.1 TO C-3.3 PAVEMENT MARKING PLAN & PROFILE
C-3.4 TO C-3.5 CROSS SECTIONS
C-4.0 DETAILS & SPECIFICATIONS
C-5.0 STORM WATER POLLUTION PREVENTION PLAN
C-5.1 STORM WATER POLLUTION PREVENTION PLAN DETAILS



"IT'S THE LAW"
CALL 2 WORKING DAYS BEFORE YOU DIG
811 or 1-800-382-5544
CALL TOLL FREE
PER INDIANA STATE LAW IC8-1-26, IT IS AGAINST THE LAW TO EXCAVATE WITHOUT NOTIFYING THE UNDERGROUND LOCATION SERVICE TWO (2) WORKING DAYS BEFORE COMMENCING WORK.

CLIENT/OWNER:

Client/Owner:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, IN 46356
(219)696-6661

PREPARED BY:

Torrenge Engineering, Inc.
907 Ridge Road
Munster, Indiana 46321
(219)836-8918

BENCHMARKS:

TBM #1
EXISTING NORTH RIM OF INLET LOCATED AT STATION 12+47, 39 FT LEFT, ELEVATION = 696.61

TBM #2
EXISTING NORTH RIM OF SANITARY MANHOLE LOCATED AT STATION 13+25, 25 FT LEFT, ELEVATION = 697.47

ALL VERTICAL DATUM IS BASED ON NAVD 88

NOTES:

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE FOLLOWING, EXCEPT AS MODIFIED HERIN OR ON THE PLANS:

-STANDARD SPECIFICATIONS, INDIANA DEPARTMENT OF TRANSPORTAION, LATEST EDITION, (INDOT SS) FOR ALLIMPROVEMENTS.

-INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT REGULATIONS


-TOWN OF LOWELL, INDIANA MUNICIPAL REGULATIONS AND STANDARDS

IN CASE OF CONFLICTS BETWEEN THE APPLICABLE ORDINANCES NOTED, THE MORE STRINGENT SHALL TAKE PRECEDENCE AND SHALL CONTROL ALL CONSTRUCTION.

DRAINAGE CERTIFICATION

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE AND BELIEF, THE DRAINAGE OF SURFACE WATERS WILL NOT BE CHANGED BY THE CONSTRUCTION OF SAID IMPROVEMENTS OR ANY PART THEREOF, OR, THAT IF SUCH SURFACE WATER DRAINAGE WILL BE CHANGED, REASONABLE PROVISION HAS BEEN MADE FOR COLLECTION AND DIVERSION OF SUCH SURFACE WATERS INTO PUBLIC AREA, OR DRAINS WHICH THE OWNER HAS A RIGHT TO USE AND THAT SUCH SURFACE WATERS WILL BE PLANNED FOR IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES SO AS TO REDUCE THE LIKELIHOOD OF DAMAGE TO THE ADJOINING PROPERTIES BECAUSE OF THE CONSTRUCTION OF THE IMPROVEMENTS.

CERTIFIED BY: DONALD C. TORRENGA
P.E. # 19868




Donald C. Torrenge

County: Lake
SE 1/4, Sec. 24, T. 33 N. R. 9 W.
Township: LOWELL-CEDAR CREEK

Table with 4 columns: NO., DATE, DESCRIPTION, BY. Row 1: 1, 03-11-2024, PRIMARY SUBMITTAL, DT/NM/MEM.

DRAWING SET PROGRESS:
[] ENGINEERING PLAN - FOR REVIEW / APPROVAL
[X] FINAL ENGINEERING - FOR CONSTRUCTION

FILE NO:Z\2023-5013 Lowell High School - Lowell\dwg\Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT




NOTES:

- TBM #1 - NORTH RIM OF EXISTING OPEN GRATE MANHOLE @ STATION 5+96, 35' RT, ELEVATION = 694.41
- TBM #2 - NORTHWEST CORNER OF CONCRETE PAD FOR ELECTRIC @ STATION 16+82, 35' RT, ELEVATION = 698.75
- TBM #3 - NORTH RIM OF EXISTING OPEN GRATE MANHOLE @ STATION 11+43, 42' LT, ELEVATION = 695.83

LEGEND:

- EXISTING
- MANHOLE
 - CATCH BASIN/INLET
 - REARYARD DRAIN
 - CURB DRAIN
 - FIBER OPTIC MANHOLE
 - TRAFFIC LIGHT POLE
 - TRAFFIC MANHOLE
 - LIGHT POLE
 - POWER POLE
 - GUY WIRE/GUY POLE
 - TELEPHONE PEDESTAL
 - CABLE TV PEDESTAL
 - WATER VALVE
 - FIRE HYDRANT
 - B-BOX
 - SIGN or BILLBOARD
 - STOP SIGN
 - CLEAN OUT
 - STEEL BOLLARD
 - PIPE INLET/OUTLET
 - DRAIN
 - ELECTRIC TRANSFORMER
 - ELECTRIC OUTLET
 - ELECTRIC PANEL/BOX
 - ELECTRIC MANHOLE
 - FOUND ROW MARKER
 - SUPPORT COLUMN
 - INTERCOM
 - I BEAM
 - FOUL POLE
 - UTILITY STUB
 - PIPELINE MARKER
 - TELEPHONE MANHOLE
 - GROUND LIGHT
 - GAS VALVE
 - LIGHTING MANHOLE
 - MONITORING WELL
 - OVERHEAD LINES
 - WATER LINE PAINTED/FLAGGED (BLUE)
 - ELEC. LINE PAINTED/FLAGGED (RED)
 - COMMUNICATION/FIBER OPTIC LINE PAINTED/FLAGGED (ORANGE)
 - GAS LINE PAINTED/FLAGGED (YELLOW)
 - SEWER LINE PAINTED/FLAGGED (GREEN)
 - WOOD FENCE
 - CHAINLINK FENCE
 - HAND/GUARD RAIL
 - SANITARY SEWER
 - STORM SEWER
 - WATER MAIN
 - RIGHT-OF-WAY LINE
 - PROPERTY LINE



CLIENT: Tri-Creek School Corporation 19290 Cline Avenue Lowell, Indiana 46356	
JOB NO: 2023-5056	
SCALE: 1" = 60'	
REVISIONS:	
DATE: 03-11-2024	



HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA

TOPOGRAPHY & EXISTING CONDITION

TORRENGA ENGINEERING, INC.


CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918 website: www.torrengea.com



SHEET


C-1.0



- NOTES:
1. THE CONTRACTOR IS RESPONSIBLE TO VERIFY ALL EXISTING SITE CONDITIONS AND SHALL NOTIFY THE ARCHITECT/ENGINEER IMMEDIATELY OF ANY DISCREPANCIES BETWEEN THE EXISTING CONDITIONS AND ALL PROPOSED IMPROVEMENTS IN THE CONSTRUCTION DRAWINGS.
 2. THE CONTRACTOR IS RESPONSIBLE FOR THE RELOCATION OF ANY MAILBOXES THAT ARE LOCATED IN THE EXPANDED ROADWAY.
 3. THE RE-LOCATION OF THE EXISTING TELEPHONE BOXES AND THE POWER POLES WITH OVERHEAD LINES SHALL BE COORDINATED BY THE CONTRACTOR WITH THE APPROPRIATE UTILITY COMPANIES.



- DEMOLITION NOTES
- | | |
|---|---|
| 1 | REMOVE ASPHALT PAVEMENT |
| 2 | REMOVE CONCRETE CURB |
| 3 | REMOVE STORM SEWER & END SECTION |
| 4 | REMOVE/RELOCATE POWER POLE/LIGHT POLE AND ITS ENTIRETY COORDIANTE WITH NIPSCO |
| 5 | REMOVE/RELOCATE TELEPHONE PEDESTAL, COORDIANTE WITH AT&T |
| 6 | REMOVE TREE |



CLIENT:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056

SCALE: 1" = 60'

REVISIONS:
DATE: 03-11-2024

HOLTZ ROAD – IMPROVEMENTS
LOWELL, INDIANA


DEMOLITION PLAN

TORRENGA ENGINEERING, INC.


CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918

website: www.torrengea.com





Donald C. Torrenge



SHEET

C-1.1

FILE NO: Z:\2023-5013 Lowell High School - Lowell\dwg\Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT



CLIENT:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056

SCALE: 1" = 20'

03-28-2024 AD-1

REVISIONS:

DATE: 03-11-2024

HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA


IMPROVEMENT PLAN

TORRENGA ENGINEERING, INC.

CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918

website: www.torrenza.com



SHEET

C-2.1

2' WIDE X 6" DEEP STONE SHOULDER



5' WIDE CONCRETE SIDEWALK

TYPICAL PAVEMENT SECTION (SEE DETAIL)

TACK COAT AND 1.5" PAVEMENT RESURFACING


STATION 5+35 TO 17+36

AD-1



03-28-2024	AD-1
REVISIONS:	
DATE: 03-11-2024	


TORRENGA ENGINEERING, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321
Tel. No.: (219) 836-8918 website: www.torrennga.com



SHEET

-2.2





FILE NO: Z:\2023-5013 Lowell High School - Lowell\dwg\Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT




Owner:
Novak, Kenneth W & Cathrine L
Novak Living Trust dtd 11/20/15
(Kenneth W & Cathrine L Novak RL)

Owner:
Speedway SuperAmerica, LLC

LEGEND PROPOSED

-  2' WIDE X 6" DEEP STONE SHOULDER
-  5' WIDE CONCRETE SIDEWALK
-  TYPICAL PAVEMENT SECTION (SEE DETAIL)
-  TACK COAT AND 1.5" PAVEMENT RESURFACING
STATION 5+35 TO 17+36

AD-1



CLIENT:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056

SCALE: 1" = 20'

03-28-2024 AD-1

REVISIONS:

DATE: 03-11-2024

HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA


IMPROVEMENT PLAN

TORRENGA ENGINEERING, INC.


CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918

website: www.torrenge.com




Donald C. Torrenge



SHEET

C-2.3





FILE NO: Z:\2023-5013 Lowell High School - Lowell\dwg\Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT




Owner:
Novak, Kenneth W & Cathrine L
Novak Living Trust dtd 11/20/15
(Kenneth W & Cathrine L Novak RL)

Owner:
Speedway SuperAmerica, LLC

LEGEND PROPOSED

-  2' WIDE X 6" DEEP STONE SHOULDER
-  5' WIDE CONCRETE SIDEWALK
-  TYPICAL PAVEMENT SECTION (SEE DETAIL)
-  TACK COAT AND 1" PAVEMENT RESURFACING STATION 5+35 TO 17+36




CLIENT: Tri-Creek School Corporation 19290 Cline Avenue Lowell, Indiana 46356	REVISIONS:	
	DATE: 03-11-2024	
	SCALE: 1" = 20'	

HOLTZ ROAD – IMPROVEMENTS
LOWELL, INDIANA


IMPROVEMENT PLAN

TORRENGA ENGINEERING, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321
Tel. No.: (219) 836-8918 website: www.torrenge.com




SHEET




C-2.3



FILE NO: Z:\2023-5013 Lowell High School - Lowell\dwg Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT



FILE NO: Z:\2023-2013 Lowell High School - Lowell\dwg\Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT



CLIENT:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056

SCALE: 1" = 20'

REVISIONS:

DATE: 03-11-2024

HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA


PAVEMENT MARKING PLAN & STREET PROFILE

TORRENGA ENGINEERING, INC.

CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918




website: www.torrengea.com



SHEET





C-3.3





-3.4

FILE NO:Z:\2023-5013 Lowell High School - Lowell\dwg\Holtz Road - Cross-Section.dwg 12/8/2023 2:38:57 PM CST



CLIENT:
Tri-Creek School Corporation
19290 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056
SCALE: 1" = 10'

REVISIONS:
DATE: 03-11-2024

HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA


CROSS SECTIONS

TORRENGA ENGINEERING, INC.

CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321

Tel. No.: (219) 836-8918


website: www.torrenge.com




SHEET

C-3.5


Dimensions							
Dia.	T (mm)	A	C	D	E	K	R 2
12"	2"	5"	4"-3"	6"-2"	2'-0"	1.3	9"
15"	2-1/4"	7"	4"-0"	6"-3"	2'-6"	1.5	11"
18"	2-1/2"	11"	4"-1"	6"-2"	3'-0"	1.8	12"
21"	2-3/4"	11"	3"-6"	6"-3"	3'-6"	2.1	13"
24"	3"	1'-0"	2'-8"	3"-3"	4'-0"	2.3	14"
27"	3-1/4"	1'-1"	2'-5"	6"-3"	4'-6"	2.6	14-1/2"
30"	3-1/2"	1'-2"	1'-10"	6"-3"	5'-0"	2.9	15"
33"	3-3/4"	1'-3"	3'-6"	6"-3"	5'-6"	3.1	15-1/2"
36"	4"	1'-5"	3'-1"	8'-3"	6'-0"	3.4	20"




PRECAST CONCRETE END SECTION
NOT TO SCALE



PLAN VIEW



SECTION A-A




NOTE:

1. ALL REGULATORY SIGNS SHALL BE HIGH INTENSITY AND IN ACCORDANCE WITH THE INDIANA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, MOST RECENT EDITION.
2. ALL PAVEMENT MARKINGS SHALL BE WHITE THERMOPLASTIC AND SPAN ACROSS APPROACH LANES.

CONTINENTAL CROSS WALK DETAIL

NOT TO SCALE




NOTES:

1. WHERE FILL IS REQUIRED, SUBGRADE SHALL BE COMPACTED TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D698 METHOD OF TESTING.


TYPICAL PAVEMENT X-SECTION
NOT TO SCALE

NOT TO SCALE




BARRIER CURB DETAIL


NOT TO SCALE



JOINT DETAIL




DEWALK PLAN



SECTION A-A


TYPICAL SIDEWALK DETAIL


NOT TO SCALE




NOTES:

1. The top part of the word **ONLY** shall be placed prior to the lane indication arrow, 32 ft for posted speeds ≤ 45 mph but not more than 80 ft for posted speeds > 45 mph.
2. Each letter is 1'-4" wide. Vertical line segments within each letter are 4" wide. Spaces between vertical line segments are 4".
3. The grid lines are 4 in. apart.

INDIANA DEPARTMENT OF TRANSPORTATION	
TRANSVERSE MARKINGS WORD MESSAGES "ONLY" AND "X-ING" SEPTEMBER 2015	
STANDARD DRAWING NO. E 808-MKPM-03	
	<i>/s/ David H. Boruff</i> 03/04/15 DESIGN STANDARDS ENGINEER DATE <i>/s/ Mark A. Miller</i> 03/06/15 CHIEF ENGINEER DATE




LEFT/THRU ARROW




LEFT ONLY ARROW ⁽³⁾


NOTES:

- ① The tip of the lane indication arrow closest to the stop line shall be 20 ft in advance of the nearest edge of the stop line.
2. The grid lines are 4 in. apart.
- ③ Reverse the dimensions of the left arrow for a right/thru or right only arrow.


INDIANA DEPARTMENT OF TRANSPORTATION		
<p align="center">TRANSVERSE MARKINGS TURN ARROWS</p> <p align="center">SEPTEMBER 2015</p>		
STANDARD DRAWING NO.		E 808-MKPM-02
	<i>/s/ David H. Boruff</i>	<i>03/04/15</i>
	DESIGN STANDARDS ENGINEER	DATE
	<i>/s/ Mark A. Miller</i>	<i>03/06/15</i>
	CHEEP ENGINEER	DATE



STANDARD DETAILS PIPE BEDDING		DATE 01/21/15
		DRAWING No. 400-5



FILE NO:Z:\2023-5013 Lowell High School - Lowell\dwg Holtz Road (3).dwg 3/11/2024 1:28:02 PM CDT




- GENERAL NOTES:**
- THIS PROPERTY IS LOCATED IN FLOOD ZONE(S) "A" & "X (UNSHADED)" AS DETERMINED BY USING SCALE MEASUREMENT FOR LOCATION UPON THE APPLICABLE FLOOD INSURANCE RATE MAP FOR THE TOWN OF LOWELL AND UNINCORPORATED AREAS, LAKE COUNTY, INDIANA AS SHOWN IN COMMUNITY PANEL(S) 180880342Z. EFFECTIVE JANUARY 18, 2012. TRACTS OF LAND LOCATED IN FLOOD ZONE "A" ARE IN A SPECIAL FLOOD HAZARD AREA SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD. THE 1% ANNUAL CHANCE FLOOD (100 YEAR FLOOD), ALSO KNOWN AS THE BASE FLOOD, IS THE FLOOD THAT HAS A 1% CHANCE OF BEING EQUALED OR EXCEEDED IN ANY GIVEN YEAR. THIS SPECIAL FLOOD HAZARD AREA IS THE AREA SUBJECT TO FLOODING BY THE 1% ANNUAL CHANCE FLOOD. THE BASE FLOOD ELEVATION IS THE WATER-SURFACE ELEVATION OF THE 1% ANNUAL CHANCE FLOOD. IN A FLOOD ZONE "A", THE BASE FLOOD ELEVATIONS HAVE NOT BEEN DETERMINED. TRACTS OF LAND LOCATED IN FLOOD ZONE X (UNSHADED) ARE AREAS DETERMINED TO BE OUTSIDE OF THE 0.2% ANNUAL CHANCE FLOOD HAZARD.
 - HYDROLOGIC UNIT CODE (HUC) - 07120001130040 SPRING RUN
 - AN IDEM CONSTRUCTION STORMWATER GENERAL PERMIT (CSGP) IS REQUIRED.
 - AT PRESENT THE SITE IS AN EXISTING SCHOOL WITH SURROUNDING PARKING AREAS, PONDS AND SPORTS FIELDS.
 - THERE IS PRESENCE OF HYDRIC SOILS ON THIS PROPERTY, (PC) PEWAMO SILTY CLAY LOAM.
 - THERE ARE NO EXISTING WETLAND AREAS ON THIS PROPERTY BUT DO EXIST ON ADJACENT PROPERTY AS CLASSIFIED BY THE U.S. FISH AND WILDLIFE SERVICE, NATIONAL WETLANDS INVENTORY, AND THE UNITED STATES DEPARTMENT OF THE INTERIOR. THERE ARE NO LAKES OR WATER COURSES BUT A DETENTION POND DOES EXIST ON THIS PROPERTY. SPRING RUN IS THE WATER COURSE WHICH THE STORMWATER FROM THE REST OF THE PROPOSED SITE WILL ULTIMATELY DISCHARGE INTO. A TRIBUTARY OF WHICH IS LOCATED APPROXIMATELY 2,000 FT EAST OF THE PROJECT SITE.
 - POTENTIAL SOURCE OF STORM WATER DISCHARGE ENTERING THE GROUNDWATER FROM THIS DEVELOPMENT WILL BE THROUGH NATURAL GROUND ABSORPTION ONLY. THERE ARE NO ABANDONED WELLS OR SINKHOLES ON THE PROPERTY.
 - THERE ARE NO SENSITIVE AREAS ASSOCIATED WITH THIS PROPERTY.
 - THERE ARE NO REGULATED DRAINS WITHIN THIS PROPERTY, OR ON ADJACENT PROPERTIES. THERE IS NO RECORD OR KNOWLEDGE OF EXISTING FARM DRAINS OR FIELD TILE, INLETS AND OUTFALLS LOCATED WITHIN THE EXISTING PROJECT LIMITS.
 - SOIL STOCKPILES, BORROW AND DISPOSAL AREAS ARE LOCATED WITHIN THE PROJECT SITE. SOIL STOCKPILES SHALL BE SURROUNDED WITH SILT FENCING AT ALL TIMES TO PREVENT EXCESSIVE EROSION, AND IF LEFT UNDISTURBED FOR A PERIOD OF MORE THAN 7 DAYS, IT SHALL BE TEMPORARILY SEEDED WITHIN 14 DAYS. UPON SITE COMPLETION THE TOPSOIL STOCKPILE SHALL BE RESPREAD, GRADED, AND PERMANENTLY SEEDED. SOIL STOCKPILES SHALL NOT BE LEFT ON THE SITE FOR GREATER THAN 6 MONTHS AFTER CONSTRUCTION IS COMPLETED. NO SOIL FROM THE STOCKPILES SHALL BE REMOVED FROM THE SITE. ALL EXTRA STOCKPILE MATERIAL SHALL BE RESPREAD IN AREAS DESIGNATED BY THE CONSTRUCTION MATERIAL.
 - AREAS WHERE THE PROPOSED ROAD WIDENING AND SIDEWALKS AS WELL AS AREAS WHERE PROPOSED UTILITIES ARE LOCATED WILL BE DISTURBED DURING CONSTRUCTION. IN ALL OTHER AREAS, EXISTING VEGETATIVE COVER WILL BE PRESERVED.
 - FUEL STORAGE AREA IF REQUIRED SHALL BE WITHIN THE CONSTRUCTION STAGING AREA. FUEL SHALL BE STORED IN APPROVED MOBILE REFUELING TANK LOCATED AWAY FROM DRAINAGE STRUCTURES AND CHANNELS. FIRE EXTINGUISHERS SHALL BE LOCATED NEAR FUEL STORAGE AREA AND BE OF SUITABLE TYPE, POSTED, AND BE MAINTAINED IN GOOD CONDITION.
 - TEMPORARILY SEED ALL AREAS OF BARE SOIL (WITH THE ADDITION OF A BLANKET WHERE SLOPES ARE 4:1 OR GREATER) THAT WILL REMAIN UNDISTURBED FOR A PERIOD OF MORE THAN 7 DAYS, WITHIN 14 DAYS. SEEDING: OPTIMUM SEEDING DATES ARE MARCH 1 - MAY 10 AND AUGUST 10 - SEPTEMBER 30. SEEDING DATES BETWEEN MAY 10 AND AUGUST 10, MAY NEED TO BE IRRIGATED. FOR SEEDING RECOMMENDATIONS SEE PRACTICE 3.12, INDIANA STORM WATER QUALITY MANUAL.
 - ALL SOIL STOCKPILES, AREAS THAT ARE DISTURBED DURING CONSTRUCTION, AND DRAINAGE SWALES WHICH ARE SCHEDULED OR LIKELY TO BE LEFT INACTIVE FOR SEVEN (7) CALENDAR DAYS OR MORE MUST BE TEMPORARILY OR PERMANENTLY SEEDED WITH MEASURES APPROPRIATE FOR THE SEASON WITHIN FOURTEEN (14) DAYS.
 - SITE ELEVATIONS ARE BASED ON NAVD 88, AND HORIZONTAL DATUM IS BASED ON INDIANA STATE PLANE COORDINATES NAD 83.


NOTES:
1. FOR POST-CONSTRUCTION STORM WATER POLLUTION PREVENTION, TEMPORARY SEEDING LOCATIONS SHALL BE PERMANENTLY SEEDED.

SWPPP LEGEND:


- BASKET INSERT INLET
- PROTECTION
- GRADE LIMITS
- SILT FENCE
- CONCRETE WASH OUT AREA
- TEMPORARY SEEDING
- STREET SWEEPING
- GRADES (PROPOSED)
- ROCK CHUTE
- POSTING CSGP NOI & NOS LETTERS AND LOCAL SWPPP PERMIT
- EROSION CONTROL BLANKET (NORTH AMERICAN GREEN OR APPROVED EQUAL) TO BE INSTALLED ON ALL DISTURBED GRASS AREAS



VICINITY MAP
NOT TO SCALE




WETLANDS MAP
NOT TO SCALE



SOIL MAP
NOT TO SCALE

Soil Type Legend
BIA - Blount silt loam, Lake Michigan Lobe, 0 to 2 percent slopes
EI - Elliott silt loam, 0 to 2 percent slopes
OzIC3 - Ozaukee silty clay loam, 6 to 12 percent slopes, severely eroded
OzaB - Ozaukee silt loam, 2 to 6 percent slopes
Pc - Pewamo silty clay loam



CLIENT:
Tri-Creek School Corporation
19230 Cline Avenue
Lowell, Indiana 46356

JOB NO: 2023-5056


SCALE: 1" = 60'

REVISIONS:
DATE: 12-xx-2023


**HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA**

STORM WATER POLLUTION PREVENTION PLAN

TORRENGA ENGINEERING, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321
Tel. No.: (219) 836-8918 website: www.torrengea.com



SHEET
C-5.0



FILE NO:Z:\2023-5013 Lowell High School - Lowell\dwg\HOLTZ ROAD SWPPP Details.dwg 3/11/2024 3:15:16 PM CDT

CONCRETE WASHOUT

Purpose: To reduce the discharge of pollutants associated with concrete wash through consolidation of solids and retention of liquids.


- Requirements:**
1. Locate concrete washout systems at least 50 feet from any creeks, wetlands, ditches, karst features, or storm drains/manned conveyance systems.
 2. Locate concrete washout systems in relatively flat areas with established vegetative cover and do not receive runoff from adjacent land areas.
 3. Locate in areas that provide easy access for concrete trucks and other construction equipment.
 4. Locate away from other construction traffic to reduce the potential for damage to the system.
 5. Minimum of ten millimeter polyethylene sheeting that is free of holes, tears, and other defects. The sheeting selected should be of an appropriate size to fit the washout system without seams or overlap of the lining.
 6. Signage.
 7. Orange safety fencing or equivalent.
 8. Straw bales, sandbags (bags should be ultraviolet-stabilized geotextile fabric), soil material, or other appropriate materials that can be used to construct a containment system (above grade systems).

- Installation:**
1. Dependent upon the type of system, either excavate the pit or install the containment system.
 2. A base shall be constructed and prepared that is free of rocks and other debris that may cause tears or punctures in the polyethylene lining.
 3. Install the polyethylene lining. For excavated systems, the lining should extend over the entire excavation. The lining for bermed systems should be installed over the pooling area with enough material to extend the lining over the berm or containment system. The lining should be secured with pins, staples, or other fasteners.
 4. Place flags, safety fencing, or equivalent to provide a barrier to construction equipment and other traffic.
 5. Place a non-collapsing, non-water holding cover over the washout facility prior to a predicted rainfall event to prevent accumulation of water and possible overflow of the system (optional).
 6. Install signage that identifies concrete washout areas.
 7. Post signs directing contractors and suppliers to designated locations.

- Maintenance:**
1. Inspect daily and after each storm event.
 2. Inspect the integrity of the overall structure including, where applicable, the containment system.
 3. Inspect the system for leaks, spills, and tracking of soil by equipment.
 4. Inspect the polyethylene lining for failure, including tears and punctures.
 5. Once concrete wastes harden, remove and dispose of the material.
 6. Excess concrete should be removed when the washout system reaches 50 percent of the design capacity. Use of the system should be discontinued until appropriate measures can be initiated to clean the structure. Prefabricated systems should also utilize this criterion, unless the manufacturer has alternate specifications.
 7. Upon removal of the solids, inspect the structure. Repair the structure as needed or construct a new system.
 8. Dispose of all concrete in a legal manner. Reuse the material on site, recycle, or haul the material to an approved construction/demolition landfill site. Recycling of material is encouraged. The waste material can be used for multiple applications including but not limited to roadbeds and building. The availability for recycling should be checked locally.
 9. The plastic liner should be replaced after every cleaning; the removal of material will usually damage the lining.
 10. The concrete washout system should be repaired or enlarged as necessary to maintain capacity for concrete waste.
 11. Concrete washout systems are designed to promote evaporation. However, if the liquids do not evaporate and the system is near capacity it may be necessary to vacuum or remove the liquids and dispose of them in an acceptable method. Disposal may be allowed at the local sanitary sewer authority provided their National Pollutant Discharge Elimination System permits allow for acceptance of this material. Another option would be to utilize a secondary containment system or basin for further dewatering.
 12. Prefabricated units are often pumped and the company supplying the unit provides this service.
 13. Inspect construction activities on a regular basis to ensure suppliers, contractors, and others are utilizing designated washout areas. If concrete waste is being disposed of improperly, identify the violators and take appropriate action.
 14. When concrete washout systems are no longer required, the concrete washout systems shall be closed. Dispose of all hardened concrete and other materials used to construct the system.
 15. Holes, depressions and other land disturbances associated with the system should be backfilled, graded, and stabilized.


CONCRETE WASHOUT

Concrete Washout (Above Grade System) Worksheet



CONCRETE WASHOUT

Concrete Washout (Below Grade System) Worksheet





SILT FENCE

Purpose: To retain sediment from small sloping disturbed areas by reducing the velocity of sheet flow.

- Requirements:**
- Trench:** 8" minimum depth, flat bottom or v-shaped, filled with compacted soil or gravel to bury lower portion of support wire and/or fence fabric.
- Support posts:** 2" x 2" hardwood posts set at least 1 foot deep.
- Spacing of Posts:** 8-foot maximum if fence supported by wire, otherwise 6 foot for extra strength fabric without wire backing.
- Fence height:** A 3 feet minimum or high enough so depth of impounded water does not exceed 1.5 feet at any point along fence line.
- Support wire :** 14 gauge, 6" mesh wire fence. (needed if using standard-strength fabric (optional))
- Fence Fabric:** Woven or non-woven Geotextile fabric with specified filtering efficiency and tensile strength and containing UV inhibitors and stabilizers to ensure 6 months minimum life at temperatures 0-120 degrees F.

- Installation:**
1. Along the entire intended fence line, maintain contour as much as possible, dig an 8" deep flat bottom or v-shaped trench.
 2. On the downslope side of the trench, drive the post at least 1 foot into the ground. (Note: If the fence has pre-attached posts or stakes, drive them deep enough so the fabric is satisfactorily in the trench per step 6)
 3. Fasten support wire fence to the upslope side of the posts, extending it 8" into trench. (use only if required by manufacturer)
 4. Run a continuous length of Geotextile fabric along upslope side of posts.
 5. If a joint is necessary, nail the overlap to the nearest post with a wood nail.
 6. Place the bottom 1' of fabric in the 8" deep trench, extending the remaining 4" of fabric toward the upslope side.
 7. Backfill the trench with compacted earth.

- Maintenance:**
1. Inspect silt fence periodically and after each storm event.
 2. If fence fabric tears, starts to decompose, or becomes ineffective, replace the affected portion.
 3. Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.
 4. Take care to avoid undermining the fence during clean out.
 5. After watershed has been stabilized, remove fence and sediment deposits, bring the disturbed area to grade and stabilize.



STREET AND PARKING LOT SWEEPING

Purpose: To reduce the amount of pollutants that get washed into the storm drain and ultimately transported and deposited in waterbodies.

- Application:**
1. Sweeping at points of egress where sediment is tracked from project site onto public or private streets and roads.

- Limitations:**
1. Sweeping may be ineffective if soil is wet or heavy accumulation of mud.
 2. May require repeat cleanings.

- Maintenance:**
1. Inspect potential sediment tracking ingress and egress points locations daily, and after rain events.
 2. Visible sediment observed outside the construction limits shall be swept and removed daily.
 3. Do not use kick brooms or sweeper attachments. These tend to spread the dirt rather than remove it.
 4. If not mixed with debris or trash, consider incorporating the removed sediment back into the project.
 5. Be careful not to sweep up any unknown substance or any object that may be potentially hazardous.
 6. Adjust brooms frequently; maximize efficiency of sweeping operations.
 7. After sweeping is finished, properly dispose of sweeper wastes at an approved dumpster.

TEMPORARY SEEDING

Purpose: To stabilize disturbed areas especially along both sides of the streets and courts after final grading work is completed and where additional work is not scheduled.

Requirements: Site and seedbed preparation: Graded, and lime and fertilizer applied

Seed Selected: Selected on the basis of quick germination, growth, and time of year. See Table for temporary seeding recommendations.

Fertilizer: According to soil test or use 600 lbs/acre 12-12-12 analysis, or equivalent.

Mulch: 1.5 - 2 tons/acre straw. Straw must be dry, unchopped and free of undesirable seeds.

- Application:**
1. Fertilize and lime as recommended by the soil test.
 2. Till the soil to obtain a uniform seedbed, working the fertilizer and lime into the soil 2-4" deep with a disk or rake operated across the slope.
 3. Apply seed uniformly with a drill or cultipacker sower, or by broadcasting, and cover to a depth as shown on Table for temporary seeding recommendations.
 4. If drilling or broadcasting, firm the seedbed with a roller or cultipacker.
 5. Mulch all seeded areas. (Note: If seeding is done with a hydroseeder, fertilizer and mulch can be applied with the seed in a slurry mixture.)

- Maintenance:**
1. Inspect periodically after planting to see that vegetative stands are adequately established; re-seed if necessary.
 2. Check for erosion damage after storm events and repair; re-seed and mulch if necessary.

- Notes:**
1. Vegetative Filter Strip: permanent or temporary, shall be done on all disturbed areas along both sides of the streets and courts to reduce erosion where additional work is not scheduled.
 2. Permanent Seeding: or sodding shall be done at the time of final landscaping.

Table 1. Temporary Seeding Specifications

Seed Species	Rate per Acre	Planting Depth	Optimum Dates
Wheat or Rye	150 lbs.	1 to 1 1/2 inches	Sept. 15 - Oct. 30
Spring Cereals	180 lbs.	1 inch	March 1 - April 15
Annual Ryegrass	40 lbs.	3/4 inch	March 1 - May 1 Aug. 1 - Sept. 1
German Millet	40 lbs.	1 to 2 inches	May 1 - June 1
Sudangrass	35 lbs.	1 to 2 inches	May 1 - July 30
Buckwheat	60 lbs.	1 to 2 inches	April 15 - June 1
Corn (annual)	300 lbs.	1 to 2 inches	May 11 - Aug. 10
Sorghum	35 lbs.	1 to 2 inches	May 1 - July 15

*Perennial species may be used as a temporary cover, especially if the area to be seeded will remain idle for more than one year (see Permanent Seeding on page 35).

†Seeding done outside the optimum seeding dates increases the chances of seeding failure. Dates may be extended or shortened based on the location of the project site within the state.

ROCK CHUTE

Purpose: To protect slopes, stream banks and channels, which are subject to erosion. Where run off velocity is great, at the outlet pipe of a detention basin, channel or culvert.

Requirements: Rock: Hard angular, weather-resistant and well graded stone, the largest pieces should not exceed two times the specified stone diameter.

Thickness: 12" minimum or two times the specified stone diameter, which ever is greater.

Filter: Under permanent riprap install geotextile fabric for stabilization and filtration


- Installation:**
- Subgrade Replacement:
1. Remove brush, trees, stumps, and other debris.
 2. Excavate only deep enough for both filter and riprap.

- Filter Placement:
1. Place geotextile fabric on a smoothed foundation, overlap the edges at least 12 inches and secure with anchor pins spaced every 3 feet along the overlap.
 2. If fabric is damaged, remove the riprap and repair damaged area by 12 inches.

- RipRap Replacement:
1. Immediately after installing the filter, add the riprap to full thickness in one operation to the design elevation, and extend riprap to the top of the bank.
 2. Place smaller rock in voids to form a dense, uniform, well-graded mass.
 3. Blend the riprap smoothly to the surrounding grade.
 4. Stabilize all disturbed areas immediately following installation.

- Maintenance:**
1. Inspect periodically for displaced rock material, slumping, and erosion at edges, especially down stream or down slope.

- Note:**
1. At owner's discretion, outlet protection & grade stabilization Scour Stop TM may be substituted for this practice.



BASKET INLET / CATCH BASIN PROTECTION


Purpose: To prevent excessive sediment from entering storm sewers at inlet/catch basin, allowing full use of the storm drain system during the construction period.

Requirements: Steel Frame with top width-length dimensions such that the basket fits into the inlet and/or catch basin (circular and/or rectangular), and a replaceable Geotextile fabric bag attached with a steel band locking cap that is suspended from the frame.

Catch-All Inlet Protector Hancor Flo-Gard bt Nyloplast or approved equal.

- Installation:**
1. Install protection to existing and newly installed inlet/catch basin in a new development before land disturbing activities begin in a stabilized area.
 2. Remove the grate, and place the basket assembly under the grate on the lip of the structure frame.
 3. Replace the inlet/catch basin grate.

- Maintenance:**
1. Inspect weekly during construction and after each storm event of a minimum of 1/2 inch rainfall, and remove built-up sediment.
 2. Replace bag every six (6) months.
 3. Replace the Geotextile fabric bag if there is a hole and/or won't pass water.
 4. Replace the Geotextile fabric bag after any oil, gasoline or solvent spill.



GENERAL NOTES:
FRAME Top Flange Fabricated from 1/2"x1/2"x1/2" angle. Base rin Fabricated from 1/2"x1/2"x1/2" channel. Handles and suspension brackets Fabricated from 1/2"x1/2" flat stock. All steel conforming to ASTM-A36.
SEDIMENT BAG Bag Fabricated from 4 oz./sq.yd. non-woven polypropylene geotextile reinforced with polyester mesh. Bag secured to base rin with a stainless steel band and lock.

TYPICAL INLET/CATCH BASIN PROTECTION INSERT DETAIL

DUST CONTROL

Purpose: To reduce wind-borne soil particles (dust) that may be transported and deposited in waterbodies, create a health hazard, and/or a visibility hazard.

- Requirements:**
1. Dust control measures may be applied at any construction site, but should always be utilized for sites with dry, unvegetated soils that are exposed to wind or vehicle traffic that can potentially result in the generation of dust.
 2. Where practical, locate haul roads and stockpiles away from existing residential housing, businesses, and public areas.
 3. Limit construction equipment on haul roads to the extent practical. Construction equipment should maintain low speed of 15 miles per hour or less.
 4. Trucks leaving a project site should be covered, especially where conditions may result in blowing of haul material.
 5. Minimize areas of disturbed, unvegetated soil exposed to traffic and wind.
 6. Water quality impacts should always be considered when selecting a dust control treatment.

- Application:**
1. Temporary Methods:
 - A. Watering/Irrigation: Typically used for haul roads and heavy traffic areas. Used as an emergency treatment measure.
 - B. Dust Suppressants: Dust suppressants that are commercially available. Some products may be toxic to the environment. The level of toxicity and proximity to waterbodies and other unique resource areas should be considered when selecting a product. Products should be strictly applied according to the standards and specifications of the manufacturer and in accordance with applicable local, state, and federal regulations.

- Challenges:**
- Used for improved construction haul roads.
 - Applied as a liquid solution or dry granules/flakes.
 - Application can inhibit growth.
 - Runoff from treated areas can pollute waterbodies.

- Resins:**
- Applied to haul roads, soil stockpiles, unvegetated soils, or used as a tackifier.
 - Water sheds off soils treated with these products.
 - Low environmental impact after application.
 - Avoid introducing resin into waterbodies during application.

- Polymer Products:**
- Used on soil stockpiles, unvegetated soils.
 - May also be applicable to haul roads.
 - Apply with truck or hydrosowing machine.
 - Use restricted to anionic polymer mixtures and shall have less than or equal to 10 percent free acrylamide monomer by weight as established by the U.S. Food and Drug Administration and the U.S. Environmental Protection Agency.

- Lignin/Sulfonates:**
- Used for haul roads.
 - Water soluble and could lose bonding capability in heavy rain.
 - Environmentally friendly.

- Tillage:**
- Large open disturbed areas.
 - Used as an emergency treatment measure.
 - Relatively flat areas of less than two percent.
 - Chisel plows with shanks spaced 12 to 18 inches apart, straight-toothed harrows, or similar tillage equipment.
 - Best if implemented before soil begins to blow.

- Mulch:**
- Disturbed areas.
 - Effective, temporary measure.
- Temporary Vegetative Cover:**
- Disturbed areas.
 - Effective, temporary measure.

- Physical Barriers:**
- Emergency treatment measure.
 - Solid board fences, snow fences, burlap fences, erate walls, bales of hay, etc.
 - Used to control air currents and soil migration.

- Street Sweeping:**
- Paved areas.
 - Street sweeper, vacuum truck, or a bucket end loader.

Application: Prepare site for the application method or product that was selected for dust control.

- Maintenance:**
1. Inspect daily.
 2. Repeat treatments as needed when using temporary dust control methods.
 3. Commercial products should be used in accordance with the recommendations of the manufacturer.

SPILL PREVENTION AND RESPONSE

Purpose: Procedures and practices to prevent and control spills in a manner that minimizes or eliminates the discharge of spilled material to the drainage system or watercourses.

- Hazardous Waste Products:**
- Petroleum Products,
 - Asphalt Products,
 - Concrete Curing Compounds,
 - Pesticides,
 - Acids,
 - Paints,
 - Stains,
 - Solvents,
 - Wood Preservatives,
 - Roofing Tar, or
- Other Waste Products:**
- Soil Stabilizers/Binders,
 - Dust palliatives,
 - Herbicides,
 - Growth inhibitors,
 - Dewatering/anti-caking chemicals,
 - Fuel,
 - Lubricants,
 - Other petroleum distillates

Any materials deemed a hazardous waste in 40 CFR Parts 110, 117, 261, or 302

Spill Prevention Practices:

- The following are management practices used for reduction of spills and other accidental exposure of materials and substances to storm water runoff:
- a. The contractors and subcontractors shall refer to the Material Safety Data Sheet (MSDS) for information on the proper storage, use, and clean-up methods for all materials anticipated being on the project site.
 - b. All required materials for spill clean up and disposal of all onsite materials shall be kept on site in a project trailer with easy access for all users of associated materials.
 - c. All disposal of spilled materials shall be done in accordance with Federal, State and Local waste disposal regulations. All contractor and subcontractor shall be responsible for any and all spills associated with their work.
 - d. Prompt cleanup of any spills that may occur of liquid or dry materials.
 - e. Cleanup of sediments that have been tracked by vehicles or have been transported by wind or storm water about the site or onto nearby roadways.

Response Practices:


In the event that a large spill occurs (that which requires extensive cleanup actions, refer to MSD sheets for information), the following procedures shall be followed to minimize exposure of the material.

- a. Immediate action shall be taken to control and contain the spill to prevent it from entering any nearby storm sewer structures or open waters.
- b. Notify the Town of Valparaiso Fire Department at 911 for all combustible and flammable materials.
- c. Notify, for local contact, the Porter County Emergency Management at Phone: 219-462-8654, and/or Fax: 219-465-3598; the Federal Emergency Spill Hotline at 1-800-424-6802 within 2 hours for spills above the reported allowable quantity, or if the material enters any nearby storm sewer structures or open waters.
- d. Notify, for local contact, the Porter County Emergency Management at Phone: 219-462-8654, and/or Fax: 219-465-3598, the Indiana Emergency Response Hotline at 1-888-233-7745.
- e. The spill area shall be isolated from all surrounding areas with absorbent pads, booms, and pillows designed for the use of spill containment and absorption.
- f. The spill kits that are required to be on site shall be utilized.
- g. Emergency Response teams shall be contacted for extensive spills above and beyond the containment by available methods.

Waste Disposal Management Practices:

All solid waste associated with the construction and development of this project shall be removed and disposed of properly with in all applicable state and federal laws associated with the waste generated. Developer and/or contractor are to provide on-site dumpsters, rented from a licensed solid waste management company, to ensure waste is collected and disposed of properly. All trash and construction debris from the site will be deposited in a dumpster. No construction waste will be buried onsite. All personnel will be instructed regarding the correct procedure for waste disposal.

- a. Select a designated waste collection area onsite.
- b. Provide an adequate number of containers with lids or covers throughout the site, and frequent pickups.
- c. Provide immediate cleanup of any container spills.
- d. Make sure that construction waste is collected, removed, and disposed of only at authorized areas.



Donald C. Torrenge

CLIENT:
Tri-Creek School Corporation
19230 Cline Avenue
Lowell, Indiana 46356


JOB NO: 2023-5056

SCALE: NO SCALE

HOLTZ ROAD - IMPROVEMENTS
LOWELL, INDIANA
STORM WATER POLLUTION PREVENTION PLAN
DETAILS

REVISIONS:
DATE: 03-11-2024

TORRENGA ENGINEERING, INC.
CONSULTING ENGINEERS & LAND SURVEYORS
907 RIDGE ROAD, MUNSTER, INDIANA 46321
Tel. No.: (219) 836-8918
website: www.torrenge.com



SHEET

C-5.1