

ADDENDUM NO. 3

January 16, 2026

Smoky Row Elementary Additions & Renovations
900 West 136th Street
Carmel, IN 46032

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications and the Drawings dated November 20, 2025, by Fanning/Howey Associates. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 3-1 through ADD 3-3, and attached Revised Architects TOC for Book 2 and Book 3, Specification Section 01 32 00c Date Correction and Revised Guideline Schedule, and Specification Section 01 53 10 – Fences.

A. SPECIFICATION SECTION 00 00 20 Table of Contents

Replace the following Specification Section

00 00 20 TOC for Volume Book 2 and Volume Book 3 in its entirety, including missing Book 3 sections.

B. SPECIFICATION SECTION 01 12 00 Multiple Contract Summary

A. Bid Category No 1 General Trades

Add the following Specification Sections

32 13 13.20	Playground Site Concrete
32 13 73.20	Playground Concrete Joint Sealants
32 18 13	Synthetic Grass Surfacing
32 18 16	Playground Protective Surfacing
32 31 13.20	Playground Fences and Gates
32 93 13	Ground Covering and Mulches
33 13 13	Facility Sanitary Sewers

Replace Specification Section 01 53 10 Fences in its entirety.

Add the following Clarifications

24. This contractor is responsible for the size and quantity of aggregate base required by the poured in place suppliers' recommendation.
25. All MEP Contractors are responsible for their own slab cut, demo and pour backs for their divisions of work.
26. All shade pockets are the responsibility of this contractor. Any wood blocking required is to be coordinated and installed by the Bid Category 5 Metal Stud, Drywall, and Ceiling Contractor.
27. Responsible for a 6" concrete curb between poured in place and synthetic turf at all playgrounds. There is no concrete required underneath the poured in place or the turf.
28. Assume 16" of mulch demo and haul off at existing playgrounds.
29. On sheet AD0.03 this contractor is responsible for slab infill all the way to the corridor wall. There is a lower riser section that is not explicitly clear on the documents.

B. Bid Category No 2 Masonry

Add the following Clarification:

5. This contractor is NOT responsible for the stacked block piers shown on sheet S1.1. These will be provided and installed by modular building contractor.

E. Bid Category No 5 Metal Studs, Drywall, and Ceilings

Add the following Clarifications:

8. In regard to Abuse Resistant Acoustical Wall Tiles follow the finish schedule with 2" beveled.
9. All shade pockets are the responsibility of the Bid Category 1 General Trades Contractor. Any wood blocking required for these openings is by the Bid Category No 5 Metal Studs, Drywall, and Ceiling Contractor.

K. Bid Category No 11 Mechanical and Plumbing

Add the following Clarification:

10. This contractor is responsible for all slab cuts, demo, and pour back for this divisions work.

L. Bid Category No 12 Electrical

Add the following Clarifications:

14. This contractor is responsible for all slab cuts, demo, and pour back for this divisions work.
15. In regard to Café/Gym AV questions. Assume 3 loud speakers in the gym going back in kind at existing 3 locations. In general, use the symbol “MA” for the locations of the 3 touch panels (Riser diagram is correct but one is not shown on stage. Assume 1 on stage, 1 at the farthest point in the gym, and 1 in the cafeteria). In regard to the café speakers bid what is shown on the line diagram on sheet T1.06.
16. If the specifications call out a new projector model for a location, these are to be included as new.
17. This contractor is responsible for demolishing all electrical, data, fire alarm, and PA at the Cherry Tree modular buildings back to the source. The existing distribution panel at Cherry Tree may be able to be reused at Smoky Row along with any other supports or disconnects.

M. Bid Category No 13 Kitchen Equipment

Revise the following Clarification:

3. Responsible for demo and removal of existing kitchen equipment. The mechanical and electrical contractor will be responsible for make safe demo.

C. **SPECIFICATION SECTION 01 21 00 Allowances**

Revise/Add the following Allowances:

3.01 Product Allowance

B. Bid Category 01 – General Trades – Interior Temporary Partitions	\$125,000
D. Bid Category 12 – Electrical/Technology - Modular Classroom Misc.	\$25,000
E. Bid Category 01 – General Trades – Future Site Utility Improvements	\$100,000
F. Bid Category 12 – Electrical/Technology - Light Fixtures P1, P5, P6	\$16,000

D. **SPECIFICATION SECTION 01 32 00 SCHEDULES**

1. Replace Sheet – Date Correction for Phase 3 on CM1.1 within 01 32 00c
2. Replace the following Guideline Schedule:

Specification Section 01 32 00d - Guideline Schedule

DOCUMENT 00 01 10 - TABLE OF CONTENTS

Book 2 of 3

INTRODUCTORY INFORMATION

00 01 05	Certifications Page
00 01 10	Table of Contents

SPECIFICATIONS

DIVISION 02: EXISTING CONDITIONS

02 41 19	Selective Demolition
----------	----------------------

DIVISION 03: CONCRETE

03 06 30.01	Concrete Schedule
03 30 00	Cast-in-Place Concrete

DIVISION 04: MASONRY

04 01 20	Maintenance of Masonry
04 20 00	Unit Masonry
04 72 00	Cast Stone Masonry

DIVISION 05: METALS

05 12 00	Structural Steel Framing
05 21 00	Steel Joist Framing
05 31 00	Steel Decking
05 40 00	Cold-Formed Metal Framing
05 50 00	Metal Fabrications
05 51 33.23	Alternating Tread Ladders
05 52 13	Pipe and Tube Railings
05 70 00	Decorative Metal
05 73 00	Decorative Metal Railings

DIVISION 06: CARPENTRY

06 10 00	Rough Carpentry
06 16 00	Sheathing
06 20 23	Interior Finish Carpentry
06 41 13	Wood Veneer-Faced Architectural Cabinets
06 42 00	Wood Paneling
06 61 16	Solid Surface Fabrications

DIVISION 07: THERMAL AND MOISTURE PROTECTION

07 01 45	Maintenance of Exterior Insulation and Finish Systems (EIFS)
07 01 50.91	Roofing Restoration
07 14 16	Cold Fluid-Applied Waterproofing
07 21 00	Thermal Insulation
07 24 19	Water Drainage Exterior Insulation and Finish System (EIFS)
07 24 23	Direct Applied Exterior Finish System

07 27 26.02	Vapor-Permeable, Fluid-Applied Membrane Air Barrier
07 41 13.16	Standing Seam Metal Roof Panels
07 54 00	Thermoplastic Membrane Roofing (PVC and KEE)
07 62 00	Sheet Metal Flashing and Trim
07 71 00	Roof Specialties
07 84 13	Penetration Firestopping
07 84 43	Joint Firestopping
07 91 00	Preformed Joint Seals
07 92 00	Joint Sealants
07 95 13.13	Interior Expansion Joint Cover Assemblies

DIVISION 08: OPENINGS

08 12 13	Hollow Metal Frames
08 14 16	Flush Wood Doors
08 16 13	Fiberglass Doors
08 31 13	Access Doors and Frames
08 33 13	Coiling Counter Doors
08 33 23	Overhead Coiling Doors
08 41 13	Aluminum-Framed Entrances and Storefronts
08 44 13	Glazed Aluminum Curtain Walls
08 71 00	Door Hardware
08 80 00	Glazing
08 81 13	Decorative Glass Glazing
08 87 23	Safety and Security Film
08 91 19	Fixed Louvers

DIVISION 09: FINISHES

09 01 91	Moisture Resistant/Water-Proof Flooring Adhesive for Concrete Slabs
09 05 16	Existing Substrate Preparation for Floor Finishes
09 21 16	Gypsum Board Assemblies
09 30 00	Tiling
09 51 13	Acoustical Panel Ceilings
09 54 23	Linear Metal Ceilings
09 65 13	Resilient Base and Accessories
09 65 16	Resilient Sheet Flooring
09 65 19	Resilient Tile Flooring
09 65 43	Linoleum Flooring
09 67 23	Decorative Resinous Flooring
09 68 13	Tile Carpeting
09 72 00	Wall Coverings
09 74 16	Wood-Veneer Wall Coverings
09 75 19	Marble Window Stools
09 77 13	Stretched Fabric Wall Systems
09 84 33	Sound-Absorbing Wall Units
09 84 33.13	Abuse-Resistant Sound-Absorbing Wall Units
09 91 23.61	Interior Painting/Repainting
09 96 00	High-Performance Coatings
09 96 63	Interior Finish System

DIVISION 10: SPECIALTIES

10 11 00	Visual Display Units
10 14 19	Dimensional Letter Signage
10 21 13.19	Solid Polymer Toilet Compartments
10 21 23	Cubicles

10 26 00	Wall and Door Protection
10 28 00	Toilet, Bath, and Laundry Accessories
10 41 16	Lock Box
10 44 13	Fire Extinguisher Cabinets
10 44 16	Fire Extinguishers

DIVISION 11: EQUIPMENT

11 13 13	Loading Dock Bumpers
11 31 00	Residential Appliances
11 40 00	Food Service Equipment
11 51 23	Library Stack Systems
11 52 13	Front Projection Screens
11 61 43	Stage Curtains
11 68 00	Playground Equipment and Structures
11 73 10	Safety Padding

DIVISION 12: FURNISHINGS

12 24 13	Roller Window Shades
12 32 16	Manufactured Plastic Laminate-Faced (Educational) Casework
12 48 26.01	Entrance Carpet Tile
12 93 00	Site Furnishings and Amenities

END OF TABLE OF CONTENTS

DOCUMENT 00 01 10 - TABLE OF CONTENTS

Book 3 of 3

INTRODUCTORY INFORMATION

00 01 05	Certifications Page
00 01 10	Table of Contents

SPECIFICATIONS

DIVISION 21: FIRE PROTECTION

21 05 00	Common Work Results for Fire Suppression
21 10 00	Water-Based Fire Suppression Systems

DIVISION 22: PLUMBING

22 00 02	Work in Existing Buildings
22 05 00	Common Work Results for Plumbing
22 05 01	Basic Plumbing Materials and Methods
22 05 19	Meters and Gages for Plumbing Piping
22 05 23	General-Duty Valves for Plumbing Piping
22 05 29	Hangers and Supports for Plumbing Piping and Equipment
22 05 53	Identification for Plumbing Piping and Equipment
22 07 00	Plumbing Insulation
22 11 16	Domestic Water Piping
22 11 19	Domestic Water Piping Specialties
22 13 16	Sanitary, Waste, and Vent Piping System
22 14 13	Facility Storm Drainage Piping
22 40 00	Plumbing Fixtures
22 47 00	Drinking Fountains and Water Coolers
22 63 13	Facility Natural Gas Piping

DIVISION 23: HEATING, VENTILATING, AND AIR CONDITIONING

23 01 30	HVAC Air Duct Cleaning
23 05 00	Common Work Results for HVAC
23 05 13	Common Motor Requirements for HVAC Equipment
23 05 19	Meters and Gages for HVAC Piping
23 05 23	General-Duty Valves for HVAC Piping
23 05 29	Hangers and Supports for HVAC Piping and Equipment
23 05 48	Vibration and Seismic Controls for HVAC Piping and Equipment
23 05 53	Identification for HVAC Piping and Equipment
23 05 93	Testing, Adjusting, and Balancing for HVAC
23 07 00	HVAC Insulation
23 09 00	Instrumentation and Control for HVAC
23 09 93	HVAC Sequence of Operation
23 21 13	Hydronic Piping
23 21 23	Hydronic Pumps
23 23 00	Refrigerant Piping
23 25 00	HVAC Water Treatment
23 29 23	Variable-Frequency Motor Controllers
23 31 13	Metal Ducts
23 33 00	Air Duct Accessories
23 34 23	HVAC Power Ventilators
23 36 00	Air Terminal Units

23 37 13	Diffusers, Registers, and Grilles
23 37 23	HVAC Gravity Ventilators
23 51 00	Breechings, Chimneys, and Stacks
23 52 16	Condensing Boilers
23 62 00	Packaged Compressor and Condenser Units
23 72 00	Air-to-Air Energy Recovery Equipment
23 73 13	Modular Indoor Central-Station Air-Handling Units
23 81 26	Split-System Air-Conditioners
23 82 19	Fan Coil Units
23 82 39	Unit Heaters

DIVISION 26: ELECTRICAL

26 00 05	Electrical Demolition
26 00 50	General Electrical Requirements
26 05 05	Electrical Testing
26 05 19	Low-Voltage Electrical Power Conductors and Cables
26 05 26	Grounding and Bonding for Electrical Systems
26 05 29	Hangers and Supports for Electrical Systems
26 05 33	Conduit and Boxes for Electrical Systems
26 05 36	Ladder Type Cable Trays
26 05 43	Underground Ducts and Raceways for Electrical Systems
26 05 53	Identification for Electrical Systems
26 05 73	Power System Studies
26 09 23	Lighting Control Devices
26 22 00	Low-Voltage Transformers
26 24 16	Panelboards
26 27 26	Wiring Devices
26 28 13	Fuses
26 28 16	Enclosed Switches and Circuit Breakers
26 29 13	Enclosed Controllers
26 32 13	Engine Generators
26 36 00	Transfer Switches
26 51 00	Interior Lighting
26 55 61	Architectural Lighting Controls
26 56 00	Exterior Lighting

DIVISION 27: COMMUNICATIONS

27 01 00	Operation Manuals of Communications Systems
27 01 11	Demonstration, Training, and Warranty of Communications Systems
27 05 00	Common Work Results For Communications
27 05 26	Grounding And Bonding For Communications Systems
27 05 28	Pathways For Communications Systems
27 05 53	Identification For Communications Systems
27 11 00	Communications Equipment Room Fittings
27 11 13	Communications Entrance Protection
27 13 23	Communications Optical Fiber Backbone Cabling
27 15 11	Conductors and Cables Public Address and Mass Notification Systems
27 15 13	Communications Copper Horizontal Cabling
27 15 53	Misc. Communications Audio-Video Cabling
27 41 17	Integrated A/V Control System and Equipment
27 51 23	Intercommunications and Program Systems

DIVISION 28: ELECTRONIC SAFETY AND SECURITY

28 05 00	Common Work Results For Electronic Safety And Security
28 05 13	Conductors And Cables For Electronic Safety And Security
28 13 00	Electronic Access Control
28 16 00	Intrusion Detection
28 23 00	Video Surveillance System
28 31 11	Digital, Addressable Fire-Alarm System

DIVISION 31: EARTHWORK

31 10 00	Site Clearing
31 20 00	Earth Moving
31 23 19	Dewatering
31 23 23	Flowable Fill
31 25 00	Erosion Control
31 32 00	Geotextile
31 50 00	Excavation Support and Protection

DIVISION 32: EXTERIOR IMPROVEMENTS

32 12 16	Asphalt Paving
32 13 13	Concrete Paving
32 13 13.01	Concrete Schedule
32 13 13.20	Playground Site Concrete
32 13 73	Concrete Paving Joint Sealants
32 13 73.20	Playground Concrete Joint Sealants
32 17 13	Parking Bumpers
32 17 23	Pavement Markings
32 18 13	Synthetic Grass Surfacing
32 18 16	Playground Surfacing
32 31 13	Chain Link Fences and Gates
32 31 13.20	Playground Fences and Gates
32 91 13	Soil Preparation
32 92 00	Turf and Grasses
32 93 00	Plants
32 93 13	Ground Coverings and Mulches

DIVISION 33: UTILITIES

33 05 00	Common Work Results for Utilities
33 13 13	Facility Sanitary Sewers
33 41 00	Storm Utility Drainage Piping
33 46 00	Subdrainage

END OF TABLE OF CONTENTS

SECTION 01 53 10 - FENCES

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including amended General Conditions and other Division-1 Specification Sections, apply to work of this Section.

1.02 SCHEDULING

- A. Provide temporary fencing to outline limits of site usage prior to start of other work as required by Contract Documents.

PART 2 – PRODUCTS

2.01 MATERIALS

- A. Provide all temporary fencing and gates shown or implied on the Construction Drawings and all fencing shown on Site Logistics Plan, Section 01 23 00c.
- B. Allow for 400 Lineal Feet of plastic construction fencing.
- C. Fence to have graphic screen as shown of Site Logistics Plan. Graphic to be provided by owner.

PART 3 - EXECUTION

3.01 INSTALLATION

- A. Install construction fencing where indicated and around temporary structures, storage areas, roadways and other hazards as required for safety and security.
- B. Space posts 6' o.c. and drive 3' into ground. Fasten fence to each post with five (5) fasteners.
- C. Space posts 10' o.c. and drive 3' into ground. Fasten fence to each post with five (5) fasteners.
- D. Provide gate posts and gates for two (2) 20'-0" side openings (each opening to contain two (2) 10'-0" leaves) with forked type or plunger type latch to permit operation from either side of gate with padlock eye as an integral part of latch.

3.02 MAINTENANCE

- A. Maintain fencing in good repair until completion of the Project unless directed otherwise by the Construction Manager.
- B. Relocate fencing if necessary due to construction progress when directed by the Construction Manager.
- C. Remove fencing when directed by the Construction Manager.

END OF SECTION 01 53 10

Schedule

Exterior Site work
Start-May 2026
End-August 2027

Phase 1
Start-May 2026
End-August 2026

Phase 2A
Start-June 2026
End-June 2027

Phase 2B
Start-June 2026
End-January 2027

Phase 3
Start-February
2027
End-April 2027

Phase 4
Start-April 2027
End-July 2027

Phase 5
Start- July 2027
End-September
2027

Phase 6
Start-August 2027
End-April 2028

Phase 7
Start-September
2027
End-December
2027

Phase 8
Start-December
2027
End-March 2028

Phase 9
Start-March 2028
End-June 2028

Phase 10
Start-May 2028
End-August 2028

Phase 11
Start-May 2026
End-August 2028

West Playground
Start-May 2027
End-August 2027

East Playground
Start-May 2028
End-August 2028



Activity Name			Original Duration	Start	Finish	2026												2027												2028												2029			
						Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	M	Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	Mar	Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	Mar	Apr			
	Punch List		15	20-Apr-27	10-May-27																																								
	Final Cleaning		5	11-May-27	17-May-27																																								
	Owner IT Move In		5	18-May-27	24-May-27																																								
	Owner Move In		10	25-May-27	07-Jun-27																																								
	Portable Classrooms			83	06-Apr-26	29-Jul-26	29-Jul-26, Portable Classrooms																																						
	Site Demo		5	06-Apr-26*	10-Apr-26																																								
	Sanitary Utilities		10	06-Apr-26	17-Apr-26																																								
	Underground Electrical and Technology Rough-In		5	13-Apr-26	17-Apr-26																																								
	Footings		10	20-Apr-26	01-May-26																																								
	Portable Classroom Delivery and Install		5	08-Jun-26*	12-Jun-26																																								
	Sidewalks		10	15-Jun-26	26-Jun-26																																								
	Electrical Feeders		10	15-Jun-26	26-Jun-26																																								
	Grading/Seeding		3	29-Jun-26	01-Jul-26																																								
	Trailer MEP Hook up		5	29-Jun-26	03-Jul-26																																								
	Fire Alarm/Technology Trim-Out		5	06-Jul-26	10-Jul-26																																								
	Punch List		5	13-Jul-26	17-Jul-26																																								
	Final Cleaning		1	20-Jul-26	20-Jul-26																																								
	Owner IT Move In		2	21-Jul-26	22-Jul-26																																								
	Owner Move In		5	23-Jul-26	29-Jul-26																																								
	Exterior Restoration			357	16-Mar-27	26-Jul-28	26-Jul-28, Exterior Restoration																																						
	Phase 2 A NewAddition South Exterior Concrete/Paving/Landscaping		40	16-Mar-27*	10-May-27																																								
	West Playgrounds/EC Playgrounds		50	24-May-27*	30-Jul-27																																								
	West Parking Lot Concrete/Paving/Landscaping		40	01-Jun-27*	26-Jul-27																																								
	East Playground		50	01-May-28*	07-Jul-28																																								
	East Parking Lot Concrete/Paving/Landscaping		40	01-Jun-28*	26-Jul-28																																								
	Interior Renovations			577	25-May-26	08-Aug-28	08-Aug-28, Interior Renovations																																						
	Phase 1			54	25-May-26	06-Aug-26	06-Aug-26, Phase 1																																						
	Owner Move Out		5	25-May-26*	29-May-26																																								
	MEPF Demo		5	01-Jun-26	05-Jun-26																																								
	Selective Demo		5	08-Jun-26	12-Jun-26																																								
Framing		5	15-Jun-26	19-Jun-26																																									
MEPF Rough-In		5	15-Jun-26	19-Jun-26																																									
Hang/Finish Drywall		5	22-Jun-26	26-Jun-26																																									
1st Coat of Paint		2	29-Jun-26	30-Jun-26																																									
Ceiling Grid		2	01-Jul-26	02-Jul-26																																									
Casework		0	01-Jul-26	01-Jul-26																																									
MEPF Trim Out		2	03-Jul-26	06-Jul-26																																									
Ceiling Pad		2	07-Jul-26	08-Jul-26																																									
2nd Coat of Paint		2	09-Jul-26	10-Jul-26																																									
Tackboards/Markerboards		2	13-Jul-26	14-Jul-26																																									
Flooring		3	15-Jul-26	17-Jul-26																																									
Projectors/Monitors Technology Trim Out		1	20-Jul-26	20-Jul-26																																									
Substantial Completion		0	21-Jul-26																																										
Punch List		5	21-Jul-26	27-Jul-26																																									

Activity Name			Original Duration	Start	Finish	2026												2027												2028												2029			
						Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	M	Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	Mar	Apr	M	Jun	Jul	A	S	Oct	N	D	Jan	F	Mar	Apr			
		Final Clean	5	28-Jul-26	03-Aug-26					▲	Final Clean																																		
		Owner Move In	3	04-Aug-26	06-Aug-26					▲	Owner Move In																																		
		Phase 3	59	01-Feb-27	22-Apr-27																																								
		Owner Move Out	3	01-Feb-27	03-Feb-27																																								
		Temporary Partitions	3	04-Feb-27	08-Feb-27																																								
		MEPF Demo	5	09-Feb-27	15-Feb-27																																								
		Selective Demo	5	16-Feb-27	22-Feb-27																																								
		Framing	6	23-Feb-27	02-Mar-27																																								
		MEPF Rough-In	10	23-Feb-27	08-Mar-27																																								
		Hang/Finish Drywall	6	23-Feb-27	02-Mar-27																																								
		1st Coat of Paint	3	09-Mar-27	11-Mar-27																																								
		Ceiling Grid	4	12-Mar-27	17-Mar-27																																								
		MEPF Trim Out	5	12-Mar-27	18-Mar-27																																								
		Casework	5	18-Mar-27	24-Mar-27																																								
		Ceiling Pad	5	19-Mar-27	25-Mar-27																																								
		2nd Coat of Paint	3	26-Mar-27	30-Mar-27																																								
		Tackboards/Markerboards	5	31-Mar-27	06-Apr-27																																								
		Flooring	6	07-Apr-27	14-Apr-27																																								
		Projectors/Monitors Technology Trim Out	3	15-Apr-27	19-Apr-27																																								
		Substantial Completion	0	20-Apr-27																																									
		Punch List	3	20-Apr-27	22-Apr-27																																								
		Owner Move In	2	20-Apr-27	21-Apr-27																																								
		Phase 4	60	20-Apr-27	12-Jul-27																																								
		Owner Move Out	1	20-Apr-27	20-Apr-27																																								
		Temporary Partitions	5	22-Apr-27	28-Apr-27																																								
		Selective Demo	9	29-Apr-27	11-May-27																																								
		MEPF Demo	5	29-Apr-27	05-May-27																																								
		Framing	5	12-May-27	18-May-27																																								
		MEPF Rough-In	7	12-May-27	20-May-27																																								
		Hang/Finish Drywall	5	12-May-27	18-May-27																																								
Hollow Metal Frames	3	12-May-27	14-May-27																																										
1st Coat of Paint	3	21-May-27	25-May-27																																										
Ceiling Grid	5	26-May-27	01-Jun-27																																										
MEPF Trim Out	7	26-May-27	03-Jun-27																																										
Casework	5	02-Jun-27	08-Jun-27																																										
Ceiling Pad	5	04-Jun-27	10-Jun-27																																										
2nd Coat of Paint	3	11-Jun-27	15-Jun-27																																										
Tackboards/Markerboards	3	16-Jun-27	18-Jun-27																																										
Flooring	10	21-Jun-27	02-Jul-27																																										
Doors / Hardware	3	21-Jun-27	23-Jun-27																																										
Projectors/Monitors Technology Trim Out	2	05-Jul-27	06-Jul-27																																										
Substantial Completion	0		06-Jul-27*																																										
Punch List	2	07-Jul-27	08-Jul-27																																										
Owner Move In	2	09-Jul-27	12-Jul-27																																										

|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|