

ADDENDUM NO. 01

January 27, 2026

Kalamazoo Public Schools Northglade Montessori Magnet
1914 Cobb Ave
Kalamazoo, MI 49007

TO: ALL BIDDERS OF RECORD

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications and the Drawings dated January 9, 2026, by TowerPinkster. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 1-3 through ADD 1-1 and TowerPinkster Architect's Supplemental Instructions, dated January 26, 2026, consisting of 2 pages.

A. SPECIFICATION SECTION 00 20 00 - INFORMATION AVAILABLE TO BIDDERS

1. Replace Section with attached.
2. After our Pre-Bid Meeting, the Skillman Team will be visiting the Northglade jobsite from 4:00 PM to 5:00 PM if any Contractors would like to attend.
3. A second Contractor Walkthrough will be held on Monday, February 2, 2026, from 1:00 PM to 3:00 PM.
4. See attached Pre-Bid RFI Log dated, January 27, 2026.
5. See attached Floor Protection Plan.

B. SPECIFICATION SECTION 01 12 00 – MULTIPLE CONTRACT SUMMARY

A. BID CATEGORY NO. 01 GENERAL TRADES

Add the following clarification(s)

1. Clarification No. 01: **Bid Category No. 01 – General Trades** shall provide all door hardware for all wood and hollow metal doors. **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** shall provide all door hardware for aluminum doors.
2. Clarification No. 02: **Bid Category No. 01 – General Trades** shall be responsible for removing existing storefront systems and window treatments as shown in the drawings.
3. Clarification No. 03: **Bid Category No. 01 – General Trades** shall be responsible to replace/grade/reseed areas within the school's grounds that are damaged throughout the construction phase.
4. Clarification No. 04: **Bid Category No. 01 – General Trades** shall be responsible for protecting existing pavements during construction per sheet LD101 using ½" plywood.
5. Clarification No. 05: **Bid Category No. 01 – General Trades** shall provide housekeeping pads in B12A.
6. Clarification No. 06: **Bid Category No. 01 – General Trades** to install, maintain and remove flooring protection for locations outlined in the attached "Flooring Protection Plan" using plastic sheeting under masonite or equivalent.

B. BID CATEGORY NO. 02 ALUMINUM FRAMED ENTRANCES AND STOREFRONTS

Add the following clarification(s)

1. Clarification No. 01: **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** shall provide all hardware for aluminum doors. **Bid Category No. 01 – General Trades** shall provide all door hardware for wood and hollow metal doors.

2. Clarification No. 02: **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** to coordinate and install louvers supplied by **Bid Category No. 03 – Mechanical** in storefront locations as show on sheets A 301, A 302 and A 303.

C. BID CATEGORY NO. 03 MECHANICAL

Add the following clarification(s)

1. Clarification No. 01: **Bid Category No. 03 – Mechanical** shall supply all louvers. Coordinate with **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** to ensure compatibility with storefront systems.
2. Clarification No. 02: **Bid Category No. 03 – Mechanical** shall install all louvers with exception of storefront locations shown on Sheets A301, A302, and A303. Coordinate with **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** to ensure compatibility with storefront systems.
3. Clarification No. 03: **Bid Category No. 02 – Aluminum Framed Entrances and Storefronts** to coordinate and install louvers supplied by **Bid Category No. 03 – Mechanical** in storefront locations as show on sheets A 301, A 302 and A 303.

C. SPECIFICATION SECTION 01 32 00 – SCHEDULES AND REPORTS

a. **1.03 GUIDELINE SCHEDULE**

Add:

1. See Guideline Schedule dated January 21, 2026, attached.
2. See Phasing Plan attached.

SECTION 00 20 00 - INFORMATION AVAILABLE TO BIDDERS

- A. Subsurface Investigation Information: The Soils Exploration Report and Soil Boring Logs were prepared for the Owner by **Driesenga & Associates dated October 19, 2021,** for general information related to subsurface conditions.
- B. The following Subsurface Investigation Report is not a part of the construction Contract Documents and is enclosed within this document for informational use only. The Architect/Engineer and Construction Manager do not accept responsibility for the information contained in the report.
 - 1. The enclosed report and Log of Borings, and any interpolations of conditions between test borings is not a warrant or guarantee by the Owner or Architect/Engineer of subsurface conditions.
 - 2. The Contractor should visit the site and acquaint himself with all existing conditions. Prior to bidding, bidders may make their own subsurface investigations to satisfy themselves as to the site and subsurface conditions, but such subsurface investigations shall be performed only under the time schedules and arrangements approved in advance by the Owner. Any additional information, needed by the Contractor, shall be obtained by the Contractor at no cost to the Owner.
 - 3. Structural design has been based on the report and assumes that existing soils are clean and can be compacted and will achieve the densities specified in the earthwork section. It shall be the Contractor's responsibility to determine for himself existing Site and or soil conditions.
- C. Existing Site Survey Information: A Site survey can be found within the construction drawings. It is not however, part of the Construction Contract Documents and is for informational use only. Information found is not a warrant or guarantee by the Owner or Project Consultant. The Contractor should visit the site and acquaint himself with all existing conditions. Any additional information, needed by the Contractor, shall be obtained by the Contractor at no cost to the Owner.
- D. Asbestos Report: The Asbestos Report (if applicable), prepared for the Owner, is not part of the Construction Documents, and is on file at the Owner's Office and is available for review upon written request. The Architect and Construction Manager do not accept responsibility for the information contained in the report.
- D. Lead Based Paint: Lead Based Paint Report (if applicable), prepared for the Owner, is not part of the Construction Documents, and is on file at the Owner's Office and is available for review upon written request. The Architect and Construction Manager do not accept responsibility for the information contained in the report.

END OF SECTION 00 20 00

October 19, 2021

via electronic mail

Ms. Karen Jackson
KALAMAZOO PUBLIC SCHOOLS
1220 Howard Street
Kalamazoo, Michigan 49008

**Re: Geotechnical Pavement Recommendations
Northglade School Pavement
1914 Cobb Street, Kalamazoo, Michigan
D&A Project No. 2150818.3B**

Dear Ms. Jackson:

Driesenga & Associates, Inc. (D&A) is pleased to submit the following geotechnical evaluation report and recommendations for the proposed parking lot reconstruction of the Northglade School bus drive, northwest parking area and southeast playground pavement. This work was performed as requested by Mr. Mike Galovan of TowerPinkster on behalf of Kalamazoo Public Schools and in accordance with our proposal dated August 27, 2021 and authorized by Kalamazoo Public Schools Purchase Order No. 157609-00, dated September 10, 2021.

FIELD EXPLORATION AND LABORATORY PROCEDURES

Six (6) soil borings, designated SB-1 to SB-6, were performed at selected locations on October 16 and 18, 2021, as depicted on the attached Soil Boring Location Map. The soil borings were conducted using a standard, truck-mounted drill rig to a depth of 5-feet below existing grades or a 3.5-inch diameter hand auger to a depth of 3-feet. Upon completion, the boreholes were backfilled with soil cuttings and the surface was repaired approximating previous conditions. Split-barrel samples were obtained in the soil below the bottom of the augers in general accordance with the Standard Method for Penetration and Split-Barrel Sampling of Soils when using the drill rig. Samples were collected at 2.5 feet intervals to the requested boring depth of 5-feet below existing grades. The collected samples were transported to our laboratory and characterized in general accordance with the Unified Soil Classification System (USCS). At soil boring SB-6, a Dynamic Cone Penetrometer following ASTM D6951-09 was used to determine the relative density of the soils to a depth of 5-feet below grade. The estimated group symbol is shown on the attached boring logs, just before the soil description.

SITE, SOIL, AND GROUNDWATER CONDITIONS

The existing pavement areas were observed to be in poor condition with regular cracking, potholed areas and a moderately to severely worn surface.

The material profile generally consists of 2 to 8 inches of asphalt underlain by 5 to 22 inches of aggregate base material underlain by medium dense to dense clayey sand or sand fill with trace brick and coal slag to a depth of approximately 1.5 to 2.5 feet below grade. Underlying the fill soils, gray clayey sand was encountered to the explored depth of 5 feet. Below the fill at SB-2, SB-3 and SB-6, a layer of peat was encountered. See attached boring logs for specific soil information.



Approximate asphalt, aggregate base, and underlying subsurface soils thicknesses were measured in the field by the drillers. These measurements should be considered approximate since some mixing of the materials with one another occurs during drilling.

Water was encountered at several boring locations that appears to be perched. This water appears to be surface infiltrated water that cannot readily permeate the cohesive soils found at the site. Hydrostatic groundwater levels and the elevations and volumes of groundwater should be expected to fluctuate throughout the year, based on variations in precipitation, evaporation, run-off, and other factors. The groundwater levels (or lack thereof) indicated by the soil borings and presented in this section represent conditions at the time the readings were taken. The actual groundwater levels at the time of construction may vary.

ANALYSIS AND RECOMMENDATIONS

Based on the relative density and characteristics of the soil profile encountered (particularly the organic containing soils), along with the current surface condition of the pavement, we recommend a complete reconstruction of the existing pavement section. The existing bituminous asphalt pavement layer and the aggregate base layer should be removed, exposing the subgrade soils. The asphalt material may be pulverized/crushed and along with the existing aggregate, stockpiled for later use as undercut backfill (engineered fill) on the site. Neither of these materials should be used as aggregate base material.

A comprehensive proofroll of the exposed subgrade should be performed. Any areas that are found to exhibit excessive pumping, rutting or unsuitable/unsuitable (organic containing) soils should be undercut and replaced with compacted engineered fill to design subgrade elevation. Based on the soils encountered, undercutting of unsuitable soils could extend 4-feet or more below pavement surface elevations where the peat soils were encountered. We recommend a contingency in the project for the unknown amount of unsuitable soils. Compaction of the backfill soils should be to a minimum of 95% of Modified Proctor maximum dry density MDD, or 98% of MDD as determined by the Michigan Cone Method.

To maintain a similar surface elevation and accommodate a sand drainage layer, the existing subgrade soils will need to be undercut an approximate depth of 12 inches. Above the subgrade, the sand subbase should be constructed using a minimum of 12 inches of Michigan Department of Transportation (MDOT) Class II Fine Aggregate fill (MDOT Division 3, Section 301 "2012 Standard Specifications for Construction", April 1, 2011) compacted to a minimum of 95% of the material's MDD as determined by Modified Proctor.

Due to the cohesive soils encountered below the aggregate base material at the site, site grading and stormwater controls will be important to protect paved drives and parking areas. To further protect new paved areas, perimeter underdrains should be placed beneath pavement edges within the bottom portion of the pavement sand subbase. Four (4) inch-diameter sock-tube backfilled with at least 6 inches of peastone cover should be used. The drains should flow via gravity to a common low point and into the off-site storm sewer system.

The aggregate base for pavement areas should follow MDOT Dense-Graded Aggregate Base Course Materials – Division 3, Section 302 and Division 9, Section 902, using a 21AA (Grading Requirements per MDOT Table 902-1) Limestone Dense-Graded Aggregate material with a minimum compacted thickness of 8 inches. This gravel base may be placed in one (1) lift and should be compacted to a minimum of 95% of the material's MDD as determined by Modified Proctor.



Light duty bituminous pavement should consist of a 1.5-inch base course using MDOT 13A, and a 1.5-inch surface course using MDOT 13A, for a total thickness of 3.0 inches. Heavy duty bituminous pavement should consist of a 2.5-inch base course using MDOT 13A, and a 1.5-inch surface course using MDOT 13A, for a total thickness of 4.0 inches. Compaction of the asphalt courses should range between 92% and 96% of the Theoretical Maximum Density (TMD). Construction traffic should be minimized on the new pavement. If excessive construction traffic is anticipated on the pavement structure, the initial asphalt lift thickness could be increased and placement of the final lift could be delayed until the majority of the construction activities have been completed. This action will allow repair of localized failure, if any does occur, as well as reduce load damage on the pavement system.

A bond coat of emulsion should be used between the base course and wearing course when more than 48 hours have elapsed between placement of the courses, or the surface of the base course has been contaminated by soil or dust. Performance grade asphalt cement should be used in the production of all bituminous mixtures. After the pavement is complete, we recommend instituting a regular maintenance program that includes sealing of cracks and patching of distressed areas. This should reduce the effect of water infiltration and associated frost action.

GENERAL COMMENTS

This report and any future reports or addenda performed for this site should be supplied to potential bidders prior to them submitting their proposals. We also recommend the construction contract include provisions for dealing with differing conditions. Contingency funds should be reserved for potential problems during earthwork and pavement construction.

This report has been prepared solely for the use of the client for the project specifically described in this report. This report cannot be relied upon by other parties not involved in this project, unless written permission is granted by Driesenga & Associates, Inc. If this report or any of its contents are utilized by parties other than our original client and the project team members, Driesenga & Associates, Inc. cannot be held responsible for the suitability of the field exploration, scope of services, or recommendations made for the new project. Driesenga & Associates, Inc. also is not responsible for the interpretation of our soil boring logs and the recommendations provided herein by other parties.

We appreciate the opportunity to be of service to you. If you have any questions, or if we can be of further service as design and construction progresses, please contact our office.

Sincerely,

DRIESENKA & ASSOCIATES, INC.

A handwritten signature in blue ink, appearing to read "Michael Stork".

Michael Stork
Project Geologist

A handwritten signature in blue ink, appearing to read "R. Pail".

Randy Pail, P.E.
Director of Geotechnical Engineering

cc: Jim Henning, P.E. – Driesenga & Associates, Inc.

Attachments – Soil Boring Location Map
Soil Boring Logs
Soil Classification Sheets



Scale: NTS



Figure Number: 1

Site Location

Project Name:

Northglade School
Pavement

Project Number:

2150818.3B

Project Location:

1914 Cobb Street
Kalamazoo, MI

Date: 10-18-21

Sheet: 1 of 1

Modified by: MWS





Scale: NTS

● Boring Location



Figure Number: 2

Boring Locations

Project Name:

Northglade School
Pavement

Project Number:

2150818.3B


Project Location:

1914 Cobb Street
Kalamazoo, MI

Date: 10-18-21

Sheet: 1 of 1

Modified by: MWS





Engineering · Surveying · Testing

Drilling Company	: Great Lakes Drilling
Field Sampling	: J. Cook
Reviewed By	: M. Stork
GW Encountered	: Dry
GW Completion	: Dry

Client Name: Kalamazoo Public Schools

10-18-2021 C:\Users\Michael Stork\Dropbox (DAI)\Kalamazoo\Projects\2021\2150818.3B\QLogs\SB-1 Northqlade.bor



Engineering · Surveying · Testing

GW Completion : Dry cave in at 3.9'

Client Name: Kalamazoo Public Schools

[illegible]



**DRIESEN &
ASSOCIATES, INC.**

Engineering · Surveying · Testing

SB-3 Northglade

Project: Northglade School Pavement
1914 Cobb Street
Kalamazoo, Michigan

Project No. 2150818.3B

Client Name: Kalamazoo Public Schools

Date Started : October 16, 2021
Date Completed : October 16, 2021
Hole Diameter : 6-inches
Drilling Method : Solid-Stem Auger
Sampling Method : Split-Spoon Sampler

Drilling Company : Great Lakes Drilling
Field Sampling : J. Cook
Reviewed By : M. Stork
GW Encountered : 2.2'
GW Completion : 2.2'

Depth in Feet	Surf. Elev. 99	USCS	GRAPHIC	Water Levels	DESCRIPTION	Samples	Blow Count	N Value	Pocket Pen (tsf)	Water Level	Moisture Content %
				▼ During Drilling ▽ After Completion							
0	99				ASPHALT - 4 inches						
		GW			GRAVEL - 9 inches						
		SW/Fill			Fill - SAND, medium dense, brown to dark brown, fine to medium grained with trace gravel, moist to wet.	1	8	20			
		PT			PEAT - 12 inches		13				
		SC			CLAYEY SAND, loose, gray, fine to medium grained with trace gravel, wet.	2	7				
5	94						3				
							4	8			
							4				
10											



Engineering · Surveying · Testing

GW Completion : Dry

Client Name: Kalamazoo Public Schools

[illegible]



Engineering · Surveying · Testing

Drilling Company	: Great Lakes Drilling
Field Sampling	: J. Cook
Reviewed By	: M. Stork
GW Encountered	: Dry
GW Completion	: Dry

Client Name: Kalamazoo Public Schools

[illegible]



DRISENGA & ASSOCIATES, INC.

SB-6 Northglade

Engineering · Surveying · Testing

Project: Northglade School Pavement
1914 Cobb Street
Kalamazoo, Michigan

Project No. 2150818.3B

Client Name: Kalamazoo Public Schools

Date Started : October 18, 2021
Date Completed : October 18, 2021
Hole Diameter : 3.5-inches
Drilling Method : Hand Auger
Sampling Method : Auger Cuttings

Drilling Company : Driesenga & Associates
Field Sampling : M. Stork
Reviewed By : M. Stork
GW Encountered : 1.2'
GW Completion : 1.2'

Depth in Feet	Surf. Elev. 96	USCS	GRAPHIC	Water Levels ▼ During Drilling ▽ After Completion	Samples	Blow Count	N Value	Pocket Pen (tsf)	Water Level	Moisture Content %
				DESCRIPTION						
0	96			ASPHALT - 8 inches						
		GW		GRAVEL - 10 inches	1				▼	
		PT		PEAT - At least 18 inches						
Auger hole collapse due to high groundwater										
5	91									
10										



CLASSIFICATION OF SOILS FOR ENGINEERING PURPOSES

For use with a Standard Hammer for SPT

Per ASTM D 2487—92

(Based on Unified Soil Classification System)

Soil Description: Consistency/Relative Density, Color, Secondary Soil Type BASIC SOIL TYPE, Supplemental Soil Type, Moisture, Miscellaneous comments. (Group Symbol)

Ex. Loose, brown, fine to medium, silty SAND, trace of gravel, moist. (SM)

Consistency/Relative Density – a measurement of in-situ consistency or density of cohesive or cohesionless soils, respectively, based upon Standard Penetration Testing blow counts (N) per ASTM D 1586.

Color – visual inspection of soil appearance.

Secondary Soil Type – adjective for the BASIC SOIL TYPE describing material making up greater than 12% but less than 50% of the primary soil type by weight. For sands this also includes a description of grain size (fine, medium or coarse).

BASIC SOIL TYPE – primary constituent of sample; material making up greater than 50% of the sample by weight. Material is classified by grain size and material properties.

Supplementary Soil Type – a description of any other material that may be mixed with the BASIC SOIL TYPE. Qualifying terms are based on the percentage of the supplementary soil type in the sample by weight.

Moisture – description of the in-situ moisture content of the sample (dry, moist or wet).

Miscellaneous Comments – anything observed in the sample or in the field that does not fit into the above categories but should be noted (odor, etc.).

CONSISTENCY/RELATIVE DENSITY				
COHESIONLESS SOILS		COHESIVE SOILS		
SPT N-VALUES	IN-SITU RELATIVE DENSITY	SPT N-VALUES	SHEAR STRENGTH (PSF)	IN-SITU CONSISTENCY
0-4	VERY LOOSE	0-2	BELOW 250	VERY SOFT
5-10	LOOSE	3-4	250 - 500	SOFT
11-30	MEDIUM DENSE	5-8	500 - 1,000	MEDIUM STIFF
31-50	DENSE	9-16	1,000 - 2,000	STIFF
>50	VERY DENSE	17-32	2,000 - 4,000	VERY STIFF
		>32	OVER 4,000	HARD

SUPPLEMENTAL TEXTURE QUALIFYING TERMS	
DESCRIPTOR	PERCENTAGE BY WEIGHT
TRACE	1-10%
LITTLE	10-20%
SOME	20-35%
AND	35-50%



SOIL CLASSIFICATION CHART (Per ASTM D2487)

Criteria for Assigning Symbols and Group Names Using Laboratory Tests ^A				Soil Classification	
				Group Symbol	Group Name
COHESIONLESS SOILS More than 50% retained on No. 200 sieve	Gravels More than 50% of coarse fraction retained on No. 4 Sieve	Clean Gravels Less than 5% fines ^C	$Cu \geq 4$ and $1 \leq Cc \leq 3^E$	GW	Well-graded gravel ^F
			$Cu < 4$ and/or $1 > Cc > 3^E$	GP	Poorly graded gravel ^F
		Gravels with Fines More than 12% fines ^C	Fines classify as ML or MH	GM	Silty gravel ^{F,G,H}
			Fines classify as CL or CH	GC	Clayey gravel ^{F,G,H}
	Sands More than 50% of coarse fraction retained on No. 4 Sieve	Clean Sands Less than 5% fines ^D	$Cu \geq 6$ and $1 \leq Cc \leq 3^E$	SW	Well-graded sand ^F
			$Cu < 6$ and/or $1 > Cc > 3^E$	SP	Poorly graded sand ^F
		Sands with Fines More than 12% fines ^D	Fines classify as ML or MH	SM	Silty sand ^{G,H,I}
			Fines classify as CL or CH	SC	Clayey sand ^{G,H,I}
COHESIVE SOILS 50% or more passes the No. 200 Sieve	Silts and Clays Liquid limit less than 50	Inorganic	$PI \geq 7$ and plots on or above 'A' line ^J	CL	Lean clay ^{K,L,M}
			$PI < 4$ or plots below 'A' line ^J	ML	Silt ^{K,L,M}
		Organic	Liquid limit - oven dried < 0.75	OL	Organic clay ^{K,L,M,N}
			Liquid limit - not dried < 0.75		Organic silt ^{K,L,M,O}
	Silts and Clays Liquid limit 50 or more	Inorganic	PI plots on or above 'A' line	CH	Fat clay ^{K,L,M}
			PI plots below 'A' line	MH	Elastic Silt ^{K,L,M}
		Organic	Liquid limit - oven dried < 0.75	OH	Organic Clay ^{K,L,M,P}
			Liquid limit - not dried < 0.75		Organic silt ^{K,L,M,O}
HIGHLY ORGANIC SOILS	Primarily organic matter, dark in color, and organic odor			PT	Peat

A Based on the material passing the 3-in. sieve

B If field sample contained cobbles or builders, or both, add "with cobbles or boulders or both" to group name

C Gravels with 5 to 12% fines require dual symbols:
GW-GM well-graded gravel with silt
GW-GC well-graded gravel with clay
GP-GM poorly graded gravel with silt
GP-GC poorly graded gravel with clay

D Sands with 5 to 12% fines require dual symbols:
SW-SM well-graded sand with silt
SW-SC well-graded sand with clay
SP-SM poorly graded sand with silt
SP-SC poorly graded sand with clay

E $Cu = D_{60}/D_{10}$ $Cc = (D_{30})^2/(D_{10} \cdot D_{60})$

F If soil contains $\geq 15\%$ sand, add "with sand" to group name.

G If fines classify as CL-ML, use dual symbol GC-GM or SC-SM

H If fines are organic, add "with organic fines" to group name.

I If soil contains $\geq 15\%$ gravel, add "with gravel" to group name.

J If Atterberg limits plot in hatched area, soil is a CL-ML, silty clay.

K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel" whichever is predominant

L If soil contains $\geq 30\%$ plus No. 200, predominantly sand, add "sandy" to group name.


M If soil contains $\geq 30\%$ plus No. 200, predominantly gravel, add "gravelly" to group name
N $PI \geq 4$ and plots on or above 'A' line.

O $PI < 4$ or plots below 'A' line.


P PI plots on or above 'A' line.

Q PI plots below 'A' line.

For classification of fine-grained soils and fine-grained fraction of coarse-grained soils



SIEVE ANALYSIS




KPS CEC - Pre-Bid RFI Log

Date - 01/27/2026


TowerPinkster
Architecture · Engineering · Interiors





RFI #	Company Submitting RFI	Date Received	RFI Description	RFI Response
1	Moore Electric	1/26/2026	Bid Category 04 - Electrical •Do you know which fire alarm company is in this building currently?.	TSC: Riverside Integrated Systems - (616) 726-7026





Activity Name	Original Duration	Start	Finish	2026												2027												2028							
				Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr				
KPS Northglade Montessori				<div><div></div><div>KPS Northglade Montessori</div></div>																															
Administration				<div><div></div><div>Administration</div></div>																															
Bidding and Contracts				<div><div></div><div>Bidding and Contracts</div></div>																															
Project Advirtisement & Released				<div><div></div><div>Project Advirtisement & Released</div></div>																															
Pre-Bid Meeting				<div><div></div><div>Pre-Bid Meeting</div></div>																															
Bids Due				<div><div></div><div>Bids Due</div></div>																															
Review and Post Bid Tabs				<div><div></div><div>Review and Post Bid Tabs</div></div>																															
Pre-Award Conferences				<div><div></div><div>Pre-Award Conferences</div></div>																															
Letter of Recommendation to KPS				<div><div></div><div>Letter of Recommendation to KPS</div></div>																															
KPS Board of Authorization				<div><div></div><div>KPS Board of Authorization</div></div>																															
Contractors Notice to Proceed				<div><div></div><div>Contractors Notice to Proceed</div></div>																															
Pre-Construction				<div><div></div><div>Pre-Construction</div></div>																															
Contractor Agreements				<div><div></div><div>Contractor Agreements</div></div>																															
Material Procurement				<div><div></div><div>Material Procurement</div></div>																															
Procure Permits				<div><div></div><div>Procure Permits</div></div>																															
Pre-Construction Meeting				<div><div></div><div>Pre-Construction Meeting</div></div>																															
Submittals				<div><div></div><div>Submittals</div></div>																															
Pre-Installation Meeting(s)				<div><div></div><div>Pre-Installation Meeting(s)</div></div>																															
Contractors Mobilize				<div><div></div><div>Contractors Mobilize</div></div>																															
Pre-Demolition Meeting				<div><div></div><div>Pre-Demolition Meeting</div></div>																															
KPS Students Last Day of School				<div><div></div><div>KPS Students Last Day of School</div></div>																															
KPS Move Out of Select Areas				<div><div></div><div>KPS Move Out of Select Areas</div></div>																															
KPS Abatement & Clearances				<div><div></div><div>KPS Abatement & Clearances</div></div>																															
KPS Staff Last Day				<div><div></div><div>KPS Staff Last Day</div></div>																															
Closeout				<div><div></div><div>Closeout</div></div>																															
Contractor Closeout Meeting				<div><div></div><div>Contractor Closeout Meeting</div></div>																															
Closeout Submittals Due				<div><div></div><div>Closeout Submittals Due</div></div>																															
Final Mechanical/Electrical/Plumbing/Technology Inspections				<div><div></div><div>Final Mechanical/Electrical/Plumbing/Technology Inspections</div></div>																															
Contractor Incomplete Worklist & Corrections				<div><div></div><div>Contractor Incomplete Worklist & Corrections</div></div>																															
Final BCC/BFS Inspections				<div><div></div><div>Final BCC/BFS Inspections</div></div>																															
KPS, TP, and TSC Punch List Inspection				<div><div></div><div>KPS, TP, and TSC Punch List Inspection</div></div>																															
Contractor Punch List Corrections				<div><div></div><div>Contractor Punch List Corrections</div></div>																															

 Actual Work

 Remaining Work

 Critical Remaining Work


 Milestone

 Summary

224010.17 KPS Northglade Montessori

Guideline Schedule - 21-January-26

1 of 4



Activity Name			Original Duration	Start	Finish	2026												2027												2028							
						Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr				
Construction	Owner Training	10	28-Jun-27	09-Jul-27	Owner Training																																
	Project Substantial Completion	0		28-Jun-27	Project Substantial Completion																																
	Attic Stock Turnover	5	12-Jul-27	16-Jul-27	Attic Stock Turnover																																
	Project Completion	0		23-Jul-27	Project Completion																																
	KPS Staff Returns to Building	0	16-Aug-27		KPS Staff Returns to Building																																
	KPS Students First Day of School	0	24-Aug-27		KPS Students First Day of School																																
	Construction		305	30-Mar-26	28-May-27	Construction																															
	Unit A / Unit B		270	30-Mar-26	09-Apr-27	Unit A / Unit B																															
	Roof Unit Layout Walkthrough	5	30-Mar-26	03-Apr-26	Roof Unit Layout Walkthrough																																
	Storefront Field Measurements	5	30-Mar-26	03-Apr-26	Storefront Field Measurements																																
	Install & Maintain SESC Measures & Plant Protection	5	15-Jun-26*	19-Jun-26	Install & Maintain SESC Measures & Plant Protection																																
	Site Demolition	10	29-Jun-26*	10-Jul-26	Site Demolition																																
	Install and Maintain Floor Protection on Existing Floor Finishes to Remain	150	29-Jun-26*	22-Jan-27	Install and Maintain Floor Protection on Existing Floor Finishes to Remain																																
	Foundation Hydronic Piping	15	29-Jun-26*	17-Jul-26	Foundation Hydronic Piping																																
	Portable Classroom Demolition	5	06-Jul-26*	10-Jul-26	Portable Classroom Demolition																																
	Remove Paging Speakers/Clocks, Install Cover Plates, and Stock	10	06-Jul-26*	17-Jul-26	Remove Paging Speakers/Clocks, Install Cover Plates, and Stock																																
	Remove Existing Call Buttons & Install Atlasied Call Buttons	5	06-Jul-26*	10-Jul-26	Remove Existing Call Buttons & Install Atlasied Call Buttons																																
	Remove Doors/Lockers/Salvage as Noted	5	09-Jul-26*	15-Jul-26	Remove Doors/Lockers/Salvage as Noted																																
	Remove Countertops, Metal Grilles and Casework/Salvage Casework	10	15-Jul-26*	28-Jul-26	Remove Countertops, Metal Grilles and Casework/Salvage Casework																																
	Remove Ceiling Tile and Grid Assembly/Salvage/Dispose	10	20-Jul-26*	31-Jul-26	Remove Ceiling Tile and Grid Assembly/Salvage/Dispose																																
	Remove All Hydronic Piping/Insulation/Valves/Hangers	10	03-Aug-26*	14-Aug-26	Remove All Hydronic Piping/Insulation/Valves/Hangers																																
	Remove Wall and Storefront System/Shore/Brace as Required	15	03-Aug-26*	21-Aug-26	Remove Wall and Storefront System/Shore/Brace as Required																																
	Install New Panels PPA/PPB	10	03-Aug-26*	14-Aug-26	Install New Panels PPA/PPB																																
	Install New Electrical Service Upgrade	15	17-Aug-26*	04-Sep-26	Install New Electrical Service Upgrade																																
	Unit B - Demo and Remove All Hydronics in B12A Mechanical & Prepare for New Work	10	17-Aug-26	28-Aug-26	Unit B - Demo and Remove All Hydronics in B12A Mechanical & Prepare for New Work																																
	Provide New Steel Roof Frames/RTU Supports/Joist Reinforcing	20	24-Aug-26*	18-Sep-26	Provide New Steel Roof Frames/RTU Supports/Joist Reinforcing																																
	Unit A - Remove All OA Ductwork/RTU's/EF's/Controls/Assemblies	10	31-Aug-26*	11-Sep-26	Unit A - Remove All OA Ductwork/RTU's/EF's/Controls/Assemblies																																
	Remove All Mech. Equipment UV's/Ductwork/FT/AHU's	20	14-Sep-26*	09-Oct-26	Remove All Mech. Equipment UV's/Ductwork/FT/AHU's																																
	Prepare Existing Opening for New SF Assembly, Blocking/Steel/CMU	10	21-Sep-26*	02-Oct-26	Prepare Existing Opening for New SF Assembly, Blocking/Steel/CMU																																
	Provide New Storefront Assembly	30	05-Oct-26*	13-Nov-26	Provide New Storefront Assembly																																
Install New FCU/RA Unit/Ductwork/Unit Ventilators/EF's & FT Units	40	12-Oct-26*	04-Dec-26	Install New FCU/RA Unit/Ductwork/Unit Ventilators/EF's & FT Units																																	
Unit A - New Electrical Chase	10	12-Oct-26*	23-Oct-26	Unit A - New Electrical Chase																																	
Insulated Spandrel Panels	10	02-Nov-26*	13-Nov-26	Insulated Spandrel Panels																																	


































Actual Work
 Remaining Work
 Critical Remaining Work
 Milestone
 Summary








224010.17 KPS Northglade Montessori

Guideline Schedule - 21-January-26

2 of 4


Activity Name	Original Duration	Start	Finish	2026												2027												2028			
				Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr
Unit A - Provide New Plumbing/Reinstallation of Existing Plumbing Items	20	02-Nov-26*	27-Nov-26												△▽	Unit A - Provide New Plumbing/Reinstallation of Existing Plumbing Items															
New Doors/Hardware & Trim	15	09-Nov-26*	27-Nov-26												△▽	New Doors/Hardware & Trim															
Provide New Joint Sealants	5	16-Nov-26*	20-Nov-26												△▽	Provide New Joint Sealants															
Roof Top Mechanical Equipment/Ductwork/Connections/Linesets	20	23-Nov-26*	18-Dec-26												△▽	Roof Top Mechanical Equipment/Ductwork/Connections/Linesets															
Provide New Metal Grilles	10	23-Nov-26*	04-Dec-26												△▽	Provide New Metal Grilles															
Unit A - New Flooring/Patching of Flooring System	10	30-Nov-26*	11-Dec-26												△▽	Unit A - New Flooring/Patching of Flooring System															
Reinstall Salvaged Casework/Rework as Required	10	14-Dec-26*	25-Dec-26												△▽	Reinstall Salvaged Casework/Rework as Required															
Final Mech. Connections/Trim to FCU's/UV's & FT Units	10	18-Dec-26*	31-Dec-26												△▽	Final Mech. Connections/Trim to FCU's/UV's & FT Units															
Unit A - Connect New Electrical Meter, Arc Flash Switch, and MDP to BMS System	10	21-Dec-26*	01-Jan-27												△▽	Unit A - Connect New Electrical Meter, Arc Flash Switch, and MDP to BMS System															
Unit B - Roof Patching as Required for Roof Penetrations	6	21-Dec-26*	28-Dec-26												△▽	Unit B - Roof Patching as Required for Roof Penetrations															
Reinstall/Install Ceiling Assembly Grid & Tile/New/Salvaged	15	04-Jan-27*	22-Jan-27												△▽	Reinstall/Install Ceiling Assembly Grid & Tile/New/Salvaged															
Install Roller Shades	5	05-Apr-27*	09-Apr-27																												
Storage A15 Addition	75	29-Jun-26	09-Oct-26																												
Prepare Building Addition Pad	5	29-Jun-26*	03-Jul-26																												
Concrete Footings/Foundations	5	06-Jul-26*	10-Jul-26																												
A15 Storage Concrete Slab on Grade	5	13-Jul-26*	17-Jul-26																												
CMU Walls	15	20-Jul-26*	07-Aug-26																												
CMU Air Barriers & Insulation	5	10-Aug-26*	14-Aug-26																												
Steel Columns	5	17-Aug-26*	21-Aug-26																												
Steel Bar Joist, Deck Angles and Metal Decking	10	24-Aug-26*	04-Sep-26																												
Roof Expansion Joints, Roof Insulation, & Roof Membrane	10	07-Sep-26*	18-Sep-26																												
Plumbing and Mechanical Rough-In	5	14-Sep-26*	18-Sep-26																												
Install New Doors/Hardware & Trim	5	14-Sep-26	18-Sep-26																												
Patch Existing Roof for Addition	5	21-Sep-26*	25-Sep-26																												
Electrical AdditionRough-In	5	21-Sep-26*	25-Sep-26																												
A15 Prime and Paint	5	28-Sep-26*	02-Oct-26																												
A15 VCT and Base	5	05-Oct-26*	09-Oct-26																												
Alternate 1 - Boiler Replacement	80	21-Sep-26	08-Jan-27																												
Remove Existing Boilers & Associated Venting, Piping, and Controls	30	21-Sep-26	30-Oct-26																												
Install New Venting, Piping, and Controls	30	02-Nov-26	11-Dec-26																												
Set New Boilers	5	14-Dec-26	18-Dec-26																												
Boiler Startup	5	28-Dec-26	01-Jan-27																												
Final Architect Commissioning	5	04-Jan-27	08-Jan-27																												

Activity Name			Original Duration	Start	Finish	2026												2027												2028				
						Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	
		Unit C / Unit D		190	29-Jun-26	19-Mar-27	 Unit C / Unit D																											
		Install and Maintain Floor Protection on Existing Floor Finishes to Remain		117	29-Jun-26*	08-Dec-26	 Install and Maintain Floor Protection on Existing Floor Finishes to Remain																											
		Site Demolition		10	06-Jul-26	17-Jul-26	 Site Demolition																											
		Unit C - Foundation Hydronic Piping		15	08-Jul-26*	28-Jul-26	 Unit C - Foundation Hydronic Piping																											
		Remove Ceiling Tile and Grid Assembly/Salvage/Dispose		10	13-Jul-26*	24-Jul-26	 Remove Ceiling Tile and Grid Assembly/Salvage/Dispose																											
		Remove All Hydronic Piping/Insulation/Valves/Hangers		10	20-Jul-26*	31-Jul-26	 Remove All Hydronic Piping/Insulation/Valves/Hangers																											
		Remove Countertops, Metal Grilles and Casework/Salvage Casework		10	27-Jul-26*	07-Aug-26	 Remove Countertops, Metal Grilles and Casework/Salvage Casework																											
		Remove All Mech. Equipment UV's/Ductwork/FT/AHU's		20	03-Aug-26*	28-Aug-26	 Remove All Mech. Equipment UV's/Ductwork/FT/AHU's																											
		Remove Doors/Lockers/Salvage as Noted		5	10-Aug-26*	14-Aug-26	 Remove Doors/Lockers/Salvage as Noted																											
		Remove Wall and Storefront System/Shore/Brace as Required		15	17-Aug-26*	04-Sep-26	 Remove Wall and Storefront System/Shore/Brace as Required																											
		Roof Top Mechanical Equipment/Ductwork/Connections/Linesets		30	31-Aug-26*	09-Oct-26	 Roof Top Mechanical Equipment/Ductwork/Connections/Linesets																											
		Provide New Steel Roof Frames/RTU Supports/Joist Reinforcing		20	07-Sep-26*	02-Oct-26	 Provide New Steel Roof Frames/RTU Supports/Joist Reinforcing																											
		Prepare Existing Opening for New SF Assembly, Blocking/Steel/CMU		10	05-Oct-26*	16-Oct-26	 Prepare Existing Opening for New SF Assembly, Blocking/Steel/CMU																											
		Unit D - Mechanical D3B AHU/Ductwork/OA Duct		15	12-Oct-26	30-Oct-26	 Unit D - Mechanical D3B AHU/Ductwork/OA Duct																											
		Provide New Storefront Assembly		30	19-Oct-26*	27-Nov-26	 Provide New Storefront Assembly																											
		Install New UV's/CUH's/EF's		20	02-Nov-26*	27-Nov-26	 Install New UV's/CUH's/EF's																											
		Unit D - Provide New Aluminum Louvers/Panel/Flashing/Trim & Wall Assembly Patching		20	16-Nov-26	11-Dec-26	 Unit D - Provide New Aluminum Louvers/Panel/Flashing/Trim & Wall Assembly Patching																											
		New Doors/Hardware and Trim		15	30-Nov-26*	18-Dec-26	 New Doors/Hardware and Trim																											
		Provide New Metal Grilles		10	14-Dec-26*	25-Dec-26	 Provide New Metal Grilles																											
		Insulated Spandrel Panels		10	28-Dec-26*	08-Jan-27	 Insulated Spandrel Panels																											
		Final Connections and Trim for New UV's/CUH's/EF's		10	11-Jan-27*	22-Jan-27	 Final Connections and Trim for New UV's/CUH's/EF's																											
		Reinstall Salvaged Casework/Rework as Required		5	25-Jan-27*	29-Jan-27	 Reinstall Salvaged Casework/Rework as Required																											
		Provide New Joint Sealants		5	01-Feb-27*	05-Feb-27	 Provide New Joint Sealants																											
		Install New Panels PPC/PPD		10	08-Feb-27	19-Feb-27	 Install New Panels PPC/PPD																											
		Install New MDP Panel		15	22-Feb-27	12-Mar-27	 Install New MDP Panel																											
		Install Roller Shades		5	15-Mar-27*	19-Mar-27	 Install Roller Shades																											
		Sitework/Sidewalk		35	12-Apr-27	28-May-27	 Sitework/Sidewalk																											
		Site Grading		5	12-Apr-27	16-Apr-27	 Site Grading																											
		Install New Concrete Sidewalk		10	19-Apr-27	30-Apr-27	 Install New Concrete Sidewalk																											
		New Digital Marquee Sign Footing/Foundation/Brick/Cast Stone		10	03-May-27	14-May-27	 New Digital Marquee Sign Footing/Foundation/Brick/Cast Stone																											
New Digital Marquee Sign Aluminum Base Plate and Aluminum Columns		5	10-May-27	14-May-27	 New Digital Marquee Sign Aluminum Base Plate and Aluminum Columns																													
Seeding, and Landscaping		5	17-May-27	21-May-27	 Seeding, and Landscaping																													
New Digital Marquee Sign		10	17-May-27	28-May-27	 New Digital Marquee Sign																													

 Actual Work  Remaining Work  Critical Remaining Work   Milestone  Summary	224010.17 KPS Northglade Montessori Guideline Schedule - 21-January-26 4 of 4	
---	--	---

Kalamazoo Public Schools


NORTHGLADE MONTESSORI SCHOOL



LEGEND:

Temp. Fenced-In

Material Laydown Area =



Temp. Tree Protection =



Skillman Site Trailer =



Contractor Parking Area =



Dumpsters =



Large Project Sign =



Project Traffic and
Contractor Entrance Signage =



Temporary Toilets =



The SKILLMAN Corporation
Construction Management

TowerPinkster
Architecture · Engineering · Interiors

Site Logistics Plan - 1/22/26

Kalamazoo Public Schools

ARCHITECT'S SUPPLEMENTAL INSTRUCTIONS ASI #001

DATE: January 26, 2026

PROJECT: Northglade Montessori School
1914 Cobb Ave

TO: The Skillman Corporation
8120 Moorsbridge Road
Portage, MI 49024

FROM: TowerPinkster
242 E Kalamzoo Ave, STE 100
Kalamazoo, MI 49007

The following information is being issued to supplement the information contained within the Construction Documents. The work shall be carried out in accordance with the following supplemental instructions to the Contract Documents without change in Contract Sum or Contract Time.


DESCRIPTION:

Reference code year for International Fuel Gas Code updated to 2021.

ATTACHMENTS:

G 101 – First Floor Code Compliance Plan






FIRST FLOOR CODE COMPLIANCE PLAN

1/16" = 1'-0"



THIS DRAWING SHEET IS INTENDED TO BE PLOTTED IN COLOR. IF THIS TEXT APPEARS IN BLACK AND WHITE, IT IS PLOTTED INCORRECTLY. DISCARD AND OBTAIN AN ACCURATE DRAWING

CODE COMPLIANCE KEY



FIRE SAFETY SYMBOLS

- XFE EXISTING FIRE EXTINGUISHER
- XFEC EXISTING FIRE EXTINGUISHER CABINET
- FE FIRE EXTINGUISHER
- FEC FIRE EXTINGUISHER CABINET
- AED AUTOMATED EXTERNAL DEFIBRILLATOR (AED)
- KNOX KNOX BOX

FIRE-RATING KEY

COORDINATE ALL REQUIRED DAMPERS WITH MECHANICAL.

DESIGNATION	RATING	PRIORITY
	3 HOUR	1
	2 HOUR FIRE WALL - 706	2
	2 HOUR FIRE PARTITION - 706	2
	2 HOUR FIRE BARRIER - 707	2
	1 HOUR FIRE PARTITION - 706	3
	1 HOUR FIRE BARRIER - 707	3
	SMOKE RESISTANT	4

- ALL PENETRATIONS THROUGH A FIRE OR SMOKE RATED PARTITION SHOULD BE SEALED WITH AN APPROVED U.L. RATED PRODUCT.
 - THE TOPS OF ALL FIRE RATED PARTITIONS SHALL BE SEALED TO THE CONTINUOUS STRUCTURE ABOVE WITH A U.L. RATED SYSTEM OR ASSEMBLY.
 - WOOD BLOCKING IN FIRE-RATED PARTITIONS SHALL BE NON-COMBUSTIBLE TREATED WOOD.
 - REFER TO SPECIFICATION U.L. RATING INFORMATION.
 - FIRE-RATED WALLS ENDING INTO AN ACOUSTICAL DECK MUST HAVE THE FLUTES FILLED, REFER TO 'TOP OF WALL DETAIL AT ACOUSTIC DECK' SHOWN ON THIS SHEET.
- FOR MASONRY WALLS THE MASON SHALL FILL VOIDS AND FIRE SPRAY WITH UL LISTED MATERIAL.
 - FOR STUD WALLS USE FIRE SAFING AND FIRE CAULK.

REFERENCED CODE

BUILDING:	2021 MICHIGAN BUILDING CODE # 2012 NFPA 101 LIFE SAFETY CODE
REHABILITATION:	2021 MICHIGAN REHAB CODE
ENERGY:	2021 MICHIGAN ENERGY CODE
PLUMBING:	2021 MICHIGAN PLUMBING CODE
MECHANICAL:	2021 MICHIGAN MECHANICAL CODE
FUEL GAS:	(IFGC) 2021 INTERNATIONAL FUEL GAS CODE
ELECTRICAL:	2023 MICHIGAN ELECTRICAL CODE, PART 8
BARRIER FREE:	2021 MICHIGAN BUILDING CODE # 2017 ICC # C A117.1
USE GROUP:	E
CONSTRUCTION TYPE:	IIIB
SPRINKLERS:	NO

PROJECT AREA

EXISTING BUILDING AREA	42549 SF
STORAGE ADDITION	533 SF
TOTAL FINISHED PROJECT	43082 SF

ASI #1

01/23/2026

ISSUED FOR

DATE

PROJECT TITLE
NORTHGLADE
MONTESSORI SCHOOL

OWNER
KALAMAZOO PUBLIC
SCHOOLS

Kalamazoo, MI

SHEET TITLE
FIRST FLOOR CODE COMPLIANCE PLAN

DATE
JANUARY 9, 2026

SHEET NUMBER
G 101
23-638.000

TowerPinkster

Architecture · Engineering · Interiors

TOWERPINKSTER.COM

© 2026 ALL RIGHTS RESERVED