

**ADDENDUM  
NO. 3**

**April 9, 2026**

**Edgewood Schools Baseball and Softball Turf  
601 Edgewood Drive  
Ellettsville, IN 47429**

**TO: ALL BIDDERS OF RECORD**

This Addendum forms a part of and modifies the Bidding Requirements, Contract Forms, Contract Conditions, the Specifications and the Drawings dated March 18, 2026, by Lancer Associates Architecture. Acknowledge receipt of the Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of Pages ADD 3-1 and Lancer Associates Architecture Addendum No. 01 which consist of two pages.

**ADDENDUM NO. ONE**

**PROJECT:** Edgewood Schools – Baseball/Softball Turf  
**PROJECT NUMBER:** 26101  
**DATE OF ADDENDUM:** 04-08-2026



**THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND IS ISSUED IN ACCORDANCE WITH THE INSTRUCTIONS TO BIDDERS. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY SIGNING THE ADDENDUM ACKNOWLEDGMENT SECTION OF THE BID FORM.**

**QUESTIONS & ANSWERS:**

**Q:** The pitchers mound turf has two different callouts for backing either 24 oz or 26 oz. Can you please specify which backing is required.

**A:** 26 oz is the requirement for secondary backing weight

**Q:** Also for the pitchers mound turf, there are contracting callouts for turf type. Calling out Slit Film Sharktooth w/ thatch and a DFE w/ thatch. Can you please clarify what is wanted.

**A:** The specified turf for the Pitcher’s Mound and Batter’s Catcher’s Boxes is Sharktooth slit film with a 4,800 denier monofilament thatch. 1.75” pile height and 90 oz face weight

**Q:**Can you clarify if the outfield turf is to include thatch?

**A:** The outfield area does include thatch. 2" DFE at 50oz face weight 24oz coating weight

**Q:** Can you please provide callouts on the items to be demoed on the baseball and softball pages. Such as the items to be removed

**A:** Refer to the Demolition Plans - Sheets L100, L101, L102

**Q:** For the alternates, can you please provide a limit of work where the curbs, fencing, etc. is to start and finish.

**A:**

Add Alt #1: Concrete bleacher pad, fence removal (see L101), new fencing, Edgewood Drive to bull pen, and all associated grading and landscape restoration.

Add Alt #2: Entirety of concrete walkway, ramp, stairs, speed table and all associated grading and landscape restoration from Edgewood Drive to Junior High entrance.

**ADDITIONAL APPROVED MANUFACTURERS:**

- 1. Section 32 18 14 Synthetic Turf
  - a. Astroturf
  - b. Shaw/Motz
- 2. Section 32 33 00 2.6 Foul Poles
  - a. USS

**Attachments:**

None

END OF ADDENDUM NO. ONE